

D1 EGRESS PLAN – FIRST FLOOR

1/8"=1'-0"

0 4' 8' 16'

EXIT SEPARATION IN SALES:
REQ'D 55'-11" (1/3 X 167'-10")
PROVIDED 71'-0"

NOTE: SPACE IS FULLY SPRINKLERED

OCCUPANT LOAD	SF		LOAD FACTOR		OCC
FIRST FLOOR:					
SALES FLOOR AREA: (OCCUPANT LOAD FACTOR PER TABLE 1004.1.1)	6,341	/	30	=	212
STOCKROOM / MISC AREA: (OCCUPANT LOAD FACTOR PER TABLE 1004.1.1)	998	/	300	=	4
MANAGER'S OFFICE: (OCCUPANT LOAD FACTOR PER TABLE 1004.1.1)	76	/	100	=	1
TOTAL FIRST FLOOR:	7,339				216
BASEMENT: STOCKROOM / MISC AREA: (OCCUPANT LOAD FACTOR PER TABLE 1004.1.1)	2,869	/	300	=	10
TOTAL BASEMENT:	2,869				10
TOTAL:	10,208				226
REQUIRED RESTROOMS PER OCCUPANCY					1 PER SEX
PROVIDED RESTROOMS					1 PER SEX

EXITING	Required:	Provided:
NUMBER OF EXITS:		
FIRST FLOOR	2	2
Exit width	43.2"	171"
BASEMENT	2	2
Exit width	2"	66"
TRAVEL DISTANCE	**Required:**	**Provided:**
MAX TRAVEL DISTANCE:	250 FT MAX	160'-3" FT MAX



A1 EGRESS PLAN – BASEMENT FLOOR

1/8"=1'-0"

0 4' 8' 16'

EXIT SEPARATION IN STOCK:
REQ'D 28'-4" (1/3 X 140'-0")
PROVIDED 45'-6"

NOTE: SPACE IS FULLY SPRINKLERED

OWNER:
WILLIAMS-SONOMA, INC.
3250 Van Ness Avenue
San Francisco, CA 94
T 415 616 8602
F 415 439 8164
www.williams-sonomair

Reviewed for Code Compliance
Jurisdiction: City of Portland
Application Number:
Date: 04/26/17

LICENSED ARCHITECT
TODD K. SENOKI
STATE OF MAINE

CALLISONRTKL™
A DESIGN CONSULTANCY OF ARCADIS
CALLISONRTKL, INC.
www.callisonrtkl.com

west elm
Dowtown Portland
164 Middle Street
Portland, ME 04101
PROJECT #006-160335.00

ISSUED / REVISED	DATE
PRELIMINARY SET	09/08/16
LL COORDINATION SET	11/08/16
LL/PERMIT SET	11/21/16

EGRESS PLANS

A-000.2

COPYRIGHT © 2016 CallisonRTKL Inc.