INTERIOR FINISH SCHEDULE

SPACE	FLOOR	BASE	WALL	CEILING	REMARKS
SALES AREA	CF-1	WB-1	WE1-ES, WE1-SG, WE2-ES, WE6	WE3-ES	WE1-SG ON ALL TRIMS AND DOORS; WE3-ES ON OTS CEILINGS; WE2-ES ON ALL PILASTERS ALONG STOREFRONT GLAZING; WE1-ES ON ALL EXPOSED CONCRETE COLUMNS
CASHWRAP	CF-1	WB-1	WE1-ES	WE3-ES	WE3-ES ON OTS CEILINGS
LOFT	WF-2	WB-1	WE1-ES	LC-1	WE1-ES ON WALLS AND SOFFIT
STOCK ROOMS	CF-2	RB-1	WESR	OTS	WE1-SG ON ALL TRIMS AND DOORS; CF-2 AT ALL FLOORS AND ARDEX RAMPS
TOILET ROOM VESTIBULE	CF-1	WB-1	WE1-ES	WE1-ES	WE1-SG ON ALL TRIMS AND DOORS
WOMEN'S TOILET	T-4	T-2	WE1-SG, T-1	WE1-SG	REFER TO DETAIL A5/A-805 FOR EXTENT OF WALL FINISHES
MEN'S TOILET	T-4	T-2	WE1-SG, T-1	WE1-SG	REFER TO DETAIL A5/A-805 FOR EXTENT OF WALL FINISHES
MANAGER'S OFFICE	CPT-1	RB-1	WE1-ES	WE1-ES	WE1-SG ON ALL TRIMS AND DOORS
EMPLOYEE BREAK AREA	CF-2	RB-1	WE5-ES	---	WE-5 WHERE NOTED ON A-112
ENTRY NO 1 & 2	CPT-2	---	---	OTS	

SUBMITTAL SCHEDULE

Status (drop down menu)	Item	Specification	Required Approvals: GC	Engineer	Architect	WSI
Physical Samples		**Simultaneously send 3 copies to WSI + 1 copy to Architect**				
Storefront						
	Storefront System Finish	Metal sample with actual finish applied	X	X	X	X
	Exterior Metal Panel	Sample with actual finish applied	X		X	X
	Exposed Flashings or Copings	Metal sample with actual finish applied	X		X	X
Finishes						
	Interior Paint	Brushout of each color and sheen specified	X		X	X
	Toilet Room Tile	Samples of each color and type	X		X	X
	Grout for Toilet Room Tile	Standard color chart with specified color indicated	X		X	X
Shop Drawings and Specifications		**Email to Architect**				
Storefront						
	Exterior Metal Panels	Including elevations, details and specifications	X		X	X
MEP						
	Air Diffusers / Grilles		X	X	X	
	HVAC Equipment		X	X	X	
	HVAC Ductwork		X	X	X	
	HVAC Controls		X	X	X	
	Plumbing Fixtures		X	X	X	
	Electrical Switchgear		X	X	X	
	Light Fixtures		X	X	X	
	Lighting Contactors		X	X	X	
	B-Line System	Cut sheets on Materials and Connections	X	X	X	
	Sprinkler Shop Drawings		X	X	X	
	Fire Alarm Shop Drawings		X	X	X	
Finishes						
	GC-provided Trim		X		X	X
Metal Fabrications						
	Door Hardware Schedule		X		X	
Miscellaneous						
	Toilet Room Accessories	Cut sheets for all accessories	X		X	X
	Stockroom Shelving	Reviewed by Architect and WSI first then copied to GC when approved	X		X	X
	Signage	Reviewed by Architect and WSI first then copied to GC when approved	X		X	X
Mockups		**Coordinate with PM**				

All submittals are to be clearly marked to include the Project Name, General Contractor Name and Subcontractor Information. Samples are to be clearly labelled to reference the material callout from the Finish Schedule or to the applicable specification section.

INTERIOR FINISH AND MATERIALS LEGEND

ITEM	CODE	MATERIAL	MANUFACTURER	TYPE	REMARKS
WALL	WE1-ES	PAINT	SHERWIN WILLIAMS	WE-1, EGGSHELL, PROMAR 200 - ZERO VOC	SOFFITS, GWB CEILING, INTERIOR WALLS, MGR'S OFFICE
	WE1-SG	PAINT	SHERWIN WILLIAMS	WE-1, SEMI-GLOSS, PROMAR 200 - ZERO VOC	DOORS AND TRIM, FEATURE WALLS, TOILET ROOMS
	WE2-ES	PAINT	SHERWIN WILLIAMS	WE-2, EGGSHELL, PROMAR 200 - ZERO VOC	WALLS AT STOREFRONT
	WE3-ES	PAINT	SHERWIN WILLIAMS	WE-3, EGGSHELL, WATERBORNE ACRYLIC DRYFALL	CEILINGS AT OPEN-TO-STRUCTURE AREAS ON SALES FLOOR, DUCTS, AND SUPPORT ROD AT LIGHT TRACK UNISTRUT
	WE4	PAINT	SHERWIN WILLIAMS	WE-4, PROMAR 200 - ZERO VOC	WOOD BASE ONLY AT SALES FLOOR
	~~WE5C~~	~~PAINT~~	~~SHERWIN WILLIAMS~~	~~WE5C, PREMIUM EXTERIOR GRADE PAINT~~	~~BARRICADE~~
	WESR	FIRE TAPE AND PRIMED	BY GC		STOCKROOMS
	WE5	PAINT	BENJAMIN MOORE	CHALKBOARD PAINT 307, EGGSHELL	EMPLOYEE BREAK AREA - SEE PLANS FOR EXTENT
	WE6	PAINT	MODERN MASTERS	METALLIC PAINT COLLECTION - CUSTOM COLOR, SEE REMARKS	PER 1 GALLON: 71 OUNCES ENGLISH BROWN; 51 OUNCES STEEL GRAY; 6 OUNCES VENETIAN BLUE. EXPOSED STRUCTURAL COLUMNS AT SALES AREA
	~~WE7 EXT~~	~~PAINT~~	~~SHERWIN WILLIAMS~~	~~WE 7, EXTERIOR~~	~~BARRICADE~~
	~~WE8~~	~~PAINT~~	~~MODERN MASTERS~~	~~METALLIC PAINT COLLECTION - CUSTOM COLOR, MATCHES ACT STEEL CHARCOAL METALLIC, SEE REMARKS APPLY TOPCOAT OF MASTERCLEAR - SEMI-GLOSS~~	~~PER 1 GALLON: 32 OUNCES ENGLISH BROWN; 96 OUNCES STEEL GRAY EXPOSED STRUCTURAL STEEL AT EXTERIOR~~
	~~WE9~~	~~PAINT~~	~~SHERWIN WILLIAMS~~	~~WE 9 EGGSHELL, PREMIUM EXTERIOR GRADE PAINT~~	~~ALL EXPOSED STEEL MEMBERS OF CANOPY & STOREFRONT SYSTEM - DO NOT PAINT METAL DECK~~
FLOORING	~~WF-1C~~	~~WOOD FLOORING~~	~~VINTAGE LUMBER~~	~~RUSTIC WHITE OAK~~	~~SIZE: RANDOM WIDTHS 3"-6", RANDOM LENGTHS 2'-10', END MATCH BLIND NAIL TO PLYWOOD SUBFLOORING. FINISH: 1 COAT SEALER - BONAKEMI BONASEAL, 3 COATS FINISH - BONAKEMI BONATECH TRAFFIC, SATIN FINISH. CULL ALL SOLID BLONDE BOARDS. FILL HOLES 3/8" AND LARGER WITH NATURAL WOOD FILLER, PRIOR TO FINAL COAT OR FINISH. CONTACT ALEX @ VINTAGE LUMBER 301-845-2500 FOR WOOD FLOORING.~~
	WF-2	WOOD FLOORING	PROVENANCE	3/4" TONGUE AND GROOVE WOOD FLOORING	SIZE: RANDOM WIDTHS 3"-6", RANDOM LENGTHS 2'-10', END MATCH BLIND NAIL TO PLYWOOD SUBFLOORING. FINISH: TBD CULL ALL SOLID BLONDE BOARDS. FILL HOLES 3/8" AND LARGER WITH NATURAL WOOD FILLER, PRIOR TO FINAL COAT OR FINISH. CONTACT ALEX @ VINTAGE LUMBER 301-845-2500 FOR WOOD FLOORING.
	~~VCT-1~~	~~VINYL COMPOSITION TILE~~	~~TARKETT~~	~~EXPRESSIONS #1318~~	~~SIZE: 12" X 12" X 1/8", INSTALLATION: PER MANUFACTURER'S RECOMMENDATIONS~~
	CPT-1	CARPET	SHAW CONTRACT	PETO II, #71525, "SLATE"	ASTM E84 FLAME SPREAD 75 OR LESS. ASTM E662 SMOKE DENSITY RATING 450 OR LESS IN FLAMING MODE
	CPT-2	ENTRY MAT	PAWLING	TAN	COCOMAT MODEL: EM-301 3/4" THICK, CONTACT: SUSAN LINDSAY 650-324-1133
	~~MT-1~~	~~WALL FLOORING~~	~~---~~	~~---~~	~~COORDINATE MATERIAL WITH THE LANDLORD~~
	ST-1	STONE FLOORING	ASSOCIATED IMPORTS	CINZA, SLATE CLEFT	FINISH SIZE: 24"x24" GROUT: HYDROMENT "NATURAL" H 146 STANDARD, 3/16" GROUT JOINTS. SEALER: "511-H20" BY MIRACLE SEALANTS, CONTACT: GEOFF MILSPAW 404-756-1104 (LOFT AREA)
	~~SV-1~~	~~SHEET VINYL FLOORING~~	~~MANNINGTON COMMERCIAL~~	~~RELAY, #22016, "DEEP WEDGEWOOD"~~	
	CF-1	CLEAR SEALER ON CONCRETE	DIVERSEY, INC	JONCRETE "MATTE CONCRETE SEALER"	CLEAR SEALER ON EXISTING CONCRETE @ SALES AREA ALL ISOLATION JOINTS TO BE CAULKED WITH TYPE PT JOINT SEALER - DO NOT FILL CONTROL JOINTS, SEE SPECS, COLOR TO MATCH EXISTING CONCRETE SLAB
	CF-2	CLEAR SEALER ON CONCRETE	H&C	HYDRO DEFEND CONCRETE AND MASONRY WATERPROOFING SEALER	CLEAR SEALER ON EXISTING CONCRETE
CEILING	LC-1	RECLAIMED WOOD	PROVENANCE	RECLAIMED WOOD	OWNER-FURNISHED, GC INSTALLED, DO NOT PAINT
TILE	T-1	WALL TILE	DALTILE	4 1/4 x 4 1/4" FIELD TILE - SEMI GLOSS, COLOR: ICE GREY K176	CONTACT: TAMARA GRANDUSKY 415-290-8302 GROUT: LATICRETE 89 SMOKE GREY, SANDED, 1/8" GROUT JOINT, SEALANT: COLOR TO MATCH GROUT
	T-2	COVE BASE TILE	DALTILE	4 1/4 x 4 1/4" COVE TILE (A-3401); COVE BASE CORNERS (SCRL-3401) SEMI-GLOSS - COLOR: ICE GREY K176	CONTACT: TAMARA GRANDUSKY 415-290-8302 GROUT: LATICRETE 89 SMOKE GREY, SANDED, 1/8" GROUT JOINT, SEALANT: COLOR TO MATCH GROUT
	~~T-3~~	~~BULLNOSE TILE~~	~~DALTILE~~	~~4 1/4 x 4 1/4" BULLNOSE TILE (S-4449); BULLNOSE CORNER TILE (ACRL-4402) SEMI-GLOSS - COLOR: ICE GREY K176~~	~~CONTACT: TAMARA GRANDUSKY 415-290-8302 GROUT: LATICRETE 89 SMOKE GREY, SANDED, 1/8" GROUT JOINT, SEALANT: COLOR TO MATCH GROUT~~
	T-4	FLOOR TILE	DALTILE	2" X 2" MOSAIC TILE - KEYSTONES - COLOR: BLACK D311	CONTACT: TAMARA GRANDUSKY 415-290-8302 GROUT: LATICRETE 45 RAVEN, SANDED, SEALANT: COLOR TO MATCH GROUT
	~~T-8~~	~~COFFEE BAR FLOOR TILE~~	~~DALTILE~~	~~12" X 24" PORCELAIN TILE - COLOR: ASHGREY P405, TEXTURED~~	~~AT COFFEE BAR GROUT: HYDROMENT EPOXY MODIFIED, "NATURAL", 1/8" GROUT JOINTS.~~
	~~T-9~~	~~COFFEE BAR WALL TILE~~		~~TBD~~	~~AT COFFEE BAR GROUT: TBD 1/8" GROUT JOINTS.~~
	~~T-10~~	~~ENTRY FLOOR TILE~~	~~DALTILE~~	~~KEYSGRANITE - BLACK ABSOLUTE, HONED - G771~~	~~STOREFRONT ENTRY FLOOR - 18"X18" TILE, CUT TO DIMENSIONS PER DWGS, SEE A-210 GROUT: HYDROMENT "CHAR BLACK" H 135 STANDARD, 1/8" GROUT JOINTS. SEALER: "511-H20" BY MIRACLE SEALANTS~~
BASE	RB-1	COVED VINYL BASE	BURKE FLOORING	#701, "BLACK"	
	SB-1	STONE BASE	DALTILE	KEYSGRANITE - BLACK ABSOLUTE, HONED - G771	STOREFRONT - 3/8" THICK TILES
	WB-1	WOOD BASE	BY GC	2" TALL WOOD BASE X 1/2" - PAINTED WE4	SALES FLOOR - PAINTED BY GC ON SITE. SEE C1/A-803.
WAINSCOT	WC-2	FRP WAINSCOT	MARLITE	P-100 WHITE - CLASS "A"	WAINSCOT AT MOP SINK - TO +48" AFF
WINDOW SCREENING FILM	WF-1	TRANSLUCENT SCREENING FILM	3M	"MILKY MILKY" - SH2MAMM	SCREENING FILM TO BE PROVIDED BY AND INSTALLED BY GC
	~~WF-2~~	~~TRANSLUCENT SCREENING FILM~~	~~3M~~	~~DIFFUSER FILM, 60% LIGHT TRANSMISSION, 3635-70 WHITE~~	~~SCREENING FILM TO BE PROVIDED BY AND INSTALLED BY SIGNAGE VENDOR~~
AWNING FABRIC	~~AF-1~~	~~AWNING FABRIC~~	~~SUNBRELLA~~	~~BLACK~~	~~TREAT WITH SPRAY ON FIREPROOFING~~
STOREFRONT	~~SF-1~~	~~ALUMINUM STOREFRONT~~	~~TUBELITE~~	~~TUBELIGHT, CLEAR ANNODIZED~~	~~14000 SERIES, LOW-RISE, CENTER SET GLASS, INSIDE/OUTSIDE GLAZED~~
	~~SF-2~~	~~STOREFRONT FINISH~~	~~OLDCASTLE~~	~~OLDCASTLE: P242 METALLIC CHARCOAL~~	~~SYSTEM: FG610T, 2 1/2" X 5", HURRICANE RESISTANT, THERMALLY BROKEN FRAME~~
	~~SF-3~~	~~ALUMINUM STOREFRONT~~	~~MATCH EXISTING~~	~~COORDINATE WITH LANDLORD FOR SPECIFICATIONS TO MATCH EXISTING~~	~~PAINT TO MATCH EXISTING~~
GLAZING	~~GL-1~~	~~TEMPERED~~		~~CLEAR GLASS~~	~~1/4" THICK GLASS, TEMPERED~~
	~~GL-2~~	~~INSULATED GLASS~~		~~CLEAR GLASS WITH SOLARBAN 67 LOW-E COATING~~	~~1" DOUBLE PANE GLASS COMPOSED OF 1/4" GLASS W/ 1/2" AIR SPACE AND LOW "E" COATING, TEMPERED WHERE INDICATED ON DWGS, U-VALUE: .29 (WINTER NIGHT), .27 (SUMMER DAY); SHGC: .29~~
METAL	M-1	~~METAL RAILING/~~ CORNER GUARD/ METAL SILL	~~BY GC~~ FOIO (BY 3D)	HOT ROLL STEEL WITH A CLEAR SATIN LACQUER SPRAY FINISH (DEFT). AREAS THAT ARE LIGHT CAN BE GUN BLUED WITH PATINA PROCESS AND THEN A SATIN CLEAR LACQUER.	DO NOT PAINT SEALED RAW STEEL FINISH TO MATCH OWNER'S APPROVED SAMPLE
BRAKE METAL	~~BRKM-1~~	~~BRAKE METAL CLADDING~~	~~BY GC~~	~~ALUMINUM: COLOR TO MATCH SF-3~~	
EXTERIOR FINISH SYSTEM	~~EFS-1~~	~~EXTERIOR FINISH COATING~~	~~STO~~	~~STOCOAT ACRYLIC EIFS FINISH, COLOR: TO MATCH BM "FAIRVIEW TAUPE", HC-85~~	~~SEE SPECIFICATION FOR MORE INFORMATION~~
THRESHOLD	TH-1	THRESHOLD	BY GC	CHROMA ENGINEERED STONE, "STORMY SKY", BS250 - HONED FINISH	
EXTERIOR WOOD SLATS	~~WS-1~~	~~RECLAIMED WOOD SLATS~~	~~PROVENANCE~~	~~RECLAIMED WOOD - TBD~~	~~7" X 3/4" BOARDS - TO BE CONFIRMED~~
BRICK VENEER	~~BV-1~~	~~BRICK VENEER~~	~~MATCH EXISTING~~	~~MATCH EXISTING SHELL BUILDING~~	~~3 5/8" X 2 1/4" X 7 5/8" - TO BE CONFIRMED~~
MASONRY UNIT	~~MU-1~~	~~MASONRY UNIT~~	~~MATCH EXISTING~~	~~MATCH EXISTING SHELL BUILDING~~	~~3 5/8" X 7 5/8" X 23 5/8"~~

OWNER:
WILLIAMS-SONOMA, INC.
3250 Van Ness Avenue
San Francisco, CA 94
T 415 616 8602
F 415 439 8164
www.williams-sonomainc

Reviewed for Code Compliance
Accessibility Division
Approved as Noted
Date: 04/26/17

LICENSED ARCHITECT TODD K. TENOKI 3-4417 STATE OF MAINE

CALLISONRTKL™
A DESIGN CONSULTANCY OF ARCADIS
CALLISONRTKL, INC.
www.callisonrtkl.com

west elm
Downtown Portland
164 Middle Street
Portland, ME 04101
PROJECT #006-160335.00

ISSUED / REVISED	DATE
PRELIMINARY SET	09/08/16
LL COORDINATION SET	11/08/16
LL/PERMIT SET	11/21/16

FINISH SCHEDULE, FINISH & MATERIAL LEGEND

A-002

COPYRIGHT © 2016 CallisonRTKL Inc.