FINISH SCHEDULE

ABBREVIATIONS

CPT	CARPET	N	NORTH	VB	VINYL BASE	EXT.	EXTERIOR
CLG	CEILING	NO	NUMBER	VCB	VINYL COVE BASE		
CT	CEILING TILE	P	PAINT	VCT	VINYL COMPOSITION TILE		
E	EAST	PL	PLASTIC LAMINATE	VSB	VINYL STRAIGHT BASE		
FRP	FIBERGLASS REINFORCE PANEL	S	SOUTH	W	WEST		
GWB	GYPSUM WALL BOARD	SAT	SUSPENDED ACOUSTICAL TILE	WC	WALLCOVERING		
HT	HEIGHT	SV	SHEET VINYL	HWD	HARDWOOD FLOORING		
MAT'L	MATERIAL	T	TILE	D	DECKING		

NO.	NAME	WALLS				FLOOR				CLG 'A'		CLG 'B'		CLG./FL. ASSEMBLY	REMARKS
		N	E	S	W	MAT'L	BASE	MAT'L	BASE	TYPE	HT.	TYPE	HT.		
301	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
301.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
302	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
302.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
303	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-8 1/4"	1/A-1.6	
303.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
304	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-8 1/4"	1/A-1.6	
304.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
305	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
305.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
306	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
306.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
307	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
307.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
308	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
308.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
309	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-8 1/4"	1/A-1.6	
309.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
310	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-8 1/4"	1/A-1.6	
310.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
311	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
311.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
312	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
312.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
318	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
318.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
319	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
319.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
320	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-8 1/4"	1/A-1.6	
320.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
321	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-8 1/4"	1/A-1.6	
321.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
322	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
322.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
323	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
323.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
324	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
324.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
325	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
325.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
326	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-8 1/4"	1/A-1.6	
326.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
327	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-8 1/4"	1/A-1.6	
327.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
328	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
328.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
329	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	-	-	CONC.	8'-0"	G.W.B.	7'-9 3/4"	1.1/A-1.6	
329.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #2 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
401	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
401.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	7'-4"	-	-	N/A	NEW S.A.T. CL'G - WC1 @ EXTERIOR OF BATH WALLS
401.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
402	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
402.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	7'-4"	-	-	N/A	NEW S.A.T. CL'G - WC1 @ EXTERIOR OF BATH WALLS
402.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
403	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
403.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
403.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
404	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
404.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
404.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
405	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
405.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
405.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
406	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
406.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
406.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
407	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
407.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
407.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
408	HOTEL ROOM	P1	P1	WC1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
408.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
408.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
410	HOTEL ROOM	P1	P1	WC1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
410.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
410.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
411	HOTEL ROOM	P1	WC1	WC1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
411.1	BEDROOM	P1	P1	P1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
411.2	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	7'-4"	-	-	N/A	NEW S.A.T. CL'G - WC1 @ EXTERIOR OF BATH WALLS
411.3	KITCHENETTE	P1	P1	P1	P1	T 3	N/A	-	-	G.W.B.	7'-9"	-	-	-	SEE PLAN FOR TILE AREA
411.4	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
419	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
419.1	KITCHENETTE	P1	P1	P1	P1	T 3	N/A	-	-	G.W.B.	7'-9"	-	-	-	SEE PLAN FOR TILE AREA
419.2	BEDROOM	P1	P1	P1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
419.3	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	7'-4"	-	-	N/A	NEW S.A.T. CL'G - WC1 @ EXTERIOR OF BATH WALLS
419.4	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
420	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
420.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	7'-4"	-	-	N/A	NEW S.A.T. CL'G - WC1 @ EXTERIOR OF BATH WALLS
420.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
421	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
421.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	7'-4"	-	-	N/A	NEW S.A.T. CL'G - WC1 @ EXTERIOR OF BATH WALLS
421.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
422	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
422.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
422.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
423	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
423.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
423.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
424	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
424.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
424.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
425	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
425.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
425.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
426	HOTEL ROOM	WC1	P1	P1	WC1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
426.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
426.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
427	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
427.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
427.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-
429	HOTEL ROOM	WC1	WC1	P1	P1	CPT1	WB1	HWD1	WB1	G.W.B.	7'-9"	G.W.B.	8'-0"	2/A-1.6	-
429.1	BATH	P2	P2	P2	P2	T 1	TB1	-	-	S.A.T. 1	+/- 7'-4"	-	-	N/A	SEE BID ALTERNATE #3 (WC1 @ EXTERIOR OF BATH WALLS BASE BID)
429.2	DECK	N/A	N/A	N/A	N/A	DECK 1	N/A	-	-	-	-	-	-	-	-

KEY TO FINISHES

PAINTS: BENJAMIN MOORE PAINTS

(1) PRIME COAT & (2) FINISH TOP COATS

P1: COLOR T.B.D.
P2: COLOR T.B.D.
P3: COLOR T.B.D.
P4: COLOR T.B.D.

WALLCOVERING:

WC1: MATERIAL BY OWNER - G.C. TO INSTALL
WC2: MATERIAL BY OWNER - G.C. TO INSTALL (SEE BID ALTERNATE #2 & #3)

CARPET:

CPT1: MATERIAL BY OWNER - G.C. TO INSTALL

HARDWOOD FLOORING:

HWD1: PRE-ENGINEERED HARDWOOD FLOORING - 5/16" MIN. HWOOD THICKNESS
- SAPELE - CLEAR SEAL FINISH - 3 1/2" WIDTH
- WOOD TRANSITION STRIP AS SHOWN BELOW, MATERAIL TO MATCH

TILE:

T 1: WHITE CARRARA TILE - 24"x24"
T 2: WHITE CARRARA TILE - 12"x12"
(INSTALL WITHIN SHOWER ENCLOUSER ONLY, SEE BID ALTERNATES #2 & #3)

SUSPENDED ACOUSTICAL TILES

S.A.T. 1: ARMSTRONG ACOUSTICAL TIN TILE CEILING #1240

DECKING:

DECK 1: MATS INC. - OUTDOOR/ ROOFTOP PAVER - 1 1/2"x24"x24" INTERLOCKING TILE BLACK FINISH, SMOOTH TOP DESIGN

BASE:

WB1: WOOD BASE - 1x6 BASE MOLD (P1)
TB1: TILE BASE - RADIUS TILE COVE BASE, CARRARA TILE

LIGHTING:

LIGHTING @ NEW GUEST ROOMS & BATHROOMS SHALL BE PROVIDED BY OWNER, INSTALLED BY G.C. (SEE SPECS. FOR INTERIOR LIGHTING NOTES)

CONSTRUCTION SET: OCTOBER 31, 2011

LICENSED ARCHITECT MARK L. MUELLER No. 2737 STATE OF MAINE

MARK MUELLER ARCHITECTS A.I.A.
100 Commercial Street
Suite 205
Portland, Maine 04101
Phone/Fax 207.774.9057
Email:
rfi@muellerarchitects.com

© COPYRIGHT 2011
MARK MUELLER ARCHITECTS

RENOVATION & ADDITION:
PORTLAND REGENCY
DORMER ADDITION
20 MILK STREET - PORTLAND, MAINE

INTERIOR SCHEDULE

REVISIONS
DATE
02.24.2011
PROJECT
13 D.E. PROM
DRAWN BY
MRP
CHECK BY
MLM

I-1.0