



FAN DIMENSIONAL DATA								CURB SIZE		FILTER SIZES
MODEL	A	B	C	D	E	F	G	H	I	
ARS-18	42"	42"	43"	30"	18 7/8"	21 7/8"	18"	41"	41"	(4) 20"x25"x1"

**STANDARD FEATURES:** Heavy Gauge Housing • Easily Removable Cover • Corrosion Resistant Fasteners • Constructed of Galvanized Steel (Painting not Required) • Double Inlet Supply Blower, Belt Driven, Mounted on Vibration Isolators • Cast Iron Motor and Fan Drives • Factory Mounted Disconnect Switch • Permanently Lubricated Bearings • Cleanable Aluminum Mesh Filters • ETL Listed

FAN 2

For Hood: 1 SECTIONS: 1 & 2

QUAN	MODEL	CFMS	S.P.	H.P.	VOLTAGE	PHASE	AMPS	WEIGHT
1	ARS-18	6316	.375	2	230	1	12.00	370

**OPTIONS**

41X41X12 Sloped Roof Curb Need Slope