

M.T.L.

RENOVATIONS

Design Build Remodel Repair

Michael J. Lionetta (207) 332-1987

Job Location: Restaurant "Spread" 100 Commercial Street, Portland, Maine

Job Description: Fabricate sign and install

Sign bracket to be made from 5/8" round steel stock with 1/4" plate steel wall bracket with 4 mounting holes to accommodate 5/16" lag bolts wall bracket measuring 5"x20" all painted black.

Manufactured by "Rustin Puffin Metalwork's" of Portland.

Bracket to be installed to granite header centered above front entry way.

Mounting hardware to consist of Long Lead Lag Shield with 5/16" x 3" galvanized lag screws and washers.

Sign to be constructed of 3/4" plywood with metal edge banding and vinyl graphics

Sign to hang with 3/8" galvanized chain and bolts with screw shackle thru hold in sign set at approx. 30 degree angle to set taught

Clearance from bottom of sign to sidewalk to be 9'1".