

FRAMING PLAN SYMBOLS KEY

▫	WOOD POST
(X)	NUMBER OF STUDS IN POST BELOW
A	COLUMN ABOVE THIS LEVEL
C	COLUMN CONTINUOUS THROUGH THIS LEVEL
◄	TRUSS OR JOIST BEARING
▶	FLUSH FRAMED JOIST BEARING WITH HANGER
	INDICATES OVER FRAMING, SEE PLAN
	STUD BEARING WALL BELOW
	SHEAR WALL
"X"T	N UMBER OF TRIM STUDS UNDER HEADER
"X"K	NUMBER OF KING STUDS ADJACENT TO HEADER

FRAMING PLAN SYMBOLS KEY

▫	WOOD POST
(X)	NUMBER OF STUDS IN POST BELOW
A	COLUMN ABOVE THIS LEVEL
C	COLUMN CONTINUOUS THROUGH THIS LEVEL
◄	TRUSS OR JOIST BEARING
▶	FLUSH FRAMED JOIST BEARING WITH HANGER
	INDICATES OVER FRAMING, SEE PLAN
	STUD BEARING WALL BELOW
	SHEAR WALL
"X"T	NUMBER OF TRIM STUDS UNDER HEADER
"X"K	NUMBER OF KING STUDS ADJACENT TO HEADER

NEW MEZZ ROOF FRAMING PLAN

SCALE 1/4"=1'-0"

NOTES:

1. SEE SHEET S1.0 FOR GENERAL STRUCTURAL NOTES
2. ROOF SHEATHING SHALL BE 1/2" PLYWOOD, SEE GENERAL NOTES FOR ADDITIONAL INFO.
3. PROVIDE LIGHT GAUGE BLOCKING BETWEEN LIGHT GAUGE JOISTS WHERE BEARING ON STRUCTURAL STEEL -TYP.

1
REV. 07-26-13

STATE OF MAINE
AARON C. JONES
No. 10968
LICENSED
PROFESSIONAL ENGINEER
Date: 05/28/14
6/5/13

Prepared For:

Consultant:
Structural Integrity Consulting Engineers
77 Oak Street
Portland, ME, 04101
p. 207-774-4684
f. 866-793-7835
www.structuralintegr.com
BUILD WITH CONFIDENCE
© 2011 Aaron C. Jones, PE
SI# 13-0052

Architect:
ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
MAINE WHARF OFFICE RENOVATION BUILDING B
68 COMMERCIAL ST. PORTLAND, MAINE

Revisions:
1. 07-26-13

Scale: 1/4" = 1'-0"

Date: 06-05-13

NEW MEZZ ROOF FRAMING PLAN

S1.5