

1 | BUILDING SECTION

1/4" = 1'-0"

5" 4" 3" 2" 1" 0 5' 10'



2 | WINDOW DETAIL

6" = 1'-0"

3" 2" 1" 0 3" = 1'-0" 1'



F-1 FLOOR SYSTEM

1. **Concrete**
2. **Deck --** Metal deck.
3. **Joists --** Existing bar joists, spaced a max of 5 ft. OC.

3 | FLOOR/CEILING ASSEMBLY

1 1/2" = 1'-0"

6" 4" 2" 0 1' 2'



RC1 Roof Assembly

1. EPDM
2. Densdeck
3. 3" Poly-iso rigid insulation
4. Relocated existing decking or new metal decking - see structural
5. Relocated and sloped roof joists

4 | ROOF ASSEMBLY

1 1/2" = 1'-0"

6" 4" 2" 0 1' 2'



W-1 EXTERIOR WALL - FROM 4'-0" ABOVE FIRST FLOOR FINISHED FLOOR

1. **Siding --** Metal panel and mounting system.
2. 2" Poly - Iso -- Rigid Insulation
3. **Sheathing --** ½" Densglass
4. **Studs --** 6" Galv. steel studs at 16" OC.
5. **Gypsum Board --** 5/8 in. thick, 4 ft wide Type X "Sheetrock" brand wallboard.



W-2 EXTERIOR WALL - TO 4'-0" ABOVE FIRST FLOOR FINISHED FLOOR(FLOOD PROOF)

1. **Siding --** Metal panel and mounting system.
2. 2" Poly - Iso -- Rigid Insulation
3. Sheathing -- ½" Durock
4. **Studs --** 6" Galv. steel studs at 16" OC.
5. Interior Finish -- 1/2 in. thick, Exterior Grade plywood

5 | WALL TYPES

1 1/2" = 1'-0"

6" 4" 2" 0 1' 2'

REGISTERED ARCHITECT
WILLIAM KENNETH HOPKINS
No. 1050
STATE OF MAINE

Prepared For:
MAINE WHARF LLC
72 COMMERCIAL STREET
PORTLAND, ME 04101

Consulting Engineer:

Architect:
ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
MAINE WHARF
68 COMMERCIAL STREET
PORTLAND, MAINE

Revisions:
PHASE 3 PERMIT AND CONST. 12/13/13

Scale: AS INDICATED

Date: 13 Dec 2013

PHASE 3 SECTIONS

A3.02