



13oz Scrim Vinyl Banner

Product Description

Duratex 13oz Scrim Banner is a lightweight substrate compatible with most super wide format digital printers. The topcoat is formulated to achieve consistent image quality with optimal color reproduction. Available in gloss and matte finishes.

Physical Properties

Caliper: 13 mil **Denier:** 1000x1000 **Weight:** 13oz/yd² **Flame Resistance:** NFPA 701
Outdoor Life: Up to 3 Years **Shelf Life:** 1 year

Features/Benefits

Polyester Scrim/Outdoor Strength Easy Finish/Grommet, Sewed & Hem Stitch Capable
Quick Drying/Abrasion Resistance Water Resistant/Anti-Smudge
Outdoor Durability/Lamination Not Required

Applications Product

Indoor Signage Building Signs Front-lit Signage
Outdoor Signage Trade Show Displays Outdoor Displays

Storage & Handling Conditions

To maintain a shelf life of 1 year, store material at a temperature of 72° F with a relative humidity of 50%. Allow material to stabilize to room/printing conditions for 24 hours prior to use.

Installing – This product can be grommeted for short-term indoor banner applications. Metal grommets should be inserted to penetrate 2-4 layers of materials for increased strength and durability. Standard high tack banner tape can be used for added strength and reinforcement. Sewing the material can scratch or pick off coating. If sewing is desired, it is recommended that the material be double stitched hem side up with a maximum of five stitches per inch. Half moon wind slits are recommended for banners that are 10 feet or larger. Corner reinforcements, professional installer and proper installation tools are strongly recommended.

Printer Compatibility

Compatible with most Solvent, Eco-Solvent, Latex and UV curable inkjet printers.

Product Information

Size	Gloss	Matte	Size	Gloss	Matte
38"x10 ft.	3272-1100129	3272-1100141	80"x164 ft.	3272-1100135	3272-1100147
30"x164 ft.	3272-1100130	3272-1100142	98"x164 ft.	3272-1100136	3272-1100148
38"x164 ft.	3272-1100131	3272-1100143	126"x164 ft.	3272-1100137	3272-1100149
54"x164 ft.	3272-1100132	3272-1100144	150"x164 ft.	3272-1100138	3272-1100150
63"x164 ft.	3272-1100133	3272-1100145	177"x164 ft.	3272-1100139	3272-1100151
72"x164 ft.	3272-1100134	3272-1100146	196"x164 ft.	3272-1100140	3272-1100152

* Custom size by order