



United Way
of Greater Portland

AdMesh Vinyl Coated Scrim

AdMesh Vinyl Coated Scrim 9x9 is a lightweight, porous fabric that allows air to flow through it. It is ideally suited for signs, banners or as a protective barrier for scaffolding or bleachers. AdMesh Vinyl Coated Scrim 9x9 can be used on most inkjet printing machines or can be screen printed.

Applications:
Screen printing

Properties	Test Method	Results
Support Cloth		1000D Polyester
Weight	5041	0.5 oz/yd ²
Type of Coating		PVC
Width		62"
Tensile Strength	5100 (ward x fill)	209 x 204 lbs/inch

- Breathable
- Flexible
- High Tensile Strength
- Heat Sealable
- Rot & Tear Resistant

Available Colors:

Standard Green	Red
Standard Orange	Bermuda Blue
BFI Blue	Black
Standard Yellow	C. Green
Fluorescent Orange	Saturn Yellow

The above information on physical and chemical characteristics is based upon test believed to be reliable. The values are intended only as a source of information. They are given without guaranty and do not constitute a warranty. The purchaser should independently determine prior to use, the suitability of this material for his/her specific purpose. (Data represents averages and is not intended for use as a specification.)