

250 COMMERCIAL ST

250 COMMERCIAL STREET PORTLAND, MAINE

March 26, 2013

LIFE SAFETY CODE SUMMARY OF 250 COMMERCIAL STREET

250 COMMERCIAL STREET: GROUP B
TOTAL GROSS SQUARE FOOTAGE OF SALON IS: 3,202 SF

250 COMMERCIAL STREET OCCUPANCY LOAD IS:
3,202 SQFT @ 100 GSF PER PERSON = 32 PEOPLE

NFPA 7.3.1.2

COMMON PATH OF TRAVEL FOR GROUP B IS 100 FT

NFPA 38.2.5.3.1

SINGLE EXIT SHALL BE PERMITTED FOR A ROOM OR AREA WITH A TOTAL
OCCUPANT LOAD OF FEWER THAN 100 PERSONS

NFPA 38.2.4.3

MAX TRAVEL DISTANCE TO EXTINGUISHERS IS 75 FT

NFPA 10

OWNER:

CM WATERFRONT PROPERTIES, LLC
36 UNION WHARF
BOX 7467
PORTLAND, MAINE 04112
(207) 772-8160

ARCHITECT:

ARCHETYPE P.A.
48 UNION WHARF
PORTLAND, ME 04101
(207) 772-6022

DRAWING LIST

COVER PAGE
A1.00 FLOOR PLAN, FRAMING PLAN &
EGRESS
A2.00 BUILDING SECTIONS, ELEVATIONS
& SCHEDULES,