12'-7" RO LINTEL SECTION
WIDE FLANGE BEAM ASTM A-992.
PLATE ASTM A-36.
PROVIDE 6" BEARING AT BOTH ENDS.
INSTALL TEMPORARY SUPPORT FOR CMU WALL PRIOR TO CUTTING OPENINGS.

9 | SECT DETAIL AT WINDOW HEAD
SCALE: 1 1/2"=1'-0"

10 | SECT DETAIL AT WINDOW SILL
SCALE: 1 1/2"=1'-0"

5'-0" RO LINTEL SECTION
L ASTM A-36.
PROVIDE 6" BEARING AT BOTH ENDS.
INSTALL TEMPORARY SUPPORT FOR CMU WALL PRIOR TO CUTTING OPENINGS.

7 | SECT DETAIL AT WINDOW HEAD
SCALE: 1 1/2"=1'-0"

8 | SECT DETAIL AT WINDOW SILL
SCALE: 1 1/2"=1'-0"

4 | CROSS SECTION
SCALE: 1/4"=1'-0"

5 | WALL SECTION
SCALE: 1/4"=1'-0"

6 | WALL SECTION
SCALE: 1/4"=1'-0"

DOOR TYPES

DOOR SCHEDULE

No.	SIZE	DOOR		FINISH	THRESH	FRAME		REMARKS
	W x H x T	Type	Material			Material	Finish	
01	6'-0" x 7'-0" x 1 3/4"	A	SCW	PTD		HM	Ptd.	
02	6'-0" x 7'-0" x 1 3/4"	A	SCW	PTD		HM	Ptd.	
03	3'-0" x 7'-0" x 1 3/4"	B	SCW	PTD		HM	Ptd.	

WINDOW SCHEDULE

3 | INTERIOR ELEVATION
SCALE: 1/8"=1'-0"

2 | EAST ELEVATION
SCALE: 1/8"=1'-0"

1 | NORTH ELEVATION
SCALE: 1/8"=1'-0"

LICENSED ARCHITECT DAVID LLOYD NO. 936 STATE OF MAINE

Prepared For:

Architect: ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project: 250 COMMERCIAL STREET
250 COMMERCIAL STREET PORTLAND, MAINE

Revisions:

Scale: AS NOTED

Date: 14 March 2013

BUILDING SECTIONS, ELEVATIONS & SCHEDULES

A2.00

Reviewed for Code Compliance Inspections Division Approved with Conditions
Date: 5/2/2013
Planner: Jeanie Bourke