

STONEHILL & TAYLOR 21264 PRESS HOTEL- PORTLAND,MAINE							
PLUMBING FIXTURE SCHEDULE							
ISSUED: 08.27.13 REVISED 10.11.13							
GUESTROOMS							
LAVATORY							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	F-1	WALL-MOUNTED THREE-HOLE LAVATORY MIXER	WATERMARK JACK ABEL P.E. jabel@watermark-designs.com CL 718-257-2800	22-2.2-CL15SM	00 - POLISHED CHROME		1.5GPM
	F-2	SOFT TOUCH LAVATORY DRAIN WITH OVERFLOW WALL-MOUNTED THREE-HOLE LAVATORY MIXER (LEVER HANDLE) SOFT TOUCH LAVATORY DRAIN WITH OVERFLOW	WATERMARK	MPJ6	00 - POLISHED CHROME		ADA COMPLIANT/1.5GPM
SHOWER							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	F-5	TRIM KIT FOR THERMOSTATIC VALVE WITH SEPARATE CONTROLS 1/2" THERMOSTATIC VALVE 1/2" TILE STOP	WATERMARK	24-TFRK20-CL15SM+24-WTR-CL15SM	00 - POLISHED CHROME		ONE WATER OUTLET AT A TIME
	F-3	RAIN HEAD WITH CEILING MOUNTED SHOWER ARM	WATERMARK	SS-603AF+SH-PRES50	00 - POLISHED CHROME		2.5GPM
	F-4	HAND SHOWER KIT - HOOK AND ELBOW IN ONE	WATERMARK	HSS-KT104	00 - POLISHED CHROME		INCLUDES ELBOW, WALL MOUNTED, 15' HOSE AND SHOWER HEAD WITH 1.5 GPM HAND SHOWER. HAND SHOWER FLOW RATE - 2.5 GPM
ADA SHOWER							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	F-6	TRIM KIT FOR THERMOSTATIC VALVE WITH SEPARATE CONTROLS	WATERMARK	24-TFRK20-CL15SM+24-WTR-CL14SM	00 - POLISHED CHROME		ONE WATER OUTLET AT A TIME. FOR USE WITH SS-T11000 THERMOSTATIC VALVE AND 2X SS-TS200 VOLUME CONTROLS
	F-3	CEILING MOUNTED RAIN SHOWER	WATERMARK	28-569-970	00 - POLISHED CHROME		2.5GPM
	F-4	HAND SHOWER SET	WATERMARK	27-802-892	00 - POLISHED CHROME		2.5 GPM
	F-4	ROUGH	WATERMARK	35-080-970-50			
TOILET							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	P-9	WALL-HUNG TOILET, CARRIER, FLUSH PLATE AND SEAT	GEBERT	#111.335.00.5 WITH UP320 CONCEALED DUAL FLUSH TANK			WHERE APPLICABLE
			GEBERT	FIRE PROTECTION SET FOR SIGMA 111.863.00.1 464.00			
			GEBERT	BOLERO DUAL FLUSH PANEL 115.777.21.1	POLISHED CHROME		
			TOTO	AQUA CT419FG WITH SS204 SOFT CLOSE SEAT	01 COTTON		
SHOWER DRAIN & MISC							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	P-10	SHUT OFF VALVES AND EXPOSED P TRAP	BY CONTRACTOR		POLISHED CHROME		TO BE COORDINATED WITH DESIGNER
	P-11	SQ. SHOWER DRAIN	INFINITY DRAIN	TD 15 SERIES 5" SQ 12 GAUGE	POLISHED STAINLESS		
	P-13						
	P-14						
SINK							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	P-15	UNDERCOUNTER LAVATORY	KOHLER	LADENA K-2214 23-1/4" x 16-1/4" x 8-1/8"	WHITE		
	P-18	UNDERCOUNTER LAVATORY	KOHLER	LADENA K-2215 20-7/16" x 15-1/2" x 8-1/8"	WHITE		AT ADA VANTIES
BATH TUB							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	P-16	FREE STANDING TUB	LALFEN	SOLUTIONS 2251.2 66.98"Lx29.55"Wx 24.43"H	WHITE		
	P-8	FREE STANDING TUB FILLER WITH HAND SHOWER	WATERMARK	JW-620X20F8C	POLISHED CHROME		HAND SHOWER FLOW RATE: 1.5 GPM

STONEHILL & TAYLOR 21264 PRESS HOTEL- PORTLAND,MAINE							
PLUMBING FIXTURE SCHEDULE							
ISSUED: 08.27.13 REVISED 10.11.13							
GUESTROOMS							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	P-1	WALL-MOUNTED THREE-HOLE LAVATORY MIXER	WATERMARK JACK ABEL P.E. jabel@watermark-designs.com CL 718-257-2800	22-2.2-CL15SM	00 - POLISHED CHROME		1.5GPM
	P-19	SOFT TOUCH LAVATORY DRAIN WITH OVERFLOW	WATERMARK	MPJ6	00 - POLISHED CHROME		
	P-19	UNDERMOUNT BAR SINK - SMALL	MOEN	G204502	BRUSHED STAINLESS STEEL	JR SUITES	20 GA.
	P-20	UNDERMOUNT BAR SINK - LARGE	MOEN	G20192	BRUSHED STAINLESS STEEL	1BR SUITE	20 GA.
LOBBY & BASEMENT LAV & FAUCET							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	P-10	UNDERMOUNT SINK	KOHLER	CAXTON K-2110 17X14"	WHITE	LOBBY BATHRM	
	P-2	ROUGH SPOUT IN THE CENTER	WATERMARK	36 711 882	00 - POLISHED CHROME	LOBBY BATHRM	ADA COMPLIANT
	P-07	WALL MOUNTED ADA SINK W/ SOAP DISPENSER HOLE	KOHLER	SOHO K-2054	WHITE	FITNESS	
	P-12	DECK MOUNTED LAVATORY FAUCET	WATERMARK	22-2.2-CL14SM	POLISHED CHROME		FLOW RATE: 1.5 GPM (INCLUDES MPJ7 SOFT TOUCH DRAIN)
	P-12	STANDARD POP UP LAVATORY DRAIN	WATERMARK	MPJ1	POLISHED CHROME		
LOBBY AND BASEMENT TOILET							
IMAGE	TAG	DESCRIPTION	MANUF./VENDOR	MODEL #	FINISH	LOCATION	COMMENTS
	P-9	WALL-HUNG TOILET, CARRIER, FLUSH PLATE AND SEAT	GEBERT	#111.335.00.5 WITH UP320 CONCEALED DUAL FLUSH TANK		LOBBY FITNESS BASEMENT BATHRM	
			GEBERT	FIRE PROTECTION SET FOR SIGMA 111.863.00.1 464.00			WHERE APPLICABLE
			GEBERT	BOLERO DUAL FLUSH PANEL 115.777.21.1	POLISHED CHROME		
			TOTO	AQUA CT419FG WITH SS204 SOFT CLOSE SEAT	01 COTTON		
			TOTO	THUR10 STAINLESS STEEL URINAL DRAIN COVER			
			TOTO	TELUZ.N11#SE	STAINLESS STEEL		
			TOTO	UT10-EV1 0.5 GPF LOW CONSUMPTION WASHOUT URINAL	01 COTTON		
	P-17	URINAL WITH BACK SPUD INLET FLUSH VALVE AND URINAL DRAIN COVER					

PLUMBING LEGEND	
SYMBOL	DESCRIPTION
	SOIL OR WASTE (W.)
	GREASY WASTE (GW)
	VENT (V.)
	RAIN LEADER (RL)
	STORM DRAIN (SD)
	FORCED MAIN (FM)
	CONDENSATE DRAIN (D)
	INDIRECT WASTE/CONDENSATE DRAIN
	COLD WATER (CW)
	120° HOT WATER (HW)
	120° HOT WATER RETURN (HWR)
	FULL PORT BALL VALVE ON HOT & COLD WATER, BALANCING VALVE ON HOT WATER RETURN
	GATE VALVE
	CHECK VALVE
	UNION
	CLEANOUT
	F.C.O.
	G.C.O.
	W.C.O.
	F.D.
	F.S.
	R.D.
	L-1
	N.F.W.H.
	R.P.B.P.
	V.T.R.
	H.B.
	⊙
	⊕

NOTE: ALL BALL VALVES SHALL BE THREE PIECE FULL PORT. ALL BALANCING VALVE ON HWR LINES SHALL BE EQUAL TO BELL & GOSSETT LOWFLOW CIRCUIT SETTERS MODEL "RF" CALIBRATED BALANCING VALVES FOR LOW FLOW APPLICATIONS. BALANCING VALVE AT HWR PUMP SHALL BE EQUIPPED WITH TEST PORTS FOR BALANCING PURPOSES.

STONEHILL & TAYLOR 21264 PRESS HOTEL- PORTLAND,MAINE							
ACCESSORIES SCHEDULE							
ISSUED: 08.27.13; REVISED 10.11.13							
GUESTROOMS							
TAG	DESCRIPTION	MANUF. VENDOR	MODEL #	FINISH	LOCATION	COMMENTS	
-1	TOILET ROLL HOLDER	FROST DESIGN AF NEW YORK MINY REISS MindyR@afnewyork.com	TOILET ROLL HOLDER 1 N190	POLISHED CHROME	GUESTROOMS		
-2	SPARE TOILET ROLL HOLDER	FROST DESIGN AF NEW YORK	TOILET ROLL HOLDER 2 N191	POLISHED CHROME	GUESTROOMS		
-3	TOWEL BAR	FROST DESIGN AF NEW YORK	TOWEL BAR3 N191H-1 SIZE: 628MM(24.72")	POLISHED CHROME	GUESTROOMS	(2) REF GUESTROOM	
-4	ROBE HOOK	FROST DESIGN AF NEW YORK	HOOK6L N190-2 25MM	POLISHED CHROME	GUESTROOMS	(2) REF GUESTROOM (2) ARE IN ONE SET	
-5	1" ADA GRAB BAR	GINGER	HOTELIER #C362-PC	#26 POLISHED CHROME	GUESTROOMS		
-6	3" ADA GRAB BAR	GINGER	HOTELIER #C365-PC	#26 POLISHED CHROME	GUESTROOMS		
-7	4" ADA GRAB BAR	GINGER	HOTELIER #C366-PC	#26 POLISHED CHROME	GUESTROOMS		
-8	2" ADA GRAB BAR	GINGER	HOTELIER #C363-PC	#26 POLISHED CHROME	GUESTROOMS		
-9	FOLD-DOWN ADA SEAT	MOEN	FOLD-DOWN SHOWER SEAT DN710	SOLID TEAK WOOD	GUESTROOMS		
T-10	SOAP DISH	GINGER	553D	POLISHED CHROME	GUESTROOMS		
T-11	SHOWER ROD 3"	MOEN	DONNER 63-1	POLISHED CHROME	ADA SHOWER	CUT TO FIT	
T-12	SHOWER ROD 6"	MOEN	DONNER 63-1	POLISHED CHROME	ADA SHOWER		
T-13	4" ADA GRAB BAR	GINGER	HOTELIER #C3...PC	POLISHED CHROME	ADA SHOWER		
PUBLIC SPACES							
TAG	DESCRIPTION	MANUF. VENDOR	MODEL #	FINISH	LOCATION	COMMENTS	
T01	TOILET ROLL HOLDER	FROST DESIGN AF NEW YORK MINY REISS MindyR@afnewyork.com	TOILET ROLL HOLDER 1 N190	POLISHED CHROME	LOBBY & BASEMENT		
T02	SPARE TOILET ROLL HOLDER	FROST DESIGN AF NEW YORK	TOILET ROLL HOLDER 2 N191	POLISHED CHROME	LOBBY & BASEMENT		
T03	ROBE HOOK	FROST DESIGN AF NEW YORK	HOOK6L N190-2 25MM	POLISHED CHROME	LOBBY & BASEMENT	(1) REF STAL (2) ARE IN ONE SET	
T05	1" ADA GRAB BAR	GINGER	HOTELIER #C362-PC	#26 POLISHED CHROME	LOBBY & BASEMENT		
T06	3" ADA GRAB BAR	GINGER	HOTELIER #C365-PC	#26 POLISHED CHROME	LOBBY & BASEMENT		
T07	4" ADA GRAB BAR	GINGER	HOTELIER #C366-PC	#26 POLISHED CHROME	LOBBY & BASEMENT		
T08	P/TRAP COVER	PLUMBEREX	PRO-EXTREME 1-PC COVER	WHITE		100% PVC	
T09-T10	NOT USED						
T011	DECK MOUNTED (NOT USED) SOAP DISPENSER WITH FLANGE	DORNBRACHT BENEDICT GORSLKE bgorslke@donbrach.com CL 917-929-0648	82436970	POLISHED CHROME	FITNESS CTR		

- ### KITCHEN NOTES
- ROUGH-IN AND MAKE FINAL CONNECTIONS TO ALL KITCHEN & BAR EQUIPMENT.
 - COORDINATE WITH EQUIPMENT SUPPLIER FOR EXACT LOCATION AND REQUIREMENTS FOR ALL ROUGH-INS.
 - FURNISH AND/OR INSTALL PIPING AND FITTINGS, INCLUDING ALL NECESSARY VALVES, TRAPS, FLOW CONTROLS, FILTERS, BACKFLOW PREVENTERS, FAUCETS, STOPS, VACUUM BREAKERS AND TAILPIECES IF NOT FURNISHED OR WITH EQUIPMENT.
 - FURNISH AND INSTALL HAND SHUT-OFF VALVES ON ALL HOT AND COLD WATER LINES AT SUB-IN TO EQUIPMENT.
 - INSULATE ALL INDIRECT DRAIN LINES FROM REFRIGERATORS, ICE BINS, ETC. WITH ONE INCH THICK FIBERGLASS INSULATION.
 - HOLD WATER LINES ABOVE FLOOR A MINIMUM OF SIX INCHES. CONTRACTOR SHALL FLUSH OUT ALL UTILITY PIPING AND DRAIN LINES PRIOR TO CONNECTION OF EQUIPMENT.
 - INSTALL ALL PLUMBING AS PER PLUMBING AND HEALTH DEPARTMENT REQUIREMENTS.
 - ALL EQUIPMENT WITH QUICK CLOSING VALVES SHALL BE EQUIPPED WITH SHOCKSTOP.

JEFFREY A. CRABTREE
No. 13282
LICENSED PROFESSIONAL ENGINEER

Prepared For: **119 Development, LLC**
P.O. Box 7468
Portland, ME 04112

Consultant: **CRABTREE ENGINEERING**
978 AMIELLA COVE
COLLIERVILLE, TN 38017
PLUMBING: bobgrobstein@gmail.com

Architect: **ARCHETYPE architects**
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project: **PRESS HOTEL**
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:
 1 13_07-01 50% Marriott Submission
 2 13_09-09 60% Marriott Sub. & Pric.
 3 13_10-14 Issue for Bid & Marriott Rev.

Date: 13 October 2013
Scale: AS NOTED

PLUMBING NOTES AND SCHEDULES

P9.01