PLUMBING EQUIPMENT SCHEDULE

CALLOUT	SYMBOL	VOLTS	KVA	HP	CIRCUIT	WIRE CALLOUT
BOILER CONTROLS		120V 1P 2W	0.6		SB-2	1/2"C,1#12,#12N,#12G
BOILER CONTROLS		120V 1P 2W	0.6		SB-4	1/2"C,1#12,#12N,#12G
KITCHEN WATER HEATER CONTROLS		120V 1P 2W	1.44		SB-8	1/2"C,1#12,#12N,#12G
MOTORIZED VALVE		120V 1P 2W	0.6		2CK-31	1/2"C,1#12,#12N,#12G
RAINWATER PUMPS		208V 3P 3W	3.49	(2)1 HP	2CK-25,27,29	1/2"C,3#12,#12G
RECIRC PUMP		120V 1P 2W	0.53	1/6 HP	SB-6	1/2"C,1#12,#12N,#12G
RECIRC PUMP		120V 1P 2W	0.1	F HP	SB-10	1/2"C,1#12,#12N,#12G
SEWAGE PUMPS		208V 2P 2W	3.31	(2)3/4 HP	2CK-21,23	1/2"C,2#12,#12G
SUB PUMP CONTROLS		120V 1P 2W	0.6		SB-26	1/2"C,1#12,#12N,#12G
SUB PUMP CONTROLS		120V 1P 2W	0.6		SB-26	1/2"C,1#12,#12N,#12G
SUB PUMP CONTROLS		120V 1P 2W	0.6		SB-40	1/2"C,1#12,#12N,#12G
SUB PUMP CONTROLS		120V 1P 2W	0.6		SB-40	1/2"C,1#12,#12N,#12G
SUBMERSIBLE PUMP		208V 3P 3W	1.75	1 HP	SB-14,16,18	1/2"C,3#12,#12G
SUBMERSIBLE PUMP		208V 3P 3W	1.75	1 HP	SB-20,22,24	1/2"C,3#12,#12G
SUBMERSIBLE PUMP		208V 3P 3W	1.75	1 HP	SB-28,30,32	1/2"C,3#12,#12G
SUBMERSIBLE PUMP		208V 3P 3W	1.75	1 HP	SB-34,36,38	1/2"C,3#12,#12G
WATER HEATER		120V 1P 2W	1.32		SB-7	1/2"C,1#12,#12N,#12G
WATER HEATER		120V 1P 2W	1.32		SB-9	1/2"C,1#12,#12N,#12G

ELEVATOR EQUIPMENT SCHEDULE

CALLOUT	SYMBOL	VOLTS	KVA	CIRCUIT	WIRE CALLOUT
ELEV #1 LTS		120V 1P 2W	0.3		
ELEV #2 LTS		120V 1P 2W	0.3		
ELEV #3 LTS		120V 1P 2W	0.3		
ELEV #4 LTS		120V 1P 2W	0.3	SB-31	1/2"C,1#12,#12N,#12G
ELEVATOR #1		208V 3P 3W	9.37	ATS2-1	1"C,3#4,#8G
ELEVATOR 1 HVAC		120V 1P 2W	1.2	MR-11	1/2"C,1#12,#12N,#12G
ELEVATOR #2		208V 3P 3W	9.37	MR-1,3,5	1"C,3#4,#8G
ELEVATOR 2 HVAC		120V 1P 2W	1.2	MR-13	1/2"C,1#12,#12N,#12G
ELEVATOR #3		208V 3P 3W	25.94	MSB-20	1-1/4"C,3#1,#6G
ELEVATOR 3 HVAC		120V 1P 2W	1.2	SB-33	1-1/2"C,1#4/0,#4/0N,#4G
ELEVATOR #4		208V 3P 3W	43.59	MSB-21	2"C,3#4/0,#4G
ELEVATOR 4 HVAC		120V 1P 2W	1.2	SB-35	1-1/2"C,1#4/0,#4/0N,#4G

ELEVATOR 1,2, AND 3 LIGHTS PER LIGHTING PLAN

FIRE PROTECTION EQUIPMENT SCHEDULE

CALLOUT	VOLTS	HP	CIRCUIT	WIRE CALLOUT
FIRE PUMP	208V 3P 3W	60 HP		
JOCKEY PUMP	208V 3P 3W	5 HP	SB-23,25,27	1/2"C,3#10,#10G

FIRE PUMP TAPPED AHEAD OF MAIN REFER TO SHEET E6.02

1 | SUB-BASEMENT ELECTRICAL PLAN

SCALE: 1/8"=1'-0"

REFER TO SHEET E4.01 FOR MECHANICAL EQUIPMENT SCHEDULES AND MECHANICAL DRAWINGS FOR LOCATIONS OF ALL EQUIPMENT

Project North

W E S

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/22/14

Prepared For:
119 Development, LLC
P.O. Box 7468
Portland, ME 04112

Consultant:
CHS ENGINEERING
CONSTANCE HICKEY SCOTT, PE
7846 WOOD OAK COVE
CORDOVA, TN 38016
TEL: (901) 830-5300
EMAIL:chscott@chsengineering.com

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
PRESS HOTEL
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:

1	13_10-14	Issue for Bid & Marriott Revw
2	13_10-21	Addendum #2
3	13_10-31	Addendum #3

Scale: As indicated

Date: 23 OCT 13

SUB-BASEMENT ELECTRICAL PLAN

E1.01