1 | UNITS 205, 201, 305, 303, 405, 403, 505, 503, 605, 601 & 701 - PLUMBING

SCALE: 1/4"=1'-0"

ALL WC SHALL HAVE 3" WASTE STACKS AND 2" VENT STACK. ALL LAV AND SHOWER SHALL HAVE 2" WASTE AND VENT STACKS.	PROVIDE EACH FCU WITH 1 1/2" CONNECTION (TYPICAL ALL FCU ALL FLOORS).	CONNECT ALL 1 1/2" IW W/ SAN. TEE ABOVE TRAP ON SH (TYPICAL ALL FCU ALL FLOORS).
DROP WATER RISERS DN. AT LAVATORY. LOCATE BALL VALVES AND BALL COCK IN WALL WITH ACCESS PANEL. (TYPICAL ALL SECOND FLOORS).	PROVIDE WCO AT BASE OF ALL WASTE STACKS.	WASTE, VENT, CONDENSATE AND WATER RISERS OFFSETS ARE NOT INDICATED. PROVIDE OFFSETS AS REQUIRED.

2 | UNITS 211, 209, 207, 411, 409, 407, 511, 509, 507, 611, 609, 607, 711, 709, & 707 - PLUMBING

SCALE: 1/4"=1'-0"

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/22/14

Prepared For:
119 Development, LLC
P.O. Box 7468
Portland, ME 04112

Consultant:
CRABTREE ENGINEERING
278 AMELIA COVE
COLLIERVILLE, TN. 38017
PLUMBING: bobbygookin@gmail.com

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
PRESS HOTEL
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:

1	13_10-14	Issue for Bid & Marriott Revw
2	13_10-21	Addendum #2
3	13_10-31	Addendum #3

Date: 13 October 2013

Scale: 1/4" = 1'-0"

TYPICAL GUESTROOMS PLUMBING

P7.04