ACCESSIBLE AND HEARING IMPAIRED ROOMS PER ARCHITECTURAL PLANS:

201, 207 (HEARING); 222 (ACCESSIBLE)
307, 322 (HEARING); 309, 323 (ACCESSIBLE)
407, 422 (HEARING); 410 (ACCESSIBLE)
502, 523 (HEARING); 516 (ACCESSIBLE)
601 (HEARING & ACCESSIBLE), 614 (HEARING)
701, 712 (HEARING); 710 (ACCESSIBLE)

VERIFY LOCATIONS PRIOR TO ROUGH-IN

LIGHTING KEY NOTES:

1. ILLUMINATED CLOSET ROD FURNISHED WITH INTERIOR PACKAGE, E.C. TO WIRE THEM TO DOOR SWITCH.

LIGHTING GENERAL NOTES:

1. ALL LT-101 J-BOXES TO BE MOUNTED AT +82"AFF.
2. ALL J-BOXES FOR LT-102 VANITY SCONCE TO BE MOUNTED AT +64"AFF.
3. ALL LT-103 & LT-103A J-BOXES FOR HEADBOARD SCONCE ARE TO BE MOUNTED AT +54"AFF.
4. ALL CLOCK OUTLETS FOR LT-105 PICTURE LIGHT TO BE MOUNTED AT +60"AFF.
5. LT-106 SHOWER LIGHT IS TO BE MOUNTED IN RECESSED CEILING POCKET. SEE DETAIL.
6. SEE GUESTROOM BATH DRAWINGS, SHT. ID7.XX FOR TYPICAL VANITY SCONCE LT-107 LOCATION.
7. BEDSIDE GOOSENECK READING LIGHT LT-108 IS PLUG-IN. SEE HEADBOARD DETAIL FOR INFO.
8. ALL LT-109 CORRIDOR PICTURE CLOCK OUTLETS TO BE MOUNTED AT +66"AFF.
9. DRAPERY VALANCE IS GC PROVIDED. SEE DETAIL.

GENERAL NOTES:

1. REFER TO SHEET E3.01 FOR GUEST ROOM GENERAL NOTES AND ELECTRICAL SYMBOLS.

1 SEVENTH FLOOR 'GUESTROOM' ELECTRICAL PLANS
SCALE: 1/4"=1'-0"

Project North
W E
S

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 01/22/14

Prepared For:
119 Development, LLC
P.O. Box 7468
Portland, ME 04112

Consultant:
CHS ENGINEERING
CONSTANCE HICKEY SCOTT, PE
7646 WOOD OAK COVE
CORDOVA, TN 38016
TEL: (901) 830-5300
EMAIL:chsscott@chsengineering.com

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
PRESS HOTEL
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:

1	13_10-14	Issue for Bid & Marriott Revw
2	13_10-21	Addendum #2
3	13_10-31	Addendum #3

Scale: As indicated

Date: 23 OCT 13

SEVENTH FLOOR 'GUESTROOM' ELECTRICAL PLANS

ADDENDUM
E3.06