1 | SUB - BASEMENT PLAN - WATER

SCALE: 1/8"=1'-0"

MISCELLANEOUS PLUMBING NOTES:

1. CEILING SPACE FOR PIPING FOR FLOORS 2ND AND LOWER IS LIMITED. CONTRACTOR SHALL PENETRATE BEAMS WHERE NECESSARY TO KEEP PIPING AT THE HIGHEST ELEVATION POSSIBLE. CONTRACTOR SHALL PREPARE SHOP DRAWINGS OF ALL BEAM PENETRATIONS AND FLOOR CORE-DRILL LOCATIONS AND SUBMIT TO STRUCTURAL ENGINEER AND ARCHITECT FOR APPROVAL.
2. ALL FIXTURES/DRAINS SHALL BE VENTED AS PER CODE.
3. AT CONDENSATE RISERS FOR GUEST ROOMS PROVIDE A WASTE AND A VENT STACK AS PER CODE.
4. ALL CONCRETE SHALL BE SAWCUT BEFORE BREAKING AND REMOVING.
5. DITCHES SHALL BE DEWATERED AND PROVIDED WITH SUITABLE BACKFILL AS REQUIRED. SEE EXCAVATION SECTION INSPECIFICATIONS FOR BACKFILL REQUIREMENTS AND COMPACTION.
6. ALL PIPING 4" AND LARGER SHALL BE RUN AT 1/8" FALL/FT.

2 | SUB - BASEMENT PLAN - WASTE, VENT AND RAIN LEADER

SCALE: 1/8"=1'-0"

CITY OF PORTLAND, MAINE – RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/22/14

Prepared For:
119 Development, LLC
P.O. Box 7468
Portland, ME 04112

Consultant:
CRABTREE ENGINEERING
278 AMELIA COVE
COLLIERVILLE, TN. 38017
PLUMBING: bobbygookin@gmail.com

Architect:
ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
PRESS HOTEL
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:

1	13_10-14	Issue for Bid & Marriott Review
2	13_10-21	Addendum #2
3	13_10-31	Addendum #3

Date: 13 October 2013

Scale: 1/8"=1'-0"

SUB-BASEMENT PLANS - PLUMBING

P0.10