

KITCHEN/BAR NOTES

1. ROUGH-IN AND MAKE FINAL CONNECTIONS TO ALL KITCHEN, PANTRY, BAR, ETC. EQUIPMENT. COORDINATE WITH EQUIPMENT SUPPLIER FOR EXACT LOCATION AND REQUIREMENTS FOR ALL ROUGH-INS.
2. FURNISH AND/OR INSTALL PIPING AND FITTINGS, INCLUDING ALL NECESSARY VALVES, TRAPS, FLOW CONTROLS, FILTERS, BACKFLOW PREVENTERS, FAUCETS, STOPS, VACUUM BREAKERS AND TAILPIECES IF NOT FURNISHED ON OR WITH EQUIPMENT.
3. FURNISH AND INSTALL HAND SHUT-OFF VALVES ON ALL HOT AND COLD WATER LINES AT STUB-IN TO EQUIPMENT.
4. INSULATE ALL INDIRECT DRAIN LINES FROM REFRIGERATORS, ICE BINS, ETC. WITH ONE INCH THICK FIBERGLASS INSULATION.
5. HOLD WATER LINES ABOVE FLOOR A MINIMUM OF SIX INCHES.
6. CONTRACTOR SHALL FLUSH OUT ALL UTILITY PIPING AND DRAIN LINES PRIOR TO CONNECTION OF EQUIPMENT.
7. INSTALL ALL PLUMBING AS PER PLUMBING AND HEALTH DEPARTMENT REQUIREMENTS.
8. ALL EQUIPMENT WITH QUICK CLOSING VALVES SHALL BE EQUIPPED WITH SHOKSTOP.
9. SEE KITCHEN EQUIPMENT DRAWINGS FOR ADDITIONAL REQUIREMENTS INCLUDING EXACT LOCATION FOR ALL ROUGH-INS.

1 | ENLARGED KITVHEN PLAN - PLUMBING
SCALE: 1/4"=1'-0"

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/22/14

Prepared For:
119 Development, LLC
P.O. Box 7468
Portland, ME 04112

Consultant:
CRABTREE ENGINEERING
278 AMELIA COVE
COLLIERVILLE, TN. 38017
PLUMBING: bobbygookin@gmail.com

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
PRESS HOTEL
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:

1	13_10-14	Issue for Bid & Marriott Revw
2	13_10-21	Addendum #2
3	13_10-31	Addendum #3

Scale: 1/4" = 1'-0"

Date: 13 October 2013

ENLARGE KITCHEN PLAN - PLUMBING

P7.06