DOOR SCHEDULE - SUB-BASEMENT THRU FIRST FLOOR

DOOR No.	LOCATION	DOOR W	DOOR H	DOOR THCK	DOOR TYPE	DOOR MAT'L	FRAME HEAD/ JAMB	FRAME THRES	FRAME MAT'L	LABEL	OPER.	CL.	REMARKS
SUB-BASEMENT													
B0A	STAIR A	3'-0"	7'-0"	1 3/4"	3	HM	A/A1	-	HM	90 MINS	PASSAGE	Yes	GALV. FRAME & DOOR
B0B	STAIR B	3'-0"	7'-0"	1 3/4"	3	HM	A/A1	-	HM	90 MINS	PASSAGE	Yes	GALV. FRAME & DOOR
B0C	ELEV. 1 PIT	3'-0"	6'-4"	1 3/4"	1	HM	G/G1	ALUM.	HM	90 MINS	STORAGE	Yes	GALV. FRAME & DOOR
B01	ELEV. MACH. RM	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	90 MINS	STORAGE	Yes	GALV. FRAME & DOOR
B02	ELEV. MACH. RM	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	90 MINS	STORAGE	Yes	GALV. FRAME & DOOR
B10	DRY STORAGE	6'-0"	7'-0"	1 3/4"	2	HM	A/A1	-	HM	-	DUMMY/ELEC STRIKE	Yes	GALV. FRAME & DOOR
B10B	REFRIG. TRASH	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	ALUM.	HM	45 MINS	PASSAGE	Yes	INSULATED DOOR & FRAME
B10C	REFRIG. RECYC.	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	ALUM.	HM	45 MINS	PASSAGE	Yes	INSULATED DOOR & FRAME
B12	SUMP ROOM	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	ALUM	HM	-	STORAGE	Yes	GALV. FRAME & DOOR
B21	MECHANICAL	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	45 MINS	STORAGE	Yes	GALV. FRAME & DOOR
B24	MECHANICAL	3'-6"	7'-0"	1 3/4"	3	HM	A/A1	-	HM	45 MINS	STORAGE	Yes	GALV. FRAME & DOOR
LOWER LEVEL													
00A	STAIR A	3'-0"	7'-4"	1 3/4"	3	HM	H/H1	-	HM	90 MINS	PANIC-PASS	Yes	-
00AB	STAIR A	3'-0"	7'-4"	1 3/4"	3	HM	H/H1	-	HM	90 MINS	PANIC-PASS	Yes	-
00B	STAIR B	3'-0"	8'-0"	1 3/4"	6	HM	B/B1	-	HM - FL	90 MINS	PANIC-PASS	Yes	-
00BA	STAIR B	3'-0"	7'-0"	1 3/4"	3	HM	B/B1	-	HM	90 MINS	PANIC-PASS	Yes	-
00E	ELEV. 3 - PIT	3'-0"	7'-0"	1 3/4"	1	HM	H/H1	ALUM.	HM	90 MINS	STORAGE	Yes	-
001	PREFUNCTION /GALLERY	6'-0"	8'-0"	1 3/4"	14	STL-GLS	D/D1	-	STL	-	PANIC	Yes	STL & GL DOOR SYSTEM, PROVIDE HOLD OPEN. COORD. w/ FA/SMOKE DETECTORS
001A	PREFUNCTION /GALLERY	6'-0"	8'-0"	1 3/4"	14	STL-GLS	D/D1	-	STL	-	PANIC	Yes	STL & GL DOOR SYSTEM, PROVIDE HOLD OPEN. COORD. w/ FA/SMOKE DETECTORS
003	MEN	3'-0"	8'-0"	1 3/4"	13	STL-GLS	D/D1	-	STL	-	PUSH/PULL	Yes	STL & GL DOOR SYSTEM
004	WOMEN	3'-0"	8'-0"	1 3/4"	13	STL-GLS	D/D1	-	STL	-	PUSH/PULL	Yes	STL & GL DOOR SYSTEM
005	MEETING ROOM #2	6'-0"	8'-0"	1 3/4"	14	STL-GLS	D/D1	-	STL	-	PANIC	Yes	STL & GL DOOR SYSTEM, PROVIDE HOLD OPEN. COORD. w/ FA/SMOKE DETECTORS
005A	MEETING ROOM #2	3'-0"	8'-0"	1 3/4"	5	SCWD	C/C1	-	HM - FL	-	PANIC	Yes	FLUSH PANEL TO MATCH WAINSCOTTING, SEE INTERIORS
005B	STORAGE	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	-	STORAGE	Yes	-
006	ELEC.	3'-0"	8'-0"	1 3/4"	5	SCWD	C/C1	-	HM - FL	-	STORAGE	Yes	FLUSH PANEL TO MATCH WAINSCOTTING, SEE INTERIORS
007	HALL	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	45 MINS	STORAGE	Yes	-
007A	ELEC. SERVICE ENTRANCE	6'-0"	7'-0"	1 3/4"	2	HM	A/A1	-	HM	-	STORAGE	No	-
008	HALL	3'-0"	8'-0"	1 3/4"	4	SCWD	B/B1	-	HM - FL	-	STORAGE	Yes	-
008A	HALL	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	-	PASSAGE	Yes	-
008D	EMERG. TRANS. SWITCH CL	6'-0"	7'-0"	1 3/4"	2	HM	A/A1	-	HM	90 MINS	STORAGE	No	-
009	COATS	3'-0"	8'-0"	1 3/4"	4	SCWD	B/B1	-	HM - FL	-	OFFICE	Yes	-
010	BOARD ROOM	3'-0"	8'-0"	1 3/4"	13	STL-GLS	D/D1	-	STL	-	PANIC	Yes	STL & GL DOOR SYSTEM, PROVIDE HOLD OPEN. COORD. w/ FA/SMOKE DETECTORS
010A	BOARD ROOM	3'-0"	8'-0"	1 3/4"	4	SCWD	C/C1	-	HM - FL	45 MINS	PANIC-PASS	Yes	FLUSH PANEL TO MATCH WAINSCOTTING
011	CORRIDOR	3'-0"	8'-0"	1 3/4"	4	SCWD	B/B1	-	HM	45 MINS	PASSAGE	Yes	-
011A	MEETING ROOM #1A	3'-0"	8'-0"	1 3/4"	4	SCWD	C/C1	-	HM - FL	45 MINS	PANIC-PASS	Yes	FLUSH PANEL TO MATCH WAINSCOTTING
012	STORAGE VESTIBULE	3'-0"	8'-0"	1 3/4"	4	SCWD	C/C1	-	HM - FL	45 MINS	PANIC-PASS	Yes	FLUSH PANEL TO MATCH WAINSCOTTING
013	STORAGE VESTIBULE	6'-0"	7'-0"	1 3/4"	2	HM	A/A1	-	HM	-	PASSAGE	No	-
014	PREFUNCTION /GALLERY	3'-0"	8'-0"	1 3/4"	4	SCWD	B/B1	-	HM - FL	45 MINS	STORAGE	Yes	-
020A	CORRIDOR	3'-0"	8'-0"	1 3/4"	6	SCWD	B/B1	-	HM - FL	20 MINS	PASSAGE	Yes	-
021	LAUNDRY	3'-0"	7'-0"	1 3/4"	1	SCWD	A/A1	-	HM	45 MINS	PASSAGE	Yes	-
021A	ELEV. VEST.	3'-0"	7'-0"	1 3/4"	3	HM	A/A1	-	HM	-	PASSAGE	Yes	-
021B	PANTRY	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	-	PASSAGE	Yes	-
021C	PANTRY	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	-	PASSAGE	Yes	-
021D	LAUNDRY	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM				
022	ADMIN	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	-	DUMMY/ELEC STRIKE	Yes	-
022A	ADMIN	3'-0"	7'-0"	1 3/4"	8	SCWD	A/A1	-	HM	-	OFFICE	No	-
022B	ADMIN	3'-0"	7'-0"	1 3/4"	8	SCWD	A/A1	-	HM	-	OFFICE	No	-
022C	ADMIN	3'-0"	7'-0"	1 3/4"	8	SCWD	A/A1	-	HM	-	OFFICE	No	-
022D	ADMIN	3'-0"	7'-0"	1 3/4"	8	SCWD	A/A1	-	HM	-	OFFICE	No	-
023	EMPLOYEE BREAK ROOM	3'-0"	7'-0"	1 3/4"	3	HM	A/A1	-	HM	20 MINS	DUMMY/ELEC STRIKE	Yes	-
024	MENS	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	45 MINS	DUMMY/ELEC STRIKE	Yes	-
024A	MENS	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	-	PRIVACY SET	No	-
025	WOMENS	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	45 MINS	DUMMY/ELEC STRIKE	Yes	-
025B	WOMENS	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	-	PRIVACY SET	No	-
026	FITNESS	3'-0"	8'-0"	1 3/4"	13	STL-GLS	D/D1	-	STL	20 MINS	DUMMY/ELEC STRIKE	Yes	STL & GL DOOR SYSTEM
027	WC	3'-0"	8'-0"	1 3/4"	5	SCWD	B/B1	-	HM - FL	-	PRIVACY SET	No	-
028	JAN.	3'-0"	7'-0"	1 3/4"	1	SCWD	A/A1	-	HM - FL	20 MINS	STORAGE	Yes	-
030	ELEV. VEST.	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM	45 MINS	PASSAGE	No	-
120C	BOH	3'-0"	7'-0"	1 3/4"	1	HM	A/A1	-	HM - FL	-	STORAGE	No	-
F001	MEETING ROOM #1B	15'-0"	10'-2 1/2"	1 1/2"	-	-	-	-	-	-	-	No	OPERABLE PARTITION BY MODERNFOLD, SEE FINISH SCHD. FULLY CONCEALED HEADER AND JAMB
1ST FLOOR													
10A	STAIR A	3'-0"	7'-0"	1 3/4"	1	HM	B/B1	-	HM	-	PANIC-PASS	Yes	MODIFIED EXISTING
10B	FEDERAL ENTRY	3'-0"	8'-0"	1 3/4"	4	HM	C/C1	-	HM - FL	-	PANIC-PASS	Yes	STYLE AND RAIL DOOR w/ VISION PANEL
101	WOMENS	3'-0"	8'-0"	1 3/4"	13	STL-GLS	D/D1	-	STL	20 MINS	PUSH/PULL	Yes	STL & GL DOOR SYSTEM
102	WOMENS	3'-0"	8'-0"	1 3/4"	13	STL-GLS	D/D1	-	STL	20 MINS	PUSH/PULL	Yes	STL & GL DOOR SYSTEM
103	FLEX SPACE	6'-0"	8'-0"	1 3/4"	14	STL-GLS	D/D1	-	STL	-	CLASSROOM	No	STL & GL DOOR SYSTEM, PROVIDE HOLD OPEN. COORD. w/ FA/SMOKE DETECTORS
104	CL.	3'-0"	8'-0"	1 3/4"	5	SCWD	B/B1	-	HM - FL	-	STORAGE	No	-
111	LUGGAGE	3'-0"	8'-0"	1 3/4"	5	SCWD	B/B1	-	HM - FL	-	DUMMY/ELEC STRIKE	Yes	-
112	OFFICE	3'-0"	8'-0"	1 3/4"	5	SCWD	B/B1	-	HM - FL	-	DUMMY/ELEC STRIKE	Yes	-
113	SAFE	3'-0"	8'-0"	1 3/4"	5	SCWD	B/B1	-	HM - FL	-	STORAGE	No	-
114	GM OFFICE	3'-0"	8'-0"	1 3/4"	5	SCWD	B/B1	-	HM - FL	-	OFFICE	No	-
115	BAR STORAGE	2'-6"	8'-0"	1 3/4"	4	WD	C/C1	-	HM - FL	-	STORAGE	Yes	FLUSH PANEL TO MATCH WAINSCOTTING, PNT GRADE
120	CONGRESS ENTRY	6'-0"	7'-10 3/4"	1 3/4"	10	WD	E/E1	MTL	WD	-	ENTRY - PANIC	Yes	NEW DOOR TO MATCH HISTORIC SEE A8.03 & A8.04
120A	CONGRESS ENTRY	6'-1"	8'-0"	1 3/4"	14	STL-GLS	D/D1	-	STL	1HR	PANIC - ENTRY	Yes	STL & GL DOOR SYSTEM
121	MARKET ENTRY	5'-0 1/16"	7'-10 3/4"	1 3/4"	10	WD	E/E1	MTL	WD	-	ENTRY - PANIC	Yes	NEW DOOR TO MATCH HISTORIC SEE A8.03 & A8.04
121A	MARKET ENTRY	6'-0"	8'-0"	1 3/4"	14	STL-GLS	D/D1	-	STL		PANIC - ENTRY	No	STL & GL DOOR SYSTEM
122	FEDERAL ENTRY	5'-7"	11'-9 1/2"	1 3/4"	10	WD	E/E1	MTL	WD	-	ENTRY - PANIC	Yes	NEW DOOR TO MATCH HISTORIC SEE A8.03 & A8.04
122A	ENTRY VESTIBULE	3'-0"	8'-0"	1 3/4"	5	SCWD	B/B1	-	HM - FL	90 MINS	PANIC	Yes	-
123	EXCHANGE ENTRY	3'-0"	9'-0"	1 3/4"	11	GLASS	-	MTL	GLASS	-	ENTRY - PANIC	Yes	-
123A	EXCHANGE ENTRY	6'-0"	8'-0"	1 3/4"	14	STL-GLS	D/D1	-	STL		PANIC - ENTRY	No	STL & GL DOOR SYSTEM, AUTOMATIC DOOR OPENER
131	LOBBY	3'-0"	8'-0"	1 3/4"	13		D/D1			-	ENTRY	Yes	STL & GL DOOR SYSTEM

DOOR SCHEDULE - 2ND FL THRU ROOF

DOOR No.	LOCATION	DOOR W	DOOR H	DOOR THICK	DOOR TYPE	DOOR MAT'L	FRAME HEAD/ JAMB	FRAME THRES	FRAME MAT'L	LABEL	OPER.	CL.	REMARKS
2ND FLOOR													
20A	STAIR A	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
20B	STAIR B	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
200-C	HOUSE KEEPING	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	20 MINS	DUMMY/ ELEC. STRIKE	Yes	-
200-G	IT CL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	STORAGE	Yes	
3RD FLOOR													
30A	STAIR A	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
30B	STAIR B	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	
300-C	HOUSE KEEPING	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	20 MINS	DUMMY/ ELEC. STRIKE	Yes	-
300-D	HALL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	PASSAGE	Yes	-
300-E	ICE	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	-	STORAGE	Yes	-
300-G	IT CL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	STORAGE	Yes	
4TH FLOOR													
40A	STAIR A	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
40B	STAIR B	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	
400-C	HOUSE KEEPING	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	20 MINS	DUMMY/ ELEC. STRIKE	Yes	-
400-D	HALL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	PASSAGE	Yes	-
400-E	CL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	STORAGE	Yes	-
400-F	HALL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-		Yes	-
400-G	IT CL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1		HM - FL	-	STORAGE	Yes	
5TH FLOOR													
50A	STAIR A	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
50B	STAIR B	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
500-C	HOUSE KEEPING	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	20 MINS	DUMMY/ ELEC. STRIKE	Yes	-
500-D	HALL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	PASSAGE	Yes	-
500-E	CL.	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	STORAGE	Yes	-
500-F	HALL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	PASSAGE	Yes	-
500-G	IT CL	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	-	STORAGE	Yes	
6TH FLOOR													
60B	STAIR B	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PANIC - PASS	Yes	-
600-B	EXIT ACC. CORR.	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
600-C	HOUSE KEEPING	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	45 MINS	DUMMY/ ELEC. STRIKE	Yes	-
R601	JUNIOR SUITE	2'-11 1/2"	6'-3"	1 3/4"	8	ALUM	ALUM	ALUM	ALUM	-	STORAGE	Yes	THEM. BROKEN ALUM STOREFRONT - FULL WEATHER SEAL - INSULATED LEAF
R602	JUNIOR SUITE	3'-0"	6'-3"	1 3/4"	8	ALUM	ALUM	ALUM	ALUM	-	STORAGE	Yes	THEM. BROKEN ALUM STOREFRONT - FULL WEATHER SEAL - INSULATED LEAF
LANDING - ROOFTOP EXIT ACCESS													
R603	EXIT ACC. CORR.	3'-0"	7'-0"	1 3/4"	1	HM	-	ALUM	HM	-	STORAGE	Yes	GALV. & INSULATED FRAME AND LEAF - FULL WEATHER SEAL - PAINT GRADE
7TH FLOOR													
70A	STAIR C	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
70B	STAIR B	3'-0"	7'-0"	1 3/4"	3	SCWD	B/B1	-	HM - FL	90 MINS	PASSAGE	Yes	-
700-B	HOUSE KEEPING	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	20 MINS	DUMMY/ ELEC. STRIKE	Yes	-
700-C	HOUSE KEEPING	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	45 MINS	STORAGE	Yes	-
709-A	STAIR B	3'-0"	7'-0"	1 3/4"	1	SCWD	B/B1	-	HM - FL	90 MINS	PRIVACY	Yes	-
ROOF													
R801	STAIR B	3'-0"	7'-0"	1 3/4"	-	HM	-	ALUM	HM	-	STORAGE	Yes	GALV. & INSULATED FRAME AND LEAF - FULL WEATHER SEAL - PAINT GRADE
R802	ELEV. MACH. RM 1 & 2	3'-0"	7'-0"	1 3/4"	1	HM	-	ALUM	HM	-	STORAGE	Yes	GALV. & INSULATED FRAME AND LEAF - FULL WEATHER SEAL - PAINT GRADE

DOOR SCHEDULE - UNITS

DOOR No.	DOOR W	DOOR H	DOOR THICK	DOOR TYPE	DOOR MAT'L	FRAME HEAD/ JAMB	FRAME THRES	FRAME MAT'L	LABEL	OPER.	CL.	REMARKS
U	3'-0"	7'-0"	1 3/4"	21	SCWD	G/G1	-	HM - FL	20 MINS	HOTEL - GUEST ROOM	Yes	-
U1	3'-0"	7'-0"	1 3/4"	22	SCWD	B/B1	-	HM - FL	-	HOTEL - BATH	No	-
U1 - ADA	3'-0"	7'-0"	1 3/4"	22	SCWD	B/B1	-	HM - FL	-	HOTEL - BATH	No	-
U1.1	2'-8"	7'-0"	1 3/4"	22	SCWD	B/B1	-	HM - FL	-	HOTEL - BATH	No	-
U2	2'-6"	7'-0"	1 3/8"	23	SCWD	B/B1	-	HM - FL	-	PASSAGE	No	-
U3	3'-0"	7'-0"	1 3/4"	24	SCWD	B/B1	-	HM - FL	20 MINS	HOTEL - ADJOINING DR	No	PEMKO - SMOKE SEAL
U4	3'-0"	7'-0"	1 3/4"	24	SCWD	B/B1	-	HM - FL	AS NOTED	HOTEL - BED RM	No	-
U6			1 3/4"	11	GLASS	-	-	GLASS	-	SHOWER	No	FRAMELESS GLASS SHOWER DOOR

NOTES

ALL DOOR LEAFS ARE TO BE SOLID STILES AND RAILS WITH STAIN-GRADE VENEER PANEL, U.N.O.

STEEL AND GLASS DOOR SYSTEMS: SEE FINISH SCHEDULE FOR GLAZING TREATMENT

SEE FINISH SCHEDULE FOR LAMINATE GLAZING NOTES

ALL GUEST ROOM CLOSET LEAFS AND BATHROOM STALL LEAFS TO BE 1 3/8" THICK

ALL CLOSET DOORS ARE TO BE OPERABLE

ALL DOORS ARE TO BE PAINT-GRADE, U.N.O.

ALL DOORS OPENING FROM STAIRS A&B TO LEVELS 2-7 ARE TO BE RESTRICT ACCESS TO GUESS ROOM SPACES VIA CARDSWIPE. PROVIDE FAIL SAFE / PANIC BAR FUNCTION FROM CORRIDOR INTO STAIR WELL, TYPICAL.

LEAF GLAZING IS TO BE CLEAR TEMPERED U.N.O.

2 FRAME TYPES
1/4" = 1'-0"

REF. SH. NO : FULL SHEET ADD. NO : 2

SK-02

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/22/14

Prepared For:
119 Development, LLC
P.O. Box 7486
Portland, ME 04112

Consultant:

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
PRESS HOTEL
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:
1 13_10-14 Issue for Bid & Marriott Revw

Scale: As indicated

Date: 23 OCT 13

DOOR SCHEDULE

ADDENDUM
A8.01