FOODSERVICE EQUIPMENT SCHEDULE

MK.	QTY	DESCRIPTION	ELECTRICAL						WATER		WASTE		GAS		STEAM				VENTILATION				REMARKS
																			EXHAUST		MAKE-UP AIR		
			FLAMPS	KW	HP	VOLTS	PHASE	DIRECT PLUG	COLD	HOT	DIRECT	INDIRECT	SIZE	MBTUH	LBS/HR	PSIG	INLET	RETURN	SIZE	CFM	SIZE	CFM	
1	7	SHELVING UNIT																					
2	1	MOP SINK							1/2"	1/2"	2"												
3	2	REFRIGERATOR, 2-SECTION (REMOTE)	5.0			115	1	X															
4	2	HAND SINK							1/2"	1/2"	1-1/2"												
5	1	SINK, 3-COMPARTMENT							2@1/2"	2@1/2"	3@2"												
6	1	DISHTABLE, SOILED							1/2"	1/2"	2"												
7	1	SLANT RACK SHELF																					
8	1	DISPOSER	3.3		2	208	3	X	1/2"		2"												
9	1	DISHWASHER, DOOR-TYPE, VENTLESS	45.4			208	3	X	1/2"	1/2"	1-1/2"												
10	1	DISHTABLE, CLEAN																					
11	1	PASS-THRU SHELF																					
12	–	– SPARE NUMBER –																					
13	1	CHEF'S COUNTER, (FRYER SIDE)	10.0			115	1	X	1/2"	1/2"		2"											
			10.0			115	1	X															
14	4	WALL SHELF																					
15	1	CHEF'S COUNTER, (BROILER SIDE)	10.0			115	1	X	1/2"	1/2"		2"											
			5.0			115	1	X															
16	1	RANGE, ISLAND SUITE											1-1/2"	788									
17	1	STEAMER, CONVECTION	1.0			120	1	X					1/2"	60									
18	1	EXHAUST HOOD	15.0			120	1	X											1@12" X 23"	2783	2@10" X 14"	835	
			15.0			120	1	X											1@12" X 18"	2156	2@10" X 11"	647	
19	1	WORK COUNTER																					
20	3	BACK BAR COOLER (REMOTE)	5.0			115	1	X															
21	4	P.O.S. SYSTEM (BY OTHERS)	5.0			120	1	X															
22	–	– SPARE NUMBER –																					
23	1	UNDERBAR, DRY WASTE CHUTE																					
24	3	UNDERBAR, SODA GUN HOLDER																					
25	1	UNDERBAR, ICE BIN										1.5",3/4"											
26	1	UNDERBAR, SPEED RAIL																					
27	2	UNDERBAR, HAND SINK							1/2"	1/2"	1-1/2"												
28	1	UNDERBAR, SINK, 3-COMP.							1/2"	1/2"	3@1.5"												
29	1	UNDERBAR, CORNER DRAINBOARD										1-1/2"											
30	1	UNDERBAR, BLENDER STATION	15.0			115	1	X	1/2"	1/2"		1-1/2"											
31	1	UNDERBAR, ICE BIN, PASS-THRU										3/4"											
32	1	UNDERBAR, DRAINBOARD/GLASS RACK										1-1/2"											
33	1	UNDERBAR, DRY WASTE CHUTE																					
34	–	– SPARE NUMBER –																					
35	–	– SPARE NUMBER –																					
36	1	BEVERAGE COUNTER	15.0			120	1	X	1/2"	1/2"	2"												
37	1	WATER AND ICE STATION							1/2"			1",5/8"											
38	1	COFFEE BREWER (BY VENDOR)	25.8	6.3		120/240	1	X	3/8"														
39	1	EXPRESSO MACHINE	14.0	3.0		208	1	X	3/8"			1-1/4"											
40	–	– SPARE NUMBER –																					
41	–	– SPARE NUMBER –																					
42	–	– SPARE NUMBER –																					
43	–	– SPARE NUMBER –																					
44	–	– SPARE NUMBER –																					
45	–	– SPARE NUMBER –																					
46	–	– SPARE NUMBER –																					
47	–	– SPARE NUMBER –																					
48	–	– SPARE NUMBER –																					
49	–	– SPARE NUMBER –																					
50	1	SHEET PAN RACK																					
51	1	SHELVING UNIT																					
52	1	HEATED/HOLDING CABINET	16.0	2.0		120	1	X															
53	1	VENTLESS HOOD SYSTEM	8.0		1-1/2	208	1	X															
54	2	INDUCTION COOK TOP	30.0	10.0		208	3	X															
55	1	INDUCTION COOKTOP CABINET																					
56	1	COMBI-OVEN	86.0	31.0		208	3	X	3/4"			2"											
									3/4"														
57	1	REFRIGERATOR, 2-SECTION	6.5		1/3	115	1	X															
58	1	MIXER, 30-QUART	5.7		3/4	208	1	X															
59	1	WORK TABLE W/SINK							1/2"	1/2"		2"											
60	2	WALL SHELF																					
61	1	HAND SINK							1/2"	1/2"	1-1/2"												
62	–	– SPARE NUMBER –																					
63	–	– SPARE NUMBER –																					
64	–	– SPARE NUMBER –																					
65	–	– SPARE NUMBER –																					
66	–	– SPARE NUMBER –																					
67	–	– SPARE NUMBER –																					
68	–	– SPARE NUMBER –																					
69	–	– SPARE NUMBER –																					
70	3	SHELVING UNIT																					
71	1	P.O.S. SYSTEM (BY OTHERS)	5.0			120	1	X															
72	1	BACK BAR COOLER	7.2		1/3	115	1	X															
73	1	UNDERBAR, DRAINBOARD/GLASS RACK										1-1/2"											
74	1	UNDERBAR, ICE BIN										1.5",3/4"											
75	1	UNDERBAR, SPEED RAIL																					
76	1	UNDERBAR, SODA GUN HOLDER																					
77	1	UNDERBAR, BLENDER STATION	15.0			115	1	X	1/2"	1/2"		1-1/2"											
78	1	UNDERBAR, STORAGE CABINET										1-1/2"											
79	1	UNDERBAR, HAND SINK							1/2"	1/2"	1-1/2"												
80	1	UNDERBAR, DRY WASTE CHUTE																					
81	1	UNDERBAR, SINK, 3-COMP.							1/2"	1/2"	3@1.5"												
82	–	– SPARE NUMBER –																					
83	–	– SPARE NUMBER –																					
84	–	– SPARE NUMBER –																					
85	–	– SPARE NUMBER –																					
86	–	– SPARE NUMBER –																					
87	–	– SPARE NUMBER –																					
88	–	– SPARE NUMBER –																					
89	–	– SPARE NUMBER –																					
90	1	ICE MACHINE W/BIN	16.9			208	1	X	3/8"			3/4",1/2"											1/2" RECIRCULATING COLD WATER IN AND OUT
91	2	UTILITY CART																					
92	–	– SPARE NUMBER –																					
93	11	SHELVING UNIT																					
94	4	DUNNAGE RACK																					
95	1	WALK-IN COOLER (PRODUCE)	1.5			120	1	X															
96	1	EVAPORATOR COIL, COOLER	1.8			115	1	X				3/4"											
97	1	WALK-IN COOLER (MEAT)	1.5			120	1	X															
98	1	EVAPORATOR COIL, COOLER	1.8			115	1	X				3/4"											
99	1	WALK-IN FREEZER	1.5			120	1	X															
100	1	EVAPORATOR COIL, FREEZER	4.3	0.5		115	1	X				3/4"											
			8.8			208	1	X															
101	11	SHELVING UNIT																					
102	1	WALK-IN COOLER (BEER)	1.5			120	1	X															
103	1	EVAPORATOR COIL, COOLER	1.8			115	1	X				3/4"											
104	1	KEG STORAGE RACK																					
105	3	SHELVING UNIT																					
106	2	BAG-N-BOX RACK (BY VENDOR)	15.0			120	1	X	1/2"														
			15.0			120	1	X															
107	–	– SPARE NUMBER –																					
108	–	– SPARE NUMBER –																					
109	–	– SPARE NUMBER –																					
110	1	COMPRESSOR RACK, WATER-COOLED	54.2			208-230	3	X															1-1/2" RECIRCULATING COLD WATER IN AND OUT

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/22/14

Prepared For:
119 Development, LLC

Consultant:

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
PRESS HOTEL
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:

1	13_07-01	30% Marriott Submission
2	13_09-09	60% Marriott Sub. & Pric.
3	13_10-14	Issue for Bid & Marriott Revw

Scale: None

Date: 22 OCT 13

Foodservice Equipment
Mechanical Schedule

FS-2