1 | UNITS 221, 321, 421 & 521 - PLUMBING

SCALE: 1/4"=1'-0"

2 | UNITS 219, 217, 319, 317, 419, 417, 519 & 517 - PLUMBING

SCALE: 1/4"=1'-0"

3 | UNITS 216, 316, 416 & 516 - PLUMBING

SCALE: 1/4"=1'-0"

4 | UNITS 214, 314, 414, 514 & 614 - PLUMBING

SCALE: 1/4"=1'-0"

| | | |
|---|---|---|
| ALL WC SHALL HAVE 3" WASTE STACKS AND 2" VENT STACK. ALL LAV AND SHOWER SHALL HAVE 2" WASTE AND VENT STACKS. | PROVIDE EACH FCU WITH 1 1/2" CONNECTION (TYPICAL ALL FCU ALL FLOORS). | CONNECT ALL 1 1/2" IW W/ SAN. TEE ABOVE TRAP ON SH (TYPICAL ALL FCU ALL FLOORS). |
| DROP WATER RISERS DN. AT LAVATORY. LOCATE BALL VALVES AND BALL COCK IN WALL WITH ACCESS PANEL. (TYPICAL ALL SECOND FLOORS). | PROVIDE WCO AT BASE OF ALL WASTE STACKS. | WASTE, VENT, CONDENSATE AND WATER RISERS OFFSETS ARE NOT INDICATED. PROVIDE OFFSETS AS REQUIRED. |

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/22/14

Prepared For:
119 Development, LLC
P.O. Box 7468
Portland, ME 04112

Consultant:
CRABTREE ENGINEERING
278 AMELIA COVE
COLLIERVILLE, TN. 38017
PLUMBING: bobbygookin@gmail.com

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
PRESS HOTEL
390 CONGRESS STREET
PORTLAND, ME 04101

Revisions:

| | | |
|---|---|---|
| 1 | 13_10-14 | Issue for Bid & Marriott Revw |
| 2 | 13_10-21 | Addendum #2 |
| 3 | 13_10-31 | Addendum #3 |

Scale: 1/4" = 1'-0"

Date: 13 October 2013

TYPICAL GUESTROOMS PLUMBING

P7.02