Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 10/08/15

Nature Conservancy
45 Exchange Street
Suite 303
Proposed Alterations
Specifications for Construction
August 17, 2015

CARPENTRY:

1. Cut new opening at location marked "B" on plan. Install LH door and frame from location "C" for the new Suite entrance.
2. Remove wood door slab only of the remaining door located at "C" to create an unobstructed hallway.
3. Fill in and tape arched wall opening at location "A" using 3-1/2" metal studs and 5/8" fire code drywall on each side.
4. All other existing doors to remain.

ELECTRICAL:

1. Install exit signs at both exits of main Suite door and at rear exit corridor.
2. Confirm existing emergency lighting is adequate. Rework if necessary.

SPRINKLERS:

1. No work required as layouts remain the same.

HVAC:

1. No work required.