

PROJECT DIRECTORY

TENANT SEAMUS FINN LLC
 175 Spurwink Road,
 Scarborough, Maine 04074
 P: 207.761.0555
 Email: smcorry@msn.com

GENERAL CONTRACTOR RAM II Renovators
 17 Tenney Lane
 Scarborough, Maine 04074
 P: 207.761.0555
 Email: merriman62@gmail.com

ARCHITECT MARK MUELLER ARCHITECTS
 100 COMMERCIAL STREET
 SUITE #207
 PORTLAND, MAINE 04101
 P: 207.774.9057
 F: 207.773.3851
 Email: matt@muellerarchitects.com


AREA OF NEW WORK

KEY PLAN 1/8" = 1'-0"


NFPA 101 2009 & 220 2006 CODE DATA	
USE GROUP CLASSIFICATION	MERCANTILE CLASS C
TYPE OF CONSTRUCTION	II (2,000)
EXISTING BUILDING AREA	9,094 SF
PROPOSED BUILDING AREA	9,094 SF
TOTAL AREA OF WORK	2,000 SF
BUILDING HEIGHT (STORES/ FEET)	3 STORES/ 49'-6"
BUILDING AREA LIMITATION - SQ FT	3,000 SF (PER CLASS C)
BUILDING HEIGHT LIMITATION - STORES	NONE
TRAVEL COMMON PATH LIMIT (ALLOWABLE/ ACTUAL)	100/29'-0"
TRAVEL DEAD-END LIMIT (ALLOWABLE/ ACTUAL)	50/NONE
TRAVEL EXIT ACCESS TRAVEL DISTANCE LIMIT (ALLOWABLE/ ACTUAL)	300/7'-5"
FIRE SUPPRESSION SYSTEM	YES, PER NFPA B
NUMBER OF REQUIRED EXITS	2 EACH FLOOR
EXIT ACCESS FIRE RATINGS	
FIRE WALLS/ BARRIERS	
OCCUPANCY SEPARATION	1 HR.
PARTY WALLS	0 HR.
STAR ENCLOSURES	1 HR.
SHAFTS	1 HR.
EXIT ACCESS CORRIDORS	0 HR.
FIRE PROTECTION OF STRUCTURE	
COLUMNS	0 HR.
BEAMS, GIRDERS, TRUSSES & ARCHES	0 HR.
LOAD BEARING WALLS - EXTERIOR	2 HR.
LOAD BEARING WALLS - INTERIOR	0 HR.
NON-LOAD BEARING WALLS - EXTERIOR	0 HR.
NON-LOAD BEARING WALLS - INTERIOR	0 HR.
FLOOR CONSTRUCTION	0 HR.
ROOF CONSTRUCTION	0 HR.
OCCUPANT LOAD	45 People
FIRST FLOOR: KITCHEN/ EMPLOYEE AREA	673 SF 00 SF/ PERSON = 6
FIRST FLOOR: SEATING AREA (LOAD PER FURNITURE LAYOUT)	858 SF SF/ PERSON = 37
FIRST FLOOR: GENERAL AREA	509 SF 00 SF/ PERSON = 5

IBC 2009 CODE DATA	
USE GROUP CLASSIFICATION	BUSINESS (B)
TYPE OF CONSTRUCTION	2B
EXISTING BUILDING AREA	9,094 SF
PROPOSED BUILDING AREA	9,094 SF
TOTAL AREA OF WORK	2,000 SF
BUILDING HEIGHT (STORES/ FEET)	3 STORES/ 49'-6"
BUILDING AREA LIMITATION - SQ FT (TABLE 503)	9,000 SF
BUILDING HEIGHT LIMITATION - STORES (TABLE 503)	3 STORES
INCREASE STREET FRONTAGE (80% AREA) - SQ FT	N/A
INCREASE AUTOMATIC SPRINKLER SYSTEM HEIGHT (1 STORY)	YES (N/A)
TRAVEL COMMON PATH LIMIT (ALLOWABLE/ ACTUAL)	100/29'-2"
TRAVEL DEAD-END LIMIT (ALLOWABLE/ ACTUAL)	50/NONE
TRAVEL EXIT ACCESS TRAVEL DISTANCE LIMIT (ALLOWABLE/ ACTUAL)	400/54'-9"
FIRE SUPPRESSION SYSTEM	YES, PER NFPA B
NUMBER OF REQUIRED EXITS	2 EACH FLOOR
EXIT ACCESS FIRE RATINGS	
FIRE WALLS/ BARRIERS	
OCCUPANCY SEPARATION	0 HR.
PARTY WALLS	0 HR.
STAR ENCLOSURES	1 HR.
SHAFTS	1 HR.
EXIT ACCESS CORRIDORS	0 HR.
FIRE PROTECTION OF STRUCTURE	
PRIMARY STRUCTURAL FRAME	0 HR.
SECONDARY STRUCTURAL FRAME	0 HR.
LOAD BEARING WALLS - EXTERIOR	2 HR.
LOAD BEARING WALLS - INTERIOR	0 HR.
NON-LOAD BEARING WALLS - EXTERIOR	0 HR.
NON-LOAD BEARING WALLS - INTERIOR	0 HR.
FLOOR CONSTRUCTION	0 HR.
ROOF CONSTRUCTION	0 HR.
OCCUPANT LOAD	45 People
FIRST FLOOR: KITCHEN/ EMPLOYEE AREA	673 SF 200 SF/ PERSON = 3
FIRST FLOOR: SEATING AREA (LOAD PER FURNITURE LAYOUT)	858 SF SF/ PERSON = 37
FIRST FLOOR: GENERAL AREA	509 SF 00 SF/ PERSON = 5

AREA OF NEW WORK



KEY SECTION N. T. S.



STAIR ELEVATION 1/2" = 1'-0"

LIFE SAFETY LEGEND:

- EXIT LIGHT
- EMERGENCY BACKUP LIGHT
- SMOKE DETECTOR, BUSINESS
- HEAT & CO DETECTOR
- HORN/STROBE
- STROBE
- FIRE EXTINGUISHER IN RECESSED CABINET
- PULL STATION
- ELEC. RECEPTACLE (INSTALL PER CODE & AS SHOWN)

- LIFE SAFETY AND FIRE ALARM SYSTEMS SHALL BE RECONFIGURED AND INSTALLED PER NFPA 72 AND PER CITY OF PORTLAND CODE.

- A SEPARATE PERMIT AND CITY APPROVED CONTRACTOR IS REQUIRED.


- ALL STROBES TO BE 30 CANDELA UNLESS OTHERWISE NOTED.

- SYSTEM SHALL BE SUPERVISED BY AN OFF-SITE CERTIFIED BY THE CITY OF PORTLAND THIRD PARTY


- INTEGRATE NEW EQUIPMENT INTO EXISTING SYSTEM PER PERMIT #2014-00090

GENERAL NOTES



- THE BUILDING SHALL BE CONSTRUCTED TO CONFORM WITH ALL CURRENT APPLICABLE CODES INCLUDING, BUT NOT LIMITED TO, THE LATEST EDITIONS OF IBC, IECC, NFPA 101, ANSI, UFAS, HUD/AG, ADA/AG, MPS.
- ALL WOOD IN CONTACT WITH CONCRETE SHALL BE TREATED WITH PRESSURE PRESERVATIVE.
- CONTRACTOR SHALL WORK FROM GIVEN DIMENSIONS AND LARGE SCALE DETAILS ONLY. DO NOT SCALE THE DRAWINGS.
- INSTALL BLOCKING FOR SURFACE APPLIED FIXTURES, TRIM, CABINETS, COUNTER TOPS, AND GRAB BARS WHEN MOUNTED ON STUD WALLS, INCLUDING ALL FUTURE INSTALLATIONS.
- ALL GRAB BARS SHALL BE ABLE TO SUPPORT A DEAD WEIGHT OF 250 LBS AT ANY POINT.
- INSTALL MOISTURE RESISTANT GYPSUM BOARD IN HOUSEKEEPING, UTILITY, STORAGE, SPRINKLER AND ALL OTHER HIGH HUMIDITY AREAS, INCLUDING UNIT BATHROOMS. MOISTURE RESISTANT FIRE RATED G.W.B. @ ALL FIRE RATED WALLS COMMON WITH HOUSE UTILITY AND UNIT BATH ROOMS. IF APPLICABLE TO THIS PROJECT, SHOWERS TO HAVE DURAROCK BACKING ALL SIDES. ALL CAULKING AROUND WINDOWS SHALL BE NON-HARDENING TYPE SEALANT.
- INSTALL U.L. SLEEVE FIRE-STOPPING SYSTEM & FIRE RATED SEALANTS EQUAL TO THE FIRE RATED FLOOR, CEILING AND WALL ASSEMBLY.
- FIRESTOP VERTICAL MECHANICAL CHASES @ FLOOR & CEILING U.L. RATED PENETRATIONS. CAULK JOINTS. COORDINATE AND FLASH ALL ROOF/WALL PENETRATIONS WITH THE SUB-TRADES.
- CONTINUE SEPARATION WALLS TO UNDERSIDE OF FLOOR/CEILING ABOVE. UNIT TO UNIT, UNIT TO CORRIDOR, CORRIDOR WALLS, STORAGE WALLS, ELEVATOR, STAIRWELL WALLS, ETC.
- PROJECT ASSUMES ALL EXISTING HAZARDOUS MATERIALS HAVE BEEN REMOVED PRIOR TO THE COMMENCEMENT OF WORK. ALL HAZARDOUS MATERIAL REMOVAL IS THE RESPONSIBILITY OF THE OWNER.
- DESIGNATED EGRESS WINDOWS IN SLEEPING ROOMS SHALL MEET THE FOLLOWING MINIMUM CLEAR OPENING REQUIREMENTS OF 22" WIDE, 24" HIGH & 5.7 SF CLEAR OPENING. ALL BEDROOMS SHALL CONTAIN A MINIMUM OF (1) EGRESS OPENING. (NOT APPLICABLE TO THIS PROJECT).
- WINDOW SAFETY GLAZING SHALL BE LOCATED AS FOLLOWS, BUT NOT LIMITED TO:
 ALL WINDOWS WITHIN 60" HORIZ. & VERT. DIMENSION OF STAIRS MUST BE TEMPERED.
 ALL WINDOWS WITHIN 24" OF A DOOR SWING MUST BE TEMPERED.
 ALL WINDOWS WITHIN A SHOWER ENCLOSURE MUST BE TEMPERED.
- BUILDING INSULATION SHALL BE PROVIDED AS INDICATED & NOTED IF NOT SHOWN IN ITS ENTIRETY THROUGHOUT THE DRAWING SET. ISULATE ALL BATHROOM, LAUNDRY, MECH. ROOM WALLS, AND ROOF DRAINS THRU BUILDING. BEAM JOIST OR OTHER STRUCTURAL MEMBER PENETRATIONS NOT SHOWN OR INDICATED ON DRAWINGS MUST BE CONSULTED WITH THE ARCHITECT & OR ENGINEER PRIOR TO WORK.
- ANY CHANGE DURING CONSTRUCTION OF USE, OCCUPANCY OR CONSTRUCTION TYPE MUST BE DISCUSSED WITH ARCHITECT PRIOR TO ANY WORK PERFORMED AND SUBSTANTIAL TIME ALLOWED FOR REQUIRED CODE RESEARCH AND DRAWING MODIFICATIONS OR ADDITIONS.
- REPORT ANY AND ALL DISCREPANCIES TO THE ARCHITECT PRIOR TO PROCEEDING WITH WORK.



ENLARGED BATH PLAN 1/2" = 1'-0"



LOWER LEVEL PLAN N. T. S.





PROJECT NOTES


- SCOPE OF WORK SHALL INCLUDE INTERIOR TENANT FIT-UP FOR PATISSERIE. WORK TO INCLUDE NEW INTERIOR PARTITIONS, NEW CEILING AND NEW MILLWORK AS SHOWN.
- HISTORIC PRESERVATION NOT REQUIRED. NO EXTERIOR WORK PROPOSED. EXTERIOR SIGNAGE NOT PART OF THIS PERMIT.
- ALL NEW WORK SHALL CONFORM TO THE CITY OF PORTLAND INSPECTION, FIRE AND ZONING REQUIREMENTS.
- THE GENERAL CONTRACTOR (GC) SHALL BE RESPONSIBLE FOR ALL INTERIOR WORK. GC TO OBTAIN ALL NECESSARY PERMITS FOR THE CONSTRUCTION, INCLUDING BUT NOT LIMITED TO, STREET CLOSINGS, ELECTRICAL, MECHANICAL, SPRINKLER SYSTEMS, AS REQUIRED. GC TO MODIFY MECHANICAL, ELECTRICAL, PLUMBING AND SPRINKLER SYSTEMS ACCORDING TO ARCHITECT'S ENGINEER'S PLANS.
- BASED ON ARCHITECT'S FLOOR PLAN, LIFE SAFETY SYSTEM INSTALLER SHALL SUBMIT LIFE SAFETY PLANS TO THE STATE OF MAINE AND THE CITY OF PORTLAND FOR APPROVAL.
- FIRE ALARM WORK SHALL BE INSTALLED BY A STATE CERTIFIED CONTRACTOR. FIRE ALARM WORK TO MEET NFPA 72, CITY OF PORTLAND AND STATE FIRE MARSHAL REQUIREMENTS.
- ALL FIRE RATED PENETRATIONS SHALL BE FIRE STOPPED WITH UL APPROVED SYSTEMS. ALL INTERIOR FINISHES TO MEET NFPA 701.
- CONTRACTOR SHALL ADHERE TO BUILDING RULES AND REGULATIONS AGREEMENT FOR INTERIOR CONSTRUCTION AS PROVIDED BY THE BUILDING'S PROPERTY MANAGEMENT.
- CONTACT THE ARCHITECT PRIOR TO WORK SHOULD DISCREPANCIES BE DISCOVERED DURING THE BUILDING PROCESS.
- RECONFIGURE SPRINKLER SYSTEM PER NEW PLAN & PER NFPA 13.

DEMOLITION NOTES

- ELECTRIC POWER TO THE TENANT SPACE ONLY SHALL BE DISCONNECTED PRIOR TO ANY DEMOLITION. VERIFY WATER SHUT-OFF W/ BUILDING OWNER. EXISTING DUCT WORK TO REMAIN SHALL BE SEALED. SPRINKLER SYSTEMS, WHERE APPLICABLE, SHALL REMAIN OPERATIONAL UNLESS PERMITTED BY THE CITY BUILDING INSPECTOR. FIRE ALARM SYSTEMS TO REMAIN FULLY OPERATIONAL DURING DEMOLITION.
- DUST BARRIER PARTITIONING SHALL BE INSTALLED @ TENANT SEPARATIONS.
- ALL DEMOLITION SHALL BE REMOVED FROM THE REAR/ SIDE OF THE BUILDING ONLY.
- ALL FIRE PROTECTION (IF EXISTING), GYPSUM DRYWALL & OR FIRESPRAY ON STRUCTURAL MEMBERS SHALL REMAIN. BEARING WALLS, FIRE SEPARATION WALLS, BEAMS, COLUMNS & FIRE RATED FLOOR/ CEILING ASSEMBLIES SHALL NOT BE REMOVED.
- PROTECT ALL FINISHES, MATERIALS AND EQUIPMENT NOTED AS EXISTING TO REMAIN.
- DIMENSIONS INDICATED +/- ARE EXISTING CONDITION DIMENSIONS TO BE FIELD VERIFIED.
- REMOVE EXISTING PLUMBING FIXTURES IF ANY. VENTING AND ASSOCIATED EXHAUST FANS, CAP PLUMBING FLUSH WITH FLOOR. (NOT APPLICABLE TO THIS PROJECT).
- FIELD VERIFY ALL STRUCTURAL COMPONENTS PRIOR TO DEMOLITION. REPORT ANY DISCREPANCIES IMMEDIATELY TO ARCHITECT.



**FLOOR PLAN
1/4" = 1'-0"**
REVISED: JANUARY 09, 2015
FOR CONSTRUCTION: NOVEMBER 26, 2014



MARK MUELLER ARCHITECTS
 A.I.A.
 100 Commercial Street
 Suite 205
 Portland, Maine 04101
 Phone/ Fax 207.774.9057
 Email: rfr@muellerarchitects.com

© COPYRIGHT 2014
 MARK MUELLER ARCHITECTS

PATISSERIE
 46 MARKET STREET
 PORTLAND, MAINE

INTERIOR TENANT FIT-UP FOR:

REVISED	DATE	PROJECT	DRAWN BY	CHECK BY
	NOV 2014	46 MARKET	JME	MLM

A.1