



Professional Seal

Professional Seal

Revisions

SPECIAL NOTICE:
In the event the client consents to, allows, authorizes or approves of changes to any plans, specifications or other construction documents, and these changes are not approved in writing by the design professional, the client recognizes that such changes and the results thereof are not the responsibility of the design professional. Therefore, the client agrees to release the design professional from any liability arising from the construction, use or result of such changes. In addition, the client agrees to the fullest extent permitted by law, to indemnify and hold the design professional harmless from any damage, liability or cost (including reasonable attorney's fees and costs of defense) arising from such changes.

Copyright © 2013 by GODWIN + ASSOCIATES. All rights reserved. No part of this drawing may be reproduced by photocopy or by any other means, or stored, processed, or transmitted in or by any computer or other systems without the prior written permission of GODWIN + ASSOCIATES.

Project Number: 43115
Drawn By: PMM
Reviewed By: JAG
Date: 11.26.13

orange leaf
363 Fore Street
Portland, Maine 04101

**Interior Finish
Legend, Finish
Schedule**

CONSTRUCTION DOCUMENTS
Sheet Number

A2.2

INTERIOR FINISH LEGEND

WALL FINISHES

ABBREVIATIONS	DESCRIPTION	MANUFACTURER	MODEL NUMBER	COLOR	STYLE	REMARKS
P1	PAINT	BEHR	400B-5	GRAPE GREEN		RESTROOM WALLS (EPOXY PAINT ON RESTROOM WALLS) AND SOME SOFFIT CLOUDS
P2	PAINT	BEHR	400B-7	LEMON GRASS		SALES AND DINING AREAS
P3	PAINT	BEHR	370E-1	COUNTRY DAIRY		PREP WALLS, OFFICE WALLS (EPOXY PAINT ON PREP WALLS), STORAGE WALLS
P4	PAINT	BEHR	S-G 240	DRAGON FIRE		SOFFIT ABOVE YOGURT MACHINES AND SOME SOFFIT CLOUDS
P5	PAINT	BEHR	420B-7	PEPPER GRASS		METAL DOOR FRAMES
T1	GLASS TILE	SARK TILE	ORANGE LEAF ORAN			MACHINE WALL TILE (FIELD) MOSAIC SHEET SIZE 12 1/2"x12 1/2" / SHEET (1.085 S.F.) CONTACT JACKIE BERAN (402)475-1300 - EMAIL: jackie@sarktile.com
T2	GLASS TILE	HIRSCH GLASS	HIRSGT T00358-2			MACHINE WALL TILE (ACCENT) STAINED GLASS SERIES 2"x2" CONTACT SAMANTHA ROBERTS (405)596-5522 - EMAIL: samantha.roberts@mostertile.com - LEAD TIME 7 DAYS

CEILING FINISHES

ABBREVIATIONS	DESCRIPTION	MANUFACTURER	MODEL NUMBER	COLOR	STYLE	REMARKS
C1	ACCOUSTICAL CEILING TILE	CELOTEX		BLACK	REVEAL EDGE	ALL PUBLIC AREAS - INSTALL CHICAGO METALLIC SNAP GRID 200 (2'-0" x 2'-0") CEILING GRID WITH 12 GA. SUSPENSION WIRES
C2	ACCOUSTICAL CEILING TILE	CELOTEX		WHITE	VINYL FACE	PREP AREA - INSTALL CHICAGO METALLIC SNAP GRID 200 (2'-0" x 4'-0") CEILING GRID WITH 12 GA. SUSPENSION WIRES (WASHABLE VINYL FACE CEILING PANELS)
C3	ACCOUSTICAL CEILING TILE	CELOTEX		WHITE	REVEAL EDGE	RESTROOMS & OFFICE LOCATIONS - INSTALL CHICAGO METALLIC SNAP GRID 200 (2'-0" x 2'-0") CEILING GRID WITH 12 GA. SUSPENSION WIRES

FLOOR FINISHES

ABBREVIATIONS	DESCRIPTION	MANUFACTURER	MODEL NUMBER	COLOR	STYLE	REMARKS
V1	VINYL	NORTHWEST BUILDING SUPPLY	DW-1402	BLANCHED		SALES AREA, DINING AND RESTROOMS CONTACT LORISHA (405)946-0500
SC	SEALED CONCRETE					PREP AREA, OFFICE
VB	VINYL BASE		503	GINGER		4" TALL COVE BASE
VB2	VINYL BASE		503	GINGER		6" TALL COVE BASE

ROOM FINISH SCHEDULE

NO.	ROOM NAME	BASE		COLOR		FLOOR		COLOR		NORTH WALL		COLOR		EAST WALL		COLOR		SOUTH WALL		COLOR		WEST WALL		COLOR		CEILING		CEILING HEIGHT	REMARKS	NO.
		4" VINYL COVE	6" VINYL COVE	VB1	VB2	SEALED CONCRETE	SHEET VINYL	SC	V1	GYPSUM BOARD PAINTED	P1	P2	P3	GYPSUM BOARD PAINTED	P1	P2	P3	GYPSUM BOARD PAINTED	P1	P2	P3	GYPSUM BOARD PAINTED	P1	P2	P3	P4, T1, T2	EXPOSED TO ROOF STRUCTURE			
01	LOWER PREP																											10'-0"±	--	01
02	MECH.																											10'-0"±	--	02
101	DINING																											11'-0"±	Glass Tile T1 & T2 @ Ygrt Mach. Walls	101
102	EXIST. TOILET																											9'-0"±	--	102
103	SALES																											10'-0"±	Glass Tile T1 & T2 @ Dbl Acting Dr Wall	103
104	PREP																											10'-0"±	--	104
201	STORAGE																											10'-0"±	--	201
202	OFFICE																											10'-0"±	--	202

ROOM FINISH NOTES

- PAINT ALL SIDES OF DOOR FRAMES.
- ALL GYPSUM BOARD SHALL BE 5/8" TYPE X, UNLESS OTHERWISE NOTED.
- GYPSUM BOARD IN ALL WET AREAS (PREP AREAS AND RESTROOMS) SHALL BE MOISTURE RESISTANT.
- ALL WOOD DOORS SHALL RECEIVE MINIMUM (2) COATS POLYURETHANE FINISH.
- PROVIDE AND INSTALL PICTORIAL SYMBOL RESTROOM SIGNAGE AT ALL RESTROOMS, INCLUDING HANDICAPPED SYMBOL.
- PROVIDE AND INSTALL TRANSITION STRIP(S) AS REQUIRED OR AS INDICATED ON PLAN.
- ALL INTERIOR FINISHES SHALL BE CLASS C OR BETTER (FLAME SPREAD 76-200). FINISHES IN EXIT CORRIDORS AND ENTRY SHALL BE CLASS B OR BETTER (FLAME SPREAD 26-75). ALL INTERIOR FINISH MATERIAL SHALL HAVE A SMOKE DEVELOPMENT RATING OF 450 OR LESS.
- THE GENERAL CONTRACTOR SHALL COORDINATE ALL INTERIOR FINISH COLORS WITH FINISH SCHEDULE AND OWNER.
- PAINT SHALL BE EQUAL TO - (1) PRIMER COAT, (2) COATS LATEX SATIN.
- PAINT IN WET AREAS (PREP AREA AND RESTROOMS) SHALL BE EPOXY.
- ALL CEILINGS TO BE 10'-0" A.F.F. UNLESS NOTED OTHERWISE.
- FIRE EXTINGUISHERS SHALL BE A MINIMUM OF 5 LB. 2A-10BC UL APPROVED PORTABLE FIRE EXTINGUISHER. INSTALL SO THAT ITS TOP IS NOT MORE THAN 5'-0" A.F.F.