

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

ELEVEN EXCHANGE LLC /Jack Seidman

Located at

9 (15) EXCHANGE ST

PERMIT ID: 2013-01632

ISSUE DATE: 07/29/2013

CBL: 032 F010001

has permission to **Install a Type 1 hood exhaust system at 15 Exchange: B-Good.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.	A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
---	--

/s/ Benjamin Wallace Jr

/s/ Tammy Munson

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

1st floor at #15 - restaurant use

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2013-01632	Date Applied For: 07/29/2013	CBL: 032 F010001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: Restaurant on 1st floor		Proposed Project Description: Install a Type 1 hood exhaust system at 15 Exchange: B-Good.		
Dept: Historic Status: Approved Reviewer: Robert Wiener Approval Date: 08/20/2013 Note: Staff talked with contractor 8/12/13. Seidman Brothers to send sketches of proposed installation on building's exterior. Ok to Issue: <input checked="" type="checkbox"/> Conditions:				
Dept: Zoning Status: Approved Reviewer: Marge Schmuckal Approval Date: 07/31/2013 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions:				
Dept: Fire Status: Approved w/Conditions Reviewer: Benjamin Wallace Jr Approval Date: 07/31/2013 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions: <ol style="list-style-type: none"> 1) The exhaust termination shall be a minimum 10 feet horizontally from property lines. 2) Hood suppression system shall comply with NFPA 17A, 96, and UL 300. Activation of the suppression system shall activate the fire alarm system if available. A letter of compliance will be required at the time of final inspection stating: the date the system was tested for operation, fuel gas shut off, and fire alarm connection if applicable. The Class K fire extinguisher and proper signage should be located at the suppression system pull station. 3) A separate Non-Water Based Suppression System permit is required. This review does not include approval of the suppression system design or installation. 4) Any cutting and welding done will require a Hot Work Permit from Fire Department. 5) Installation shall comply with City Code Chapter 10 and NFPA 96, Standard for ventilation Control and Fire Protection of Commercial Cooking Operations, 2008 edition. A signed letter of certification is required. 				