Inspection Division
Date: 05/09/14

1 WORK AREA
SCALE: 1/2"=1'-0"

2 WORK AREA
SCALE: 1/2"=1'-0"

4 DOOR ELEVATION
SCALE: 1/2"=1'-0"

5 CHECK DESK
SCALE: 1/2"=1'-0"

CONFIRM DOOR SWING

Materials
M1: $\frac{3}{4}$" White melamine
M2: $\frac{1}{4}$" White melamine
M3: $\frac{3}{4}$" White melamine w/ 1 side plastic laminate
M4: $\frac{3}{4}$" Particleboard w/ 2 sides plastic laminate
M5: 1" Particleboard w/ 2 sides plastic laminate
M6: $\frac{3}{4}$" Particleboard (built up to 1 $\frac{1}{2}$") w/ 1 side plastic laminate
M7: $\frac{1}{2}$ Solid surface (built up to 1 $\frac{1}{2}$")
M8: $\frac{3}{4}$" Cherry veneer particleboard - rift cut
M9: $\frac{1}{4}$" Cherry veneer particleboard - rift cut
M10: Solid cherry - rift cut
M11: Solid poplar
M12: $\frac{1}{4}$" Hardboard
M13: $\frac{1}{4}$" Clear tempered glass
M14: 3068 unfinished birch door - $\frac{1}{2}$" half glass
Hardware
H1: Stanley 4" wire pulls - satin aluminum finish
H2: Blum 120° hinges - nickel finish
H3: Knape & Vogt 8400 drawer slides - anochrome finish
H4: Knape & Vogt 8500 lateral drawer slides - anochrome finish
H5: Timberline locks
H6: Clear plastic shelf supports
H7: Knape & Vogt 82/182 standards & brackets - white finish
H8: Designer Suites adjustable moniter arm - #8038201 for 21" monitor
H9: Outwater Plastics wire grommets
Finishes
PL1: Plastic laminate (countertops) - to be selected
PL2: Plastic laminate (cabinets) - to be selected
SS1: Solid surface (countertops) - to be selected
SS2: Solid surface (countertops) - to be selected
WF1: Transparent finish (no stain)
Edgeband
EB1: 0.018" PVC edgeband (cabinet parts)
EB2: 3mm edgeband (doors & drawer fronts)
Notes
1. All dimensions to be field verified before construction.
2. All in-wall blocking by G.C.

Norway Savings Bank
Renovations

Exchange Street
Portland, ME

Trico Millwork Inc.
Architectural Woodwork & Design
TMI
TEL:(207)637-2711 FAX:(207)637-2727
Rt.25 Limington, Maine tricomillwork.com

Title
WORK AREA / CHECK DESK
PLANS & ELEVATIONS

Drawn By: MCN	Date: 3/24/14	AM 2.2
G.C.: Perspective Construction	Revision Date: 4/9/14	
Architect	Project #: 1234	