













Ceilings: ( to be confirmed by owner)  
 Grid: 9/16" Armstrong Suprafine  
 Ceiling Tile: Ultima High NRC

-  Exit Sign:  
DualLite LXURWE, with integral 90 minute battery. Mount unit directly above and centered on doors or openings, or ceiling mount where shown on plan
-  Emergency Lighting:  
DualLite LZ35-12 Volt with (2) 10 watt Halogen MR16 lamps and integral 90 minute battery pack, mounted at 7-6 A.F.F. and spaced not more than 29" on center
-  Alarm notification and device locations to be by separate permit. Submit cut sheets and layout to Architect. Provide visual alarm at accessible toilet room and other devices required. Devices shall be white in color

-  A1 2x2 LED recessed troffer with integral 0-10 volt LED dimming driver and 3500K LED
-  A2 similar to A1 but non dimming
-  A2 to be determined
-  A4 Recessed fluorescent troffer with regressed acrylic white lens in an aluminum frame. Provide flush frame for mounting in suspended grid ceilings. Provide integral non-dimming LED driver.
-  B
-  B\_NL NL=nightlight
-  D ELP CLC Series dimmable cove light, style C mounted on vertical face of soffit with mitered corner. Manufacturer to provide shop drawings. Lighting supplier shall provide light level calculations. Coordinate with HVAC grill.
-  E 4" square LED recessed downlight, dimmable
-  F LED tape on soundcloud

# 1 3rd Floor Ceiling Plan

3/16" = 1'-0"

**AZIMUTH LLC**  
 josef chalat  
 architect  
 327 ocean house road  
 Cape Elizabeth, Maine

office 207 799 0404  
 cell 207 318 3234

e: azimuth@maine.rr.com

LICENSED ARCHITECT  
 JOSEF  
 CHALAT  
 AR2354  
 STATE OF MAINE

© josef chalat, architect  
 2014 ∞ all rights reserved

April 6, 2015: Permit

**Kepware Technologies**  
 Tenant Improvements  
 3rd floor  
 400 Congress Street, Portland, Maine 04101  
 Contractor/Owner: A&M Partners,  
 120 Exchange Street Portland ME  
 CBL: 032 G001001, B3 Zoning District

3rd Floor Ceiling Plan

a2