

2009 NFPA: CODE DATA	
TYPE OF CONSTRUCTION	CH. 38 BUSINESS (EXISTING BUILDING)
OCCUPANT LOAD - RENOVATED AREA	TYPE II O.O.O (EXISTING) 803 S.F. /100 = 9 SF/PP
EXTERIOR BEARING WALLS	0 HOUR
EXTERIOR NONBEARING WALLS	0 HOUR
INTERIOR BEARING WALLS	0 HOUR
COLUMNS	0 HOUR
BEAMS, GIRDERS, TRUSSES	0 HOUR
FLOOR CONSTRUCTION	0 HOUR
FLOOR SEPARATION AT ASSEMBLY USE GROUP	1 HOUR
ROOF CONSTRUCTION	0 HOUR
MECHANICAL/ELECTRICAL ROOMS	0 HOUR
TENANT SEPARATION	0 HOUR
SYSTEMS ENGINEERING - PARTIAL FIRST FLOOR	803 S.F.
TOTAL FLOOR AREA - FIRST FLOOR	27,000 S.F. +/- TOTAL FLOOR
BUILDING HEIGHT	70' +/- - 6 STORIES
FIRE SUPPRESSION	YES
HAZARD	1 HOUR
FIRE EXTINGUISHERS	PER NFPA 2009
COMMON PATH OF TRAVEL LIMIT	75'
DEAD-END LIMIT	50'
TRAVEL DISTANCE LIMIT	200'
EXITS	
CORRIDOR WIDTH	36"
STAIR ENCLOSURES	1 HOUR
SHAFTS	1 HOUR
EXIT ACCESS CORRIDORS	0 HOUR
FLAME SPREAD RATINGS:	
INTERIOR FINISH REQUIREMENTS (SPRINKLERED BLDG)	
WALLS AND CEILINGS	CLASS A, B OR C
EXIT ACCESS CORRIDORS	CLASS A OR CLASS B
INTERIOR FLOOR FINISH REQUIREMENTS	
EXITS	CLASS I OR CLASS II (REDUCTION PERMITTED OF ONE CLASS IN SPRINKLERED BUILDING)
CORRIDORS	
GENERAL NOTES	1. ALL PENETRATIONS OF SMOKE BARRIERS, PARTITIONS, FIRE RATED WALLS AND FLOORS SHALL BE SEALED WITH PROPER APPROVED MATERIALS

2009 IBC: CODE DATA	
OCCUPANT LOAD	Business Occupancy (EXISTING BLDG) 803/100 = 9
USE GROUP CLASSIFICATION	BUSINESS
TYPE OF CONSTRUCTION	TYPE II B (EXISTING)
ACTUAL FLOOR AREA	27,000 S.F. - RENOVATED AREA IS 803 S.F.
TOTAL BUILDING AREA	150,000 SF +/-
ACTUAL BUILDING HEIGHT	70' +/-
EXIT ACCESS TRAVEL DISTANCE	200'-0"
DEAD END CORRIDORS	20'-0" / 50'-0" W/ FIRE SUPPRESSION SYSTEM
CORRIDOR WIDTH	36"
STAIRWAY WIDTH	44"
FIRE RATING:	
EXTERIOR BEARING WALLS	0 HOUR
INTERIOR BEARING WALLS	0 HOUR
NON-BEARING WALLS & PARTITIONS	0 HOUR
FLOOR CONSTRUCTION	0 HOUR
ROOF CONSTRUCTION	0 HOUR
CORRIDORS	0 HOUR
STAIR ENCLOSURES	1 HOUR
SHAFTS	1 HOUR FOR < 4 STORIES
UNIT SEPARATION	1 HOUR
MECHANICAL/ELECTRICAL ROOMS	1 HOUR
LAUNDRY/STORAGE > 100 SF	1 HOUR
WASTE COLLECTION > 100 SF	1 HOUR
FLAME SPREAD RATINGS:	
INTERIOR WALL & CEILING FINISH REQUIREMENTS	
EXIT ENCLOSURES & EXIT PASSAGeways	A
CORRIDORS	B
ROOMS OR ENCLOSED SPACES	C
INTERIOR FLOOR FINISH REQUIREMENTS	
EXIT ENCLOSURES & EXIT PASSAGeways	CLASS II
CORRIDORS	CLASS II
GENERAL NOTES	1. ALL PENETRATIONS OF SMOKE BARRIERS, PARTITIONS, FIRE RATED WALLS AND FLOORS SHALL BE SEALED WITH PROPER APPROVED MATERIALS 2. ALL WORK SHALL CONFORM TO LOCAL AND STATE CODES, ORDINANCES, AND REQUIREMENTS, ACCESSIBILITY PER A.D.A., A.G.