Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 11/06/14

SYSTEM OUTPUTS

CONTROL UNIT ACTIVATION | NOTIFICATION | REQUIRED FIRE SAFETY CONTROL

	SYSTEM INPUTS	A: ACTIVATE COMMON ALARM SIGNAL INDICATOR	B: ACTIVATE AUDIBLE ALARM SIGNAL	C: ACTIVATE COMMON SUPERVISORY SIGNAL INDICATOR	D: ACTIVATE AUDIBLE SUPERVISORY SIGNAL	E: ACTIVATE COMMON TROUBLE SIGNAL INDICATOR	F: ACTIVATE AUDIBLE COMMON TROUBLE SIGNAL	G: DISPLAY ALPHA-NUMERIC SYSTEM STATUS MESSAGE	H: RECORD EVENTS IN THE SYSTEM MEMORY	I: ACTIVATE GENERAL EVACUATION SIGNALS	J: SEND FIREFIGHTERS WARNING SIGNAL TO ELEVATOR CONTROLS	K: TRANSMIT FIRE ALARM SIGNAL TO REMOTE ALARM RECEIVING STATION	L: TRANSMIT SUPERVISORY SIGNAL TO REMOTE ALARM RECEIVING STATION	M: TRANSMIT TROUBLE SIGNAL TO REMOTE ALARM RECEIVING STATION	N: RECALL ELEVATORS TO PRIMARY RECALL FLOOR	O: RECALL ELEVATORS TO ALTERNATE RECALL FLOOR	P: RELEASE DOOR HOLDERS	
1	MANUAL FIRE ALARM PULL STATION	●	●					●	●	●		●					●	1
2	AREA SMOKE DETECTOR	●	●					●	●	●		●					●	2
3	ELEVATOR LOBBY SMOKE DETECTOR - PRIMARY FLOOR	●	●					●	●	●		●				●	●	3
4	ELEVATOR LOBBY SMOKE DETECTOR - ALTERNATE FLOOR	●	●					●	●	●		●			●		●	4
5	NAC POWER SUPPLY AC POWER FAILURE					●	●	●	●					●				5
6	NAC POWER SUPPLY LOW BATTERY					●	●	●	●					●				6
7	OPEN CIRCUIT					●	●	●	●					●				7
8	GROUND FAULT					●	●	●	●					●				8
9	NOTIFICATION APPLIANCE CIRCUIT SHORT					●	●	●	●					●				9
10	SERVER ROOM SUPPRESSION SYSTEM DISCHARGE	●	●					●	●	●		●					●	10
		A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	

REVISION 2	DATE:	
REVISION 1	DATE:	
REVISION 0 SUBMITTAL	DATE:	10/05/2014
FACP ADDITION WIRING RISER		
PROJECT NAME **KEPWARE FIT UP** 400 CONGRESS STREET PORTLAND, ME	SCALE NTS BY: JRS CK BY:	
NORRIS INC Prepared For Tomorrow; Delivered Today 2257 BROADWAY, SOUTH PORTLAND, MAINE	SAVED AS:	