

IBC OCCUPANCY CALCULATION			
OCCUPANCY LOAD	TOTAL SQUARE FOOTAGE	FLOOR AREA IN SF PER OCCUPANT	TOTAL OCCUPANTS
STANDING SPACE	1284 SF	5 NET	257
UN-CONCENTRATED ASSEMBLY SPACE	94 SF	15 NET	7
BUSINESS AREA	404 SF	100 GROSS	5
KITCHENS	267 SF	200 GROSS	2
PLATFORM	303 SF	15 NET	21
MERCANTILE	47 SF	60 GROSS	1
STORAGE	239 SF	300 GROSS	1
<b>TOTAL OCCUPANCY</b>			<b>294</b>

NFPA OCCUPANCY CALCULATION			
OCCUPANCY LOAD	TOTAL SQUARE FOOTAGE	FLOOR AREA IN SF PER OCCUPANT	TOTAL OCCUPANTS
CONCENTRATED ASSEMBLY	1284	5 NET ALLOWED	257
UN-CONCENTRATED ASSEMBLY SPACE	94 SF	15 NET	7
BUSINESS	404 SF	100 GROSS	5
KITCHENS	267 SF	100 GROSS	3
STAGES	303 SF	15 NET	21
STORAGE	239 SF	500 GROSS	1
MERCANTILE	47 SF	30 NET	2
<b>TOTAL OCCUPANCY</b>			<b>296</b>

