

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that
CITY OF PORTLAND

Located at
15 TEMPLE ST (11)

PERMIT ID: 2014-02751 **ISSUE DATE:** 01/30/2015 **CBL:** 032 H004001

has permission to **Change of Use from retail to music venue and bar with interior renovations.**
("Temple Street Music Venue")

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ David Petruccelli

/s/ Laurie Leader

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

#11 Temple - 1st floor, left end - musice venue & bar

Building Inspections

Use Group: A-2

Type: 2B

W/some ext. Wood framing

Fire Department

Assembly - Bar/Music Hall
Occupant load = 294
Tenant space is to be sprinkled with NFPA13 (remainder of building is not sprinkled)
1ST FLOOR (11) (FAR LEFT)
MUBEC/IBC 2009

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Close-in Plumbing/Framing w/Fire & Draft Stopping
Electrical - Commercial
Fire Inspection
Final - Electric
Final - Commercial
Pre-Construction Meeting

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2014-02751	Date Applied For: 11/25/2014	CBL: 032 H004001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Music Venue & Bar ("Temple Street Music Venue")		Proposed Project Description: Change of Use from retail to music venue and bar with interior renovations. ("Temple Street Music Venue")		
Dept: Zoning		Status: Approved w/Conditions	Reviewer: Ann Machado	Approval Date: 01/13/2015
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				
1) Separate permits shall be required for any new signage.				
2) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.				
Dept: Building		Status: Approved w/Conditions	Reviewer: Laurie Leader	Approval Date: 01/30/2015
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				
1) A State Fire Marshal permit is required for this project, contact at 207-626-3880 or http://www.maine.gov/dps/fmo/plans/about_permits.html . Send SFM permit to our office along with applicable revised plans.				
2) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				
3) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				
4) Approval is subject to compliance with City and State Food Codes per the Portland Public Health Dept. It is strongly advised to contact the Health Inspector for approval of kitchen design compliance prior to commencing work in earnest.				
5) Approval of City license is subject to health inspections per the Food Code.				
6) All new construction associated with this permit is required to be non-combustible including wiring to comply with NEC standards for non-combustible construction.				
Dept: Engineering DPS		Status: Approved w/Conditions	Reviewer: Benjamin Pearson	Approval Date: 01/30/2015
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				
1) There is no food cooking or food preparation appliances to be installed. Menu consists of food brought in for sale. Regardless, grease control equipment capable of 25 gpm and 50 pound capacity must be installed to capture the three bay sink used to wash any food prep or serving utensils. The dishwasher should not plumbed into the grease control unit.				
2) Unit to be fully pumped out quarterly.				
3) Future expansion of menu will require a reconsideration of grease control equipment.				
Dept: Fire		Status: Approved w/Conditions	Reviewer: David Petrucci	Approval Date: 01/28/2015
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				
1) The entire sprinkler system shall be maintained in accordance with NFPA 25, Standard for Inspection, Testing and Maintenance of Water-Based Fire Protection Systems, 2008 edition.				
2) Fire department connection type and location shall be approved in writing by Fire Prevention Bureau.				
3) Fire walls, fire barriers, fire partitions, smoke barriers and smoke partitions or any other wall required to have protected openings or penetrations shall be effectively and permanently identified with signs or stenciling in accessible concealed floor, floor-ceiling or attic spaces at intervals not exceeding 30 feet with lettering not less than 0.5 inches in height.				

PERMIT ID: 2014-02751

Located at: 15 TEMPLE ST (11)

CBL: 032 H004001

- 4) Any cutting and welding done will require a Hot Work Permit from Fire Department.
- 5) Emergency lights and exit signs are required. Emergency lights and exit signs are required to be labeled in relation to the panel and circuit and on the same circuit as the lighting for the area they serve.
- 6) All means of egress to remain accessible at all times.
- 7) Fire extinguishers are required per NFPA 1.
- 8) A firefighter Building Marking Sign is required.
- 9) A separate Fire Alarm Permit is required for new systems; or for work effecting more than 5 fire alarm devices; or replacement of a fire alarm panel with a different model. This review does not include approval of fire alarm system design or installation.
- 10 Street addresses shall be marked on the structure and shall be as approved by the City E-911 Addressing Officer.
- 11 Installation shall be in accordance with the City of Portland Fire Department Regulations and NFPA 13 as published. A copy of the State Sprinkler permit with RMS date and signature and the Contractor's Material and Test Certificate for Aboveground Piping (NFPA 13 figure 24.1) shall be provided prior to scheduling of the final inspection.
- 12 Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.
- 13 Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.
- 14 The installation shall comply with the following:
 - City of Portland Chapter 10, Fire Prevention and Protection;
 - NFPA 1, Fire Code (2009 edition), as amended by City Code;
 - NFPA 101, Life Safety Code (2009 edition), as amended by City Code;
 - City of Portland Fire Department Rules and Regulations;
 - NFPA 72, National Fire Alarm and Signaling Code (2010 edition), as amended by Fire Department Rules and Regulations; and
 - NFPA 70, National Electrical Code (2011 edition) as amended by the State of Maine
- 15 System acceptance and commissioning must be coordinated with a fire alarm technician and suppression system contractors and the Fire Department. Call 874-8400 to schedule.
- 16 A sprinkler supervisory system shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code. Sprinkler supervisory systems shall monitor for water flow and sprinkler supervisory signals via an approved fire alarm panel to central station. One smoke detector shall be located over the panel, a manual pull station located at the front door, and an audible water flow alarm provided. A separate fire alarm permit is required from a certified fire alarm company.
- 17 The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.
- 18 All fire alarm records required by NFPA 72 should be stored in an approved cabinet located at the FACP labeled "FIRE ALARM RECORDS".
- 19 A 4100 series Knox Box is required.
- 20 Application requires State Fire Marshal approval.
- 21 A separate Suppression System Permit is required for all new suppression systems, including standpipe systems, and sprinkler work effecting more than 20 heads. This review does not include approval of system design or installation.
- 22 A separate Fire Alarm Permit is required for new systems; or for work effecting more than 5 fire alarm devices; or replacement of a fire alarm panel with a different model. This review does not include approval of fire alarm system design or installation.
- 23 All outstanding code violations shall be corrected prior to final inspection.
- 24 Assembly and educational occupancies and uses with an occupant load of 100 or more persons required listed panic or fire exit hardware on doors serving as a means of egress.
- 25 The fire alarm technician shall be present for the fire inspection. System acceptance and commissioning must be coordinated with alarm and suppression system contractors and the Fire Department. Call 874-8400 to schedule.
- 26 Supervising Station monitoring for addressable fire alarm systems shall be by point.
- 27 Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.
- 28 In field installation shall be installed per code as conditions dictate.

- 29 The fire alarm system shall have a new fire alarm inspection sticker.
- 30 All smoke detectors shall be photoelectric.
- 31 Sprinkler supervision shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code.
- 32 Fire protection systems shall be maintained. If system is to be off line over 4 hours a fire watch shall be in place. Dispatch notification required 874-8576.
- 33 The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.
- 34 ****The fire alarm system design shall be evaluated for the renovated areas by an NICET IV certified interior fire alarm designer or a licensed engineer for compliance with the code. A compliance letter is required prior to the final inspection.****
****A current inspection sticker from an approved fire alarm inspection company is required prior to the final inspection.****
- 35 Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.