BRUNING 44-132 38634

Reviewed for Code Compliance Department of Public Safety Inspection Division Date: 12/08/17

Date: 12/08/17

HARDWARE

SET NO	LOCKSET-SARGENT	1½ PR. BUTT-HAGER	CLOSER-SARGENT	DR. STOP-BROOKLINE	PANICS-SARGENT	DR. PULLS-BROOKLINE	NOTES
1	906 LOCK	BB1279 4½X4½-10A	351 54		9910-10B		3.
2	W/ LOCKS			1326-10B	9928-99 10B		2.
3	7LG5-0B 10B						
4	7LG4-0B						
5	7905-0B 10B			1326-10B			
6				1326-10B		507-10B 701-10B	
7	KAWNEER	KAWNEER	KAWNEER		PANELINE W/ TANG BAR	PANELINE	

LEGEND

- F — PULL STATION
- PULL STATION
- 2 — PULL STATION
- FACP — PANEL

MEZZANINE LEVEL SCALE 1/8" = 1'-0" • EL. 67.5

NO.	DATE	BY	REVISIONS
1	5-19-83	AJ	DIMS. CHANGED. STAIR RISER NOTES ADDED.

SCHEDULE OF ROOM FINISHES

NO.	NAME	FLOOR	BASE	WALLS	CEILING	HEIGHT	NOTES
1	THEATER	CPT, 2-C. PNT-EP	4"V.	GWB, DRAPES (N.I.C)	ACT, PNT	8'-0"/VARIES	1, 2.
2	THEATER						
3	THEATER						
4	THEATER						
5	THEATER						
6	THEATER	CPT, 2-C. PNT-EP		GWB, DRAPES (N.I.C)	ACT, PNT	8'-0"/VARIES	1, 2.
7	LOBBY	CPT, R.T.		GWB, VINYL W.C., GLASS	ACT, GWB-PNT	8'-6"	3.
8	JANITOR	V.T.		GWB-PNT	GWB-PNT	EXPOSED	
9	HANDICAPPED TLT.	R.T.		GWB-PNT		7'-6"	
10	STORAGE	V.T.		GWB-PNT		7'-6"	
11	STAIR	CPT, R.T.		GWB, VINYL-W.C.		7'-6"/8'-6"	4.
12	HALLWAY	CPT		GWB, VINYL-W.C.		7'-6"	
13	STORAGE	V.T.		GWB-PNT		7'-6"	
14	STAIR	CONC. H/S	4"V.	GWB & CMU-PNT-FR.	GWB-PNT	VARIES	4.
20	HALLWAY	CPT	4"V.	GWB-PNT	GWB-PNT	7'-6"	
21	MEN	C.T.	C.T.	C.T. DADO & APP, GWB-PNT-EP			5.
22	WOMEN	C.T.	C.T.	C.T. DADO & APP, GWB-PNT-EP			5.
23	STORAGE	CONC. H/S	4"V.	GWB-PNT			
24	PROJECTOR ROOM	V.T.					
25	PROJECTOR ROOM						
26	OFFICE						
27	PROJECTOR ROOM	V.T.					
28	HALLWAY	CPT					
29	JANITOR STORAGE	V.T.	4"V.	GWB-PNT	GWB-PNT	7'-6"	

SCHEDULE OF DOORS AND FRAMES

OPG. MARK	DOOR SIZE	DOOR MATERIAL	DOOR TYPE	DOOR GAUGE	FRAME MATERIAL	FRAME TYPE	FRAME GAUGE	FRAME DETAIL	HDW. SET NO.	HDW. THRESHOLD	LABEL	NOTES
1	2 • 2'-6" X 7'-0" X 1¾"	WD	2	–	HM		16	6/AG	(2) 2		B	1, 2.
2	3'-0" X 7'-0" X 1¾"	HM	2	16			14	3	1	1	A	3, 4, 8
3	3'-0" X 7'-0" X 1¾"	WD	2	–			16	6	2		B	1, 2.
4	3'-0" X 7'-0" X 1¾"	HM	2	16			14	3	1	1	A	3, 4, 8
5	3'-0" X 7'-0" X 1¾"	WD	2	–			16	6	2		B	1, 2.
6	3'-0" X 7'-0" X 1¾"	HM	2	16			14	4	1	1	A	3, 4, 8
7	3'-0" X 7'-0" X 1¾"	WD	2	–			16	6	2		B	1, 2.
8	3'-0" X 7'-0" X 1¾"	HM	2	16			14	8	1	1		3, 4, 8
9	3'-0" X 7'-0" X 1¾"	WD	2	–			16	6	2		B	1, 2.
10	3'-0" X 7'-0" X 1¾"	HM	2	16			14	8	1	1		3, 4, 8
11	3'-0" X 7'-0" X 1¾"	WD	2	–			16	6	2		B	1, 2.
12	3'-0" X 7'-0" X 1¾"	HM	2	16	HM		14	8	1	1		3, 4, 8.
13	2 • 3'-0" X 7'-0" X 1¾"	ALUM	1	–	ALUM		–	7	7	1		6, 8
14	2 • 3'-0" X 7'-0" X 1¾"	ALUM	1	–	ALUM		–	7	7	1		6, 8
15	2'-8" X 7'-0" X 1¾"	WD	2	–	HM		16	2	4		B	1.
16	3'-0" X 7'-0" X 1¾"	WD	2	–			16	2	3			1.
17	2'-8" X 7'-0" X 1¾"	WD	2	–			16	2	4		B	1.
18	3'-0" X 7'-0" X 1¾"	HM	2	16			14	3	1	1	A	3, 4, 8
19	2'-8" X 7'-0" X 1¾"	WD	2	–	HM		16	2	4		B	1.
20	3'-0" X 7'-0" X 1¾"	HM	2	16	HM		14	8	4	1	B	3, 4, 8
21	3'-0" X 7'-0" X 1¾"	WD	3	–	HM		16	2	2		B	1.
22	3'-0" X 7'-0" X 1¾"		2	–			16	1	6			1.
23	3'-0" X 7'-0" X 1¾"		2	–			16	1	6			1.
24	2'-8" X 7'-0" X 1¾"		2	–			16	2	4		B	1.
25	3'-0" X 7'-0" X 1¾"		2	–			16	1	5		B	1.
26	3'-0" X 7'-0" X 1¾"		2	–			16	2	2		B	1.
27	2'-8" X 7'-0" X 1¾"		2	–			16	1	5			1.
28	3'-0" X 7'-0" X 1¾"	WD	2	–			16	2	5		B	1.
29	3'-0" X 7'-0" X 1¾"	HM	2	16	HM		14	3	1	1	A	3, 4, 8
30	3'-0" X 7'-0" X 1¾"	HM	3	16	HM		14	5/AG	2	1	B	3, 4, 8
31	3'-0" X 7'-0" X 1¾"	HM	3	16	HM		14	5/AG	2	1	B	3, 4, 8
32	3'-0" X 7'-0" X 1¾"	HM	3	16	HM		14	5/AG	2	1	B	3, 4, 8
33	2'-4" X 7'-0" X 1¾"	WD	2	–	HM		16	2/AG	4		B	1.
34	2'-4" X 7'-0" X 1¾"	WD	2	–	H			2/AG	4			1.

FINISH SCHEDULE NOTES

1. 2'X4' LAY-IN ACOUSTICAL TILE CEILING.
2. CARPET CARRIED 3' UP WALL W/WD. TRIM CAP. DRAPES ON REST OF WALL - N.I.C.
3. 2'X2' ACOUSTICAL TILE CEILING.
4. STAIR STRINGERS & RISERS PAINTED, RUBBER SAFETY NOSINGS & TREADS AND RUBBER TILE FLOOR LANDING.
5. CERAMIC TILE FLOORS TO BE THIN-SET TYPE. TOILET PARTITIONS TO BE FLOOR MOUNTED.

DOOR/HDW. SCHEDULE NOTS

1. ALL WOOD DOORS TO BE SOLID CORE, STAIN GRADE BIRCH.
2. THEATER WOOD DOORS TO BE EQUIPPED WITH SOUND SEAL GASKETS AT HEAD, JAMBS AND BOTTOM.
3. ALL EXTERIOR H.M. DOORS & FRAMES TO BE INSULATED AND WEATHERSTRIPPED.
4. ALL H.M. DOORS AND H.M. FRAMES TO BE PRIMED AND PAINTED.
5. ALL H.M. FRAMES TO HAVE A MIN. OF 3 METAL STUD ANCHORS PER JAMB & 2 ADJ. BASE ANCHORS WELD TO FRAMES
6. ALL ALUMINUM DOORS TO BE WEATHERSTRIPPED AND TEMPER GLASS TO HAVE BRONZE TINT.
7. ALL EXTERIOR DOOR THRESHOLDS TO BE SET IN A BED OF MASTIC.
8. THRESHOLD - ZERO INTERNATIONAL INC. TO MATCH DOOR JAMB WIDTHS.

FREEMAN · FRENCH · FREEMAN
ARCHITECTS · BURLINGTON, VERMONT

REGISTERED ARCHITECT FREDERICK A. SENFTLEBER No. 501 STATE OF MAINE

PIZZAGALLI DEVELOPMENT CO.
50 JOY DRIVE S. BURLINGTON VT.

SCALE 1/8" = 1'-0" | CHECKED GL | DATE 5-12-83 | DRAWN DMA, AHJ | PROJECT 2063

NICKELODEON 2 THEATERS
TEMPLE STREET
PORTLAND MAINE

MEZZANINE LEVEL PLAN

A-2