Inspections Division
Date: 05/07/14

NEW DORMER:

- WILL SIMULATE APPEARANCE OF ADJACENT DORMERS
- SPACING WILL BE MADE AS EQUAL AS POSSIBLE GIVING THE EXISTING FRAMING.
- THE ALIGNMENT OF THE EXISTING DORMERS WITHTTHE FACADE OF THE BUILDING IS DIFFICULT TO ACCURATELY ASCERTAIN. THE APPARENT INTENTION OF THE EXISTING DORMERS ARE TO ALIGN WITH WINDOWS BELOW. THE NEW DORMER WILL ADOPT THIS ALIGNMENT.
- SEE ASK-1 FOR CONSTRUCTION OF NEW DORMER
- NEW DORMER TO ALIGN VERTICALLY WITH EXISTING

EXISTING DORMERS:

- WILL RECEIVE NEW MEMBRANE ROOF AND METAL EDGE TRIM SIMILAR TO EXISTING.
- ASPHALT CHEEK WALL FINISH WILL BE REPLACED WITH CLAPBOARD SIDING.
- TRIM WILL BE REPLACED WITH NEW COMPOSITE TRIM TO SIMULATE EXISTING WOOD TRIM APEARANCE
- EXISTING ANDERSEN TRIPLE WOOD CASEMENTS TO BE REPLACED WITH UPDATED ANDERSEN CLAD WOOD CASEMENTS

BR BURN
architecture for life
28 Maple St.| Suite 202| Portland, ME 04101| 207-774-8482

NEW DORMER ADDITION

NEW ADDITION FOR MURAL ASSOCIATES
80-84 EXCHANGE ST., PORTLAND, ME 04101

PROJECT NO:	1402
ISSUED:	02.17.14
DRAWN BY:	CMB
CHECKED BY:	---
SHEET TITLE:	NEW DORMER

ASK-3