WINDOW SCHEDULE

UNIT ID	VIEW FROM EXTERIOR	UNIT WIDTH	UNIT HEIGHT	UNIT TYPE	UNIT QUANTITY	NOMINAL AREA	GLAZING	FRAME	FINISH	NOTES
1		2'-4"	9'-0"	FIXED	1	21.42	TEMPERED	METAL		WINDOW TRANSOM TO ALIGN WITH DOOR TRANSOM
2		4'-5"	9'-0"	,,	1	40.22	,,	,,		,,
3		3'-1"	9'-0"	,,	1	28.19	,,	,		,,
4		2'-0"	9'-0"	,,	1	18.42	,,	,		,,
5		6'-8"	9'-0"	,,	1	60.51	,,	,,		,,
5A		4'-3"	9'-0"	,,	1	38.71	,,	,,		,,
					6	**207.47 sq ft**				

1 WINDOW SCHEDULE

DOOR SCHEDULE

UNIT ID	VIEW FROM PULL-SIDE	LEAF WIDTH	LEAF HEIGHT	UNIT TYPE	UNIT QUANTITY	FIRE RATING	GLAZING	FRAME	FINISH	NOTES
1		3'-0"	7'-0"	SWING DOOR W/ TRANSOM	1	3/4 HR DOOR 3/4 HR GLAZING	TEMPERED	STEEL	PAINT	SEE LIFE SAFETY PLAN A0.1
2		3'-0"	7'-0"	,,	1		,,	METAL	,,	
3		3'-0"	7'-0"	,,	1		,,	,,	,,	
4		3'-0"	7'-0"	,,	1		,,	,,	,,	
5		3'-0"	7'-0"	,,	1		,,	,,	,,	
6		12'-0"	9'-0"	POCKET SLIDER	1		,,	,,	,,	3 x OPERABLE LEAVES 1 x POCKET
7		2'-8"	7'-0"	SWING DOOR	1			,,	,,	FLUSH PANEL
8		2'-8"	7'-0"	,,	1			,,	,,	FLUSH PANEL
					8					

2 DOOR SCHEDULE

A AT FLOOR/CEIL.

1 HOUR
1-WAY (FROM BELOW)
SMOKE BARRIER
INSTALL STRICTLY PER UL # L501

B AT BEAM

1 HOUR
INSTALL STRICTLY PER UL # L524

C AT WALL

1 HR FIRE BARRIER
2-WAY
LOAD BEARING
INSTALL STRICTLY PER UL # U305

D AT COLUMN

1 HOUR
LOAD BEARING
INTUMESCENT PAINT APPLIED STRICTLY PER MANUFACTURER'S RECOMMENDATIONS & RELEVANT INDEPENDENT TEST CERTIFICATES

3 FIRE RATED ASSEMBLIES

KAPLAN THOMPSON ARCHITECTS
102 EXCHANGE STREET
PORTLAND, ME 04101
207-842-2888
KAPLANTHOMPSON.COM

Reviewed for Code Compliance Inspections Division
Effective Date: 08/31/16

PROJECT:
HOFFMAN OFFICE
Level 2
The Oxford Building
183 Middle Street
Portland, ME 04101

STRUCTURAL :
Structural Integrity
77 Oak Street
Portland, ME 04101
p: 207 774-4614

GENERAL CONTRATOR :
Monaghan Woodworks
100 Commercial Street, # 105
Portland, ME 04101
p: 207 775-2683

LICENSED ARCHITECT JAMES JESSE THOMPSON No. 3275 STATE OF MAINE

PROJECT NO:	HOF
DATE:	06/27/2016
DRAWN BY:	RTL
PHASE:	FOR PERMIT

SCHEDULES & RATED ASSEMBLIES
A 8.1