

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

BUCKSTAR LLC /Freedom Fire Protection, Inc

Located at

178 MIDDLE ST

PERMIT ID: 2013-00167

CBL: 032 I001001

has permission to **Install NFPA 13 sprinkler system to basement, first, second, third, fourth levels.**
provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

[Signature]
Fire Prevention Officer

(58)

Code Enforcement Officer / Plan Reviewer

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**

REQUIRED INSPECTIONS:

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

| | | |
|---------------------------------|--|----------------------------|
| Permit No: 2013-00167 | Date Applied For: 01/28/2013 | CBL: 032 I001001 |
|---------------------------------|--|----------------------------|

| | | | |
|---|---|---|--------------------------------|
| Location of Construction: 178 MIDDLE ST | Owner Name: BUCKSTAR LLC | Owner Address: 100 SILVER ST | Phone: |
| Business Name: | Contractor Name: Freedom Fire Protection, Inc | Contractor Address: 209 Quaker Ridge Road Casco | Phone (207) 627-4109 |
| Lessee/Buyer's Name Timothy Vess | Phone: 2076274109 | Permit Type: Fire Suppression Water Based | |

| | |
|---|--|
| Proposed Use: Same: Restaurant and retail on 1st floor with offices above | Proposed Project Description: Install NFPA 13 sprinkler system to basement, first, second, third, fourth levels. |
|---|--|

Dept: Zoning **Status:** Approved w/Conditions **Reviewer:** Marge Schmuckal **Approval Date:** 01/29/2013

Note: **Ok to Issue:**

- 1) ANY exterior work requires a separate review and approval thru Historic Preservation. This property is located within an Historic District.

Dept: Fire **Status:** Approved w/Conditions **Reviewer:** Ben Wallace Jr **Approval Date:** 02/14/2013

Note: **Ok to Issue:**

- 1) Installation shall be in accordance with the City of Portland Fire Department Regulations and NFPA 13 as published. A copy of the State Sprinkler permit with RMS date and signature and the Contractor's Material and Test Certificate for Aboveground Piping (NFPA 13 figure 24.1) shall be provided prior to scheduling of the final inspection.
- 2) Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.
- 3) Sprinkler supervision shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code.
- 4) A sprinkler supervisory system shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code. Sprinkler supervisory systems shall monitor for water flow and sprinkler supervisory signals via an approved fire alarm panel to central station. One smoke detector shall be located over the panel, a manual pull station located at the front door, and an audible water flow alarm provided. A separate fire alarm permit is required from a certified fire alarm company.
- 5) A Knox Box is required.
- 6) The entire sprinkler system shall be maintained in accordance with NFPA 25, Standard for Inspection, Testing and Maintenance of Water-Based Fire Protection Systems, 2008 edition.
- 7) System acceptance and commissioning must be coordinated with alarm and suppression system contractors and the Fire Department. Call 874-8703 to schedule.
- 8) Fire department connection shall be two 2 ½" inlets.

City of Portland, Maine - Building or Use Permit Application

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

| | | |
|--------------------------|-------------|---------------------|
| Permit No: 2013-00167 | Issue Date: | CBL: 032 I001001 |
|--------------------------|-------------|---------------------|

| | | | |
|---|--|---|--|
| Location of Construction: 178 MIDDLE ST | Owner Name: BUCKSTAR LLC | Owner Address: 100 SILVER ST PORTLAND , ME 04101 | Phone: |
| Business Name: | Contractor Name: Freedom Fire Protection, Inc | Contractor Address: 209 Quaker Ridge Road Casco ME 04015 | Phone (207) 627-4109 |
| Lessee/Buyer's Name Timothy Vess | Phone: (207) 627-4109 | Permit Type: Fire Suppression Water Based | Zone: B3 |
| Past Use: Restaurant and retail on first floor with offices above | Proposed Use: Same: Restaurant and retail on 1st floor with offices above | Permit Fee: \$990.00 | Cost of Work: \$96,892.00 |
| Proposed Project Description: Install Water Based Fire Suppression to basement, first, second, third, fourth levels. | | FIRE DEPT: <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Denied <input type="checkbox"/> N/A 2/14/13 | INSPECTION: Use Group: Type: |
| | | Signature: <i>[Signature]</i> <i>(50)</i> | Signature: |
| PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.) | | | |
| Action: <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied | | | |
| Signature: Date: | | | |

| | | | | |
|---|---|--|---|--|
| Permit Taken By: gg | Date Applied For: 01/28/2013 | Zoning Approval | | |
| <ol style="list-style-type: none"> This permit application does not preclude the Applicant(s) from meeting applicable State and Federal Rules. Building permits do not include plumbing, septic or electrical work. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work.. | Special Zone or Reviews <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan Maj <input type="checkbox"/> Minor <input type="checkbox"/> MM <input type="checkbox"/> Denied Date: <i>2/29/13</i> | Zoning Appeal <input type="checkbox"/> Variance <input type="checkbox"/> Miscellaneous <input type="checkbox"/> Conditional Use <input type="checkbox"/> Interpretation <input type="checkbox"/> Approved <input type="checkbox"/> Denied | Historic Preservation <i>with</i> <input type="checkbox"/> Not in District or Landmark <input type="checkbox"/> Does Not Require Review <input type="checkbox"/> Requires Review <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied Date: <i>require SA separate review approval</i> | |

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provision of the code(s) applicable to such permit.

| | | | |
|---|---------|------|-------|
| SIGNATURE OF APPLICANT | ADDRESS | DATE | PHONE |
| RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE | | DATE | PHONE |



Water-Based Fire Suppression System Permit

Dept. of Building
City of Portland Maine

If you or the property owner owes real estate or property taxes or user charges on any property within the city, payment arrangements must be made before permits of any kind are accepted.

*Enter &
electronic file*

RECEIVED

JAN 28 2013

2013 00167

Installation address: 178 Middle Street CBL: 032 I 001

Exact location: (within structure) Basement, First, Second, Third, Fourth Levels

Type of occupancy(s) (NFPA & ICC): Office Space

Building owner: ~~Commercial Properties Management~~ Dan Catlin Buckster LLC

Managing Supervisor (RMS): Timothy Vess License No: 348

Supervisor phone: 207/627-4109 E-mail: wwales@maine.rr.com

Installing contractor: Freedom Fire Protection License No: 295

Contractor phone: 207/627-4109 E-mail: wwales@maine.rr.com

The suppression work to be done will be: New: Renovation: Addition to existing system:

This is an amendment to an existing permit: Yes: NO: Permit no: _____

NFPA Standard this system is designed to: NFPA-13 Edition: 2010

*Non-NFPA systems are not approved for use within the City of Portland.

Download a new copy of this document from www.portlandmaine.gov/fire for every submittal. Attach all working documents and complete approved submittals as may be required by the State Fire Marshal's Office on electronic PDF's in addition to full sized plans.

Contractor shall verify location and type of all FDCs shall be approved in writing by the Fire Prevention Bureau.

Submit all information to the Building Inspections Department, 389 Congress Street, Room 315, Portland, Maine 04101.

Prior to acceptance of any fire protection system, a complete commissioning and acceptance test must be coordinated with all fire system contractors and the Fire Department, and proper documentation of such test(s) provided.

All installation(s) must comply with NFPA and the Fire Department Technical Standard(s).

| |
|--|
| COST OF WORK: \$96,892.00 |
| PERMIT FEE: \$990.00 |
| <small>(\$10 PER \$1,000 + \$30 FOR THE FIRST \$1,000)</small> |
| FOR CREDIT TO THE ACCOUNT OF |
| CITY OF PORTLAND |
| PLANNING & URBAN DEVELOPMENT |
| TO BANK NORTH, N.A. MAINE |
| TO BANK NORTH, N.A. MAINE |
| FOR CREDIT TO THE ACCOUNT OF |
| CITY OF PORTLAND |
| PLANNING & URBAN DEVELOPMENT |

Applicant signature: Wm Wales Date: January 24, 2013

CITY OF PORTLAND
DEPARTMENT OF PLANNING & URBAN DEVELOPMENT

389 Congress Street
 Portland, Maine 04101

RECEIPT OF FEES

| | |
|----------------------------------|--|
| Application No: 201300167 | Applicant: BUCKSTAR LLC |
| Project Name: | Location: 178 MIDDLE ST |
| CBL: 032 I001001 | Permit Type: Fire Suppression Water Based |
| Invoice Date: 01/28/2013 | |

| | | | | | | | | | |
|-------------------------|---|-------------------------|---|---------------------|---|------------------------|---|------------------|-------------------------|
| Previous Balance | - | Payment Received | + | Current Fees | - | Current Payment | = | Total Due | Payment Due Date |
| \$0.00 | | \$0.00 | | \$990.00 | | \$990.00 | | \$0.00 | On Receipt |


Previous Balance **\$0.00**

| Fee Description | Qty | Fee/Deposit Charge |
|----------------------------------|------------|---------------------------|
| Building Permit Fee First \$1000 | 1 | \$30.00 |
| Building Permit Fee Add'l \$1000 | 1 | \$960.00 |
| | | <hr/> \$990.00 |
| Total Current Fees: | + | \$990.00 |
| Total Current Payments: | - | \$990.00 |
| Amount Due Now: | | \$0.00 |

Bill to: BUCKSTAR LLC
 100 SILVER ST
 PORTLAND, ME 04101

CBL 032 I001001
Application No: 201300167
Invoice Date: 01/28/2013
Invoice No: 39879
Total Amt Due: \$0.00
Payment Amount:

Make checks payable to the *City of Portland*, ATTN: Inspections, 3rd Floor, 389 Congress Street, Portland, ME 04101.



... Fire Protection by Computer Design

FREEDOM FIRE PROTECTION INC.
209 QUAKER RIDGE ROAD
CASCO, MAINE 04015
207-627-4109

Job Name : 178 MIDDLE STREET HC1
Building : 178 MIDDLE STREET
Location : PORTLAND, MAINE 04101
System : #1 AREA#1
Contract :
Data File : 178 MIDDLE STREET HC1.WXF

Hydraulic Design Information Sheet

Name - 178 MIDDLE STREET Date - 1/22/13
Location - PORTLAND, MAINE 04101
Building - 178 MIDDLE STREET System No. - #1 AREA#1
Contractor - Contract No. -
Calculated By - MIKE NOBLIT Drawing No. - FP-3
Construction: (X) Combustible () Non-Combustible Ceiling Height - 9'-7"
Occupancy - OFFICES

S (X) NFPA 13 (X) Lt. Haz. Ord.Haz.Gp. () 1 () 2 () 3 () Ex.Haz.
Y () NFPA 231 () NFPA 231C () Figure Curve

S Other

T Specific Ruling Made By Date

| E | | | | |
|---|-----------------------------|----------|---------------|------------------|
| M | Area of Sprinkler Operation | - ROOM | System Type | Sprinkler/Nozzle |
| | Density | - 0.10 | (X) Wet | Make TYCO |
| D | Area Per Sprinkler | - 196 | () Dry | Model TY-FRB |
| E | Elevation at Highest Outlet | - 55'-0" | () Deluge | Size 1/2" |
| S | Hose Allowance - Inside | - | () Preaction | K-Factor 5.6 |
| I | Rack Sprinkler Allowance | - | () Other | Temp.Rat.155 |
| G | Hose Allowance - Outside | - 100 | | |

N Note

Calculation Flow Required - 218.951 Press Required - 72.735 At Test
Summary C-Factor Used: 120 Overhead 140 Underground

| W | Water Flow Test: | Pump Data: | Tank or Reservoir: |
|---|--------------------------|-------------|--------------------|
| A | Date of Test - 7/19/2009 | | Cap. - |
| T | Time of Test - | Rated Cap.- | Elev.- |
| E | Static Press - 83 | @ Press - | |
| R | Residual Press - 0 | Elev. - | Well |
| | Flow - 1342 | | Proof Flow |
| S | Elevation - | | |

U Location -

P Source of Information - PORTLAND WATER DISTRICT

Y


Water Supply Curve (C)

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC1

Page 2
Date 1/22/13

City Water Supply:
C1 - Static Pressure : 83
C2 - Residual Pressure: 0
C2 - Residual Flow : 1342

Demand:
D1 - Elevation : 23.820
D2 - System Flow : 118.951
D2 - System Pressure : 72.735
Hose (Adj City) : _____
Hose (Demand) : 100
D3 - System Demand : 218.951
Safety Margin : 7.365



Fittings Used Summary

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC1

Page 3
Date 1/22/13

| Fitting Legend | | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 3½ | 4 | 5 | 6 | 8 | 10 | 12 | 14 | 16 | 18 | 20 | 24 | |
|----------------|---------------------|---|---|---|----|----|----|-----|------|----|----|----|----|----|----|----|----|----|----|-----|-----|---|
| Abbrev. | Name | | | | | | | | | | | | | | | | | | | | | |
| A | Generic Alarm Valve | 0 | 0 | 0 | 0 | 0 | 0 | 7.7 | 21.5 | 0 | 17 | 17 | 27 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| E | 90° Standard Elbow | 2 | 2 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 12 | 14 | 18 | 22 | 27 | 35 | 40 | 45 | 50 | 61 | |
| G | Generic Gate Valve | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 1 | 2 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 11 | 13 | |
| T | 90° Flow Thru Tee | 3 | 4 | 5 | 6 | 8 | 10 | 12 | 15 | 17 | 20 | 25 | 30 | 35 | 50 | 60 | 71 | 81 | 91 | 101 | 121 | |

Pressure / Flow Summary - STANDARD

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC1

Page 4
Date 1/22/13

| Node No. | Elevation | K-Fact | Pt Actual | Pn | Flow Actual | Density | Area | Press Req. |
|----------|-----------|--------|-----------|----|-------------|---------|-------|------------|
| 102 | 55.0 | 5.6 | 7.92 | na | 15.76 | 0.1 | 0.001 | 7.0 |
| 103 | 55.0 | 5.6 | 7.08 | na | 14.9 | 0.1 | 0.001 | 7.0 |
| 104 | 55.0 | 5.6 | 7.0 | na | 14.82 | 0.1 | 0.001 | 7.0 |
| 13 | 55.0 | | 7.45 | na | | | | |
| 12 | 55.0 | | 8.13 | na | | | | |
| 11 | 55.0 | | 8.42 | na | | | | |
| 10 | 55.0 | | 10.71 | na | | | | |
| 101 | 55.0 | 5.6 | 11.28 | na | 18.8 | 0.1 | 130 | 7.0 |
| 106 | 55.0 | 5.6 | 10.03 | na | 17.73 | 0.1 | 0.001 | 7.0 |
| 107 | 55.0 | 5.6 | 9.54 | na | 17.29 | 0.1 | 0.001 | 7.0 |
| 17 | 55.0 | | 10.13 | na | | | | |
| 16 | 55.0 | | 10.51 | na | | | | |
| 15 | 55.0 | | 10.65 | na | | | | |
| 14 | 55.0 | | 12.07 | na | | | | |
| 105 | 55.0 | 5.6 | 12.31 | na | 19.65 | 0.1 | 130 | 7.0 |
| 9 | 55.0 | | 12.76 | na | | | | |
| 8 | 55.0 | | 29.61 | na | | | | |
| 7 | 54.5 | | 33.48 | na | | | | |
| 6 | 54.5 | | 43.33 | na | | | | |
| 5 | 54.5 | | 44.71 | na | | | | |
| 4 | 6.416 | | 67.79 | na | | | | |
| 3 | 6.416 | | 69.75 | na | | | | |
| 2 | 6.416 | | 69.82 | na | | | | |
| 1 | 0.0 | | 72.73 | na | | | | |
| TEST | 0.0 | | 72.74 | na | 100.0 | | | |

The maximum velocity is 19.03 and it occurs in the pipe between nodes 9 and 8

Final Calculations - Hazen-Williams

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC1

Page 5
Date 1/22/13

| Hyd. Ref. Point | Qa Qt | Dia. "C" Pf/Ft | Fitting or Eqv. Ln. | Pipe Ftng's Total | Pt Pe Pf | Pt Pv Pn | ***** Notes ***** |
|-----------------------|----------|----------------------|---------------------------|-------------------------|----------------|----------------|-------------------------|
| 102 | 15.76 | 1.049 | 1T 5.0 | 1.000 | 7.916 | | K Factor = 5.60 |
| to | | 120 | 0.0 | 5.000 | 0.0 | | |
| 11 | 15.76 | 0.0837 | 0.0 | 6.000 | 0.502 | | Vel = 5.85 |
| | 0.0 | | | | | | |
| | 15.76 | | | | 8.418 | | K Factor = 5.43 |
| 103 | 14.90 | 1.049 | 1E 2.0 | 7.000 | 7.077 | | K Factor = 5.60 |
| to | | 120 | 1T 5.0 | 7.000 | 0.0 | | |
| 12 | 14.9 | 0.0754 | 0.0 | 14.000 | 1.056 | | Vel = 5.53 |
| | 0.0 | | | | | | |
| | 14.90 | | | | 8.133 | | K Factor = 5.22 |
| 104 | 14.82 | 1.049 | 1T 5.0 | 1.000 | 7.000 | | K Factor = 5.60 |
| to | | 120 | 0.0 | 5.000 | 0.0 | | |
| 13 | 14.82 | 0.0747 | 0.0 | 6.000 | 0.448 | | Vel = 5.50 |
| 13 | 0.0 | 1.049 | 0.0 | 9.166 | 7.448 | | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | |
| 12 | 14.82 | 0.0747 | 0.0 | 9.166 | 0.685 | | Vel = 5.50 |
| 12 | 14.89 | 1.38 | 0.0 | 4.000 | 8.133 | | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | |
| 11 | 29.71 | 0.0712 | 0.0 | 4.000 | 0.285 | | Vel = 6.37 |
| 11 | 15.76 | 1.38 | 1T 6.0 | 8.660 | 8.418 | | |
| to | | 120 | 0.0 | 6.000 | 0.0 | | |
| 10 | 45.47 | 0.1563 | 0.0 | 14.660 | 2.292 | | Vel = 9.75 |
| 10 | 0.0 | 1.598 | 0.0 | 11.166 | 10.710 | | |
| to | | 150 | 0.0 | 0.0 | 0.0 | | |
| 101 | 45.47 | 0.0507 | 0.0 | 11.166 | 0.566 | | Vel = 7.27 |
| 101 | 18.80 | 1.598 | 1T 11.656 | 3.750 | 11.276 | | K Factor = 5.60 |
| to | | 150 | 0.0 | 11.656 | 0.0 | | |
| 9 | 64.27 | 0.0961 | 0.0 | 15.406 | 1.481 | | Vel = 10.28 |
| | 0.0 | | | | | | |
| | 64.27 | | | | 12.757 | | K Factor = 17.99 |
| 106 | 17.73 | 1.049 | 1T 5.0 | 1.000 | 10.029 | | K Factor = 5.60 |
| to | | 120 | 0.0 | 5.000 | 0.0 | | |
| 15 | 17.73 | 0.1042 | 0.0 | 6.000 | 0.625 | | Vel = 6.58 |
| | 0.0 | | | | | | |
| | 17.73 | | | | 10.654 | | K Factor = 5.43 |
| 107 | 17.29 | 1.049 | 1T 5.0 | 1.000 | 9.537 | | K Factor = 5.60 |
| to | | 120 | 0.0 | 5.000 | 0.0 | | |
| 17 | 17.29 | 0.0995 | 0.0 | 6.000 | 0.597 | | Vel = 6.42 |
| 17 | 0.0 | 1.049 | 0.0 | 3.830 | 10.134 | | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | |
| 16 | 17.29 | 0.0995 | 0.0 | 3.830 | 0.381 | | Vel = 6.42 |

Final Calculations - Standard

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC1

Page 6
Date 1/22/13

| Hyd. Ref. Point | Qa Qt | Dia. "C" Pf/Ft | Fitting or Eqv. Ln. | Pipe Ftng's Total | Pt Pe Pf | Pt Pv Pn | ***** Notes ***** |
|-----------------------|----------|----------------------|---------------------------|-------------------------|----------------|----------------|-------------------------|
| 16 | 0.0 | 1.38 | | 5.330 | 10.515 | | |
| to | | 120 | | 0.0 | 0.0 | | |
| 15 | 17.29 | 0.0261 | | 5.330 | 0.139 | | Vel = 3.71 |
| 15 | 17.74 | 1.38 | 1T | 6.0 | 8.660 | 10.654 | |
| to | | 120 | | 0.0 | 6.000 | 0.0 | |
| 14 | 35.03 | 0.0965 | | 0.0 | 14.660 | 1.415 | Vel = 7.51 |
| 14 | 0.0 | 1.598 | | 0.0 | 7.750 | 12.069 | |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 105 | 35.03 | 0.0314 | | 0.0 | 7.750 | 0.243 | Vel = 5.60 |
| 105 | 19.65 | 1.598 | | 0.0 | 6.250 | 12.312 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 9 | 54.68 | 0.0712 | | 0.0 | 6.250 | 0.445 | Vel = 8.75 |
| 9 | 64.27 | 1.598 | 1E | 5.828 | 50.330 | 12.757 | |
| to | | 150 | | 0.0 | 5.828 | 0.0 | |
| 8 | 118.95 | 0.3002 | | 0.0 | 56.158 | 16.857 | Vel = 19.03 |
| 8 | 0.0 | 1.598 | 1T | 11.656 | 0.500 | 29.614 | |
| to | | 150 | | 0.0 | 11.656 | 0.217 | |
| 7 | 118.95 | 0.3002 | | 0.0 | 12.156 | 3.649 | Vel = 19.03 |
| 7 | 0.0 | 1.598 | 1E | 5.828 | 27.000 | 33.480 | |
| to | | 150 | | 0.0 | 5.828 | 0.0 | |
| 6 | 118.95 | 0.3002 | | 0.0 | 32.828 | 9.854 | Vel = 19.03 |
| 6 | 0.0 | 2.157 | 1E | 9.298 | 10.500 | 43.334 | |
| to | | 150 | | 0.0 | 9.298 | 0.0 | |
| 5 | 118.95 | 0.0697 | | 0.0 | 19.798 | 1.379 | Vel = 10.44 |
| 5 | 0.0 | 2.635 | 1E | 8.237 | 48.583 | 44.713 | |
| to | | 120 | | 0.0 | 8.237 | 20.825 | |
| 4 | 118.95 | 0.0397 | | 0.0 | 56.820 | 2.257 | Vel = 7.00 |
| 4 | 0.0 | 2.635 | 2E | 16.474 | 32.660 | 67.795 | |
| to | | 120 | | 0.0 | 16.474 | 0.0 | |
| 3 | 118.95 | 0.0397 | | 0.0 | 49.134 | 1.951 | Vel = 7.00 |
| 3 | 0.0 | 4.026 | 1E | 10.0 | 5.000 | 69.746 | |
| to | | 120 | | 0.0 | 10.000 | 0.0 | |
| 2 | 118.95 | 0.0050 | | 0.0 | 15.000 | 0.075 | Vel = 3.00 |
| 2 | 0.0 | 4.026 | 1A | 17.0 | 6.416 | 69.821 | |
| to | | 120 | 1G | 2.0 | 19.000 | 2.779 | |
| 1 | 118.95 | 0.0050 | | 0.0 | 25.416 | 0.128 | Vel = 3.00 |
| 1 | 0.0 | 6.16 | | 0.0 | 15.000 | 72.728 | |
| to | | 140 | | 0.0 | 0.0 | 0.0 | |
| TEST | 118.95 | 0.0005 | | 0.0 | 15.000 | 0.007 | Vel = 1.28 |
| | 100.00 | | | | | | Qa = 100.00 |
| | 218.95 | | | | 72.735 | | K Factor = 25.67 |



... **Fire Protection by Computer Design**

FREEDOM FIRE PROTECTION INC.
209 QUAKER RIDGE ROAD
CASCO, MAINE 04015
207-627-4109

Job Name : 178 MIDDLE STREET HC2
Building : 178 MIDDLE STREET
Location : PORTLAND, MAINE 04101
System : #1 AREA#2
Contract :
Data File : 178 MIDDLE STREET HC2.WXF

Hydraulic Design Information Sheet

| | |
|---|------------------------|
| Name - 178 MIDDLE STREET | Date - 1/22/13 |
| Location - PORTLAND, MAINE 04101 | |
| Building - 178 MIDDLE STREET | System No. - #1 AREA#2 |
| Contractor - | Contract No. - |
| Calculated By - MIKE NOBLIT | Drawing No. - FP-3 |
| Construction: (X) Combustible () Non-Combustible | Ceiling Height - 9'-7" |
| Occupancy - OFFICES | |

S (X) NFPA 13 (X) Lt. Haz. Ord.Haz.Gp. () 1 () 2 () 3 () Ex.Haz.
 Y () NFPA 231 () NFPA 231C () Figure Curve

S Other

T Specific Ruling

Made By

Date

| | | | | |
|---|--------------------------------------|---------------|------------------|--|
| E | | | | |
| M | Area of Sprinkler Operation - ROOM | System Type | Sprinkler/Nozzle | |
| | Density - 0.10 | (X) Wet | Make TYCO | |
| D | Area Per Sprinkler - 120 | () Dry | Model TY-FRB | |
| E | Elevation at Highest Outlet - 44'-4" | () Deluge | Size 1/2" | |
| S | Hose Allowance - Inside - | () Preaction | K-Factor 5.6 | |
| I | Rack Sprinkler Allowance - | () Other | Temp.Rat.155 | |
| G | Hose Allowance - Outside - 100 | | | |

N Note

Calculation Flow Required - 247.278 Press Required - 70.999 At Test
 Summary C-Factor Used: 150 Overhead 140 Underground

| | | | |
|---|--------------------------|-------------|--------------------|
| W | Water Flow Test: | Pump Data: | Tank or Reservoir: |
| A | Date of Test - 7/19/2009 | | Cap. - |
| T | Time of Test - | Rated Cap.- | Elev.- |
| E | Static Press - 83 | @ Press - | |
| R | Residual Press - 0 | Elev. - | Well |
| | Flow - 1342 | | Proof Flow |
| S | Elevation - | | |

U Location -

P Source of Information - PORTLAND WATER DISTRICT

L

Y


Water Supply Curve (C)

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC2

Page 2
Date 1/22/13

City Water Supply:
C1 - Static Pressure : 83
C2 - Residual Pressure: 0
C2 - Residual Flow : 1342

Demand:
D1 - Elevation : 19.199
D2 - System Flow : 147.278
D2 - System Pressure : 70.999
Hose (Adj City) :
Hose (Demand) : 100
D3 - System Demand : 247.278
Safety Margin : 8.370



Fittings Used Summary

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC2

Page 3
Date 1/22/13

| Fitting Legend | | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 3½ | 4 | 5 | 6 | 8 | 10 | 12 | 14 | 16 | 18 | 20 | 24 | |
|----------------|---------------------|---|---|---|----|----|----|-----|------|----|----|----|----|----|----|----|----|----|----|-----|-----|-----|
| Abbrev. | Name | | | | | | | | | | | | | | | | | | | | | |
| A | Generic Alarm Valve | 0 | 0 | 0 | 0 | 0 | 0 | 7.7 | 21.5 | 0 | 17 | 17 | 27 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| E | 90' Standard Elbow | 2 | 2 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 12 | 14 | 18 | 22 | 27 | 35 | 40 | 45 | 50 | 61 | 61 |
| G | Generic Gate Valve | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 1 | 2 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 11 | 13 | 13 |
| T | 90' Flow Thru Tee | 3 | 4 | 5 | 6 | 8 | 10 | 12 | 15 | 17 | 20 | 25 | 30 | 35 | 50 | 60 | 71 | 81 | 91 | 101 | 121 | 121 |

Pressure / Flow Summary - STANDARD

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC2

Page 4
Date 1/22/13

| Node No. | Elevation | K-Fact | Pt Actual | Pn | Flow Actual | Density | Area | Press Req. |
|----------|-----------|--------|-----------|----|-------------|---------|------|------------|
| 201 | 44.33 | 5.6 | 14.53 | na | 21.35 | 0.1 | 120 | 7.0 |
| 204 | 44.33 | 5.6 | 12.23 | na | 19.59 | 0.1 | 120 | 7.0 |
| 203 | 44.33 | 5.6 | 13.02 | na | 20.21 | 0.1 | 120 | 7.0 |
| 202 | 44.33 | 5.6 | 15.93 | na | 22.35 | 0.1 | 120 | 7.0 |
| 205 | 44.33 | 5.6 | 8.86 | na | 16.67 | 0.1 | 120 | 7.0 |
| 208 | 44.33 | 5.6 | 7.0 | na | 14.82 | 0.1 | 120 | 7.0 |
| 207 | 44.33 | 5.6 | 7.47 | na | 15.3 | 0.1 | 120 | 7.0 |
| 206 | 44.33 | 5.6 | 9.21 | na | 17.0 | 0.1 | 120 | 7.0 |
| 25 | 44.33 | | 9.32 | na | | | | |
| 24 | 44.33 | | 9.86 | na | | | | |
| 23 | 44.33 | | 16.11 | na | | | | |
| 22 | 43.66 | | 21.82 | na | | | | |
| 21 | 43.66 | | 36.24 | na | | | | |
| 20 | 43.66 | | 46.2 | na | | | | |
| 4 | 6.416 | | 65.01 | na | | | | |
| 3 | 6.416 | | 67.91 | na | | | | |
| 2 | 6.416 | | 68.02 | na | | | | |
| 1 | 0.0 | | 70.99 | na | | | | |
| TEST | 0.0 | | 71.0 | na | 100.0 | | | |

The maximum velocity is 23.56 and it occurs in the pipe between nodes 23 and 22

Final Calculations - Hazen-Williams

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC2

Page 5
Date 1/22/13


| Hyd. Ref. Point | Qa Qt | Dia. "C" Pf/Ft | Fitting or Eqv. Ln. | Pipe Ftng's Total | Pt Pe Pf | Pt Pv Pn | ***** Notes ***** |
|-----------------------|----------|----------------------|---------------------------|-------------------------|----------------|----------------|-------------------------|
| 201 | 21.35 | 1.101 | 1T | 9.563 | 11.000 | 14.532 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 9.562 | 0.0 | |
| 23 | 21.35 | 0.0768 | | 0.0 | 20.562 | 1.579 | Vel = 7.19 |
| | 0.0 | | | | | | |
| | 21.35 | | | | | 16.111 | K Factor = 5.32 |
| 204 | 19.59 | 1.101 | | 0.0 | 12.000 | 12.234 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 203 | 19.59 | 0.0655 | | 0.0 | 12.000 | 0.786 | Vel = 6.60 |
| 203 | 20.20 | 1.101 | | 0.0 | 12.000 | 13.020 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 202 | 39.79 | 0.2429 | | 0.0 | 12.000 | 2.915 | Vel = 13.41 |
| 202 | 22.36 | 1.394 | | 0.0 | 1.000 | 15.935 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 23 | 62.15 | 0.1760 | | 0.0 | 1.000 | 0.176 | Vel = 13.06 |
| | 0.0 | | | | | | |
| | 62.15 | | | | | 16.111 | K Factor = 15.48 |
| 205 | 16.67 | 1.101 | 1T | 9.563 | 11.000 | 8.858 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 9.562 | 0.0 | |
| 24 | 16.67 | 0.0486 | | 0.0 | 20.562 | 0.999 | Vel = 5.62 |
| | 0.0 | | | | | | |
| | 16.67 | | | | | 9.857 | K Factor = 5.31 |
| 208 | 14.82 | 1.101 | | 0.0 | 12.000 | 7.000 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 207 | 14.82 | 0.0391 | | 0.0 | 12.000 | 0.469 | Vel = 4.99 |
| 207 | 15.30 | 1.101 | | 0.0 | 12.000 | 7.469 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 206 | 30.12 | 0.1451 | | 0.0 | 12.000 | 1.741 | Vel = 10.15 |
| 206 | 17.00 | 1.394 | | 0.0 | 1.000 | 9.210 | K Factor = 5.60 |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 25 | 47.12 | 0.1060 | | 0.0 | 1.000 | 0.106 | Vel = 9.91 |
| 25 | 0.0 | 1.598 | | 0.0 | 10.000 | 9.316 | |
| to | | 150 | | 0.0 | 0.0 | 0.0 | |
| 24 | 47.12 | 0.0541 | | 0.0 | 10.000 | 0.541 | Vel = 7.54 |
| 24 | 16.66 | 1.598 | 1E | 5.828 | 60.166 | 9.857 | |
| to | | 150 | | 0.0 | 5.828 | 0.0 | |
| 23 | 63.78 | 0.0948 | | 0.0 | 65.994 | 6.254 | Vel = 10.20 |
| 23 | 83.50 | 1.598 | 1T | 11.656 | 0.500 | 16.111 | |
| to | | 150 | | 0.0 | 11.656 | 0.290 | |
| 22 | 147.28 | 0.4456 | | 0.0 | 12.156 | 5.417 | Vel = 23.56 |
| 22 | 0.0 | 1.598 | 1E | 5.828 | 26.541 | 21.818 | |
| to | | 150 | | 0.0 | 5.828 | 0.0 | |
| 21 | 147.28 | 0.4457 | | 0.0 | 32.369 | 14.426 | Vel = 23.56 |

Final Calculations - Standard

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC2

Page 6
Date 1/22/13

| Hyd. Ref. Point | Qa Qt | Dia. "C" Pf/Ft | Fitting or Eqv. Ln. | Pipe Ftng's Total | Pt Pe Pf | Pt Pv Pn | ***** Notes ***** |
|-----------------------|------------------|------------------------|---------------------------|-------------------------|------------------|----------------|---------------------------------|
| 21 to 20 | 0.0 147.28 | 1.61 120 0.6493 | 1E 4.0 0.0 | 11.330 4.000 | 36.244 0.0 | | Vel = 23.21 |
| 20 to 4 | 0.0 147.28 | 2.635 120 0.0590 | 1E 8.237 0.0 | 37.250 8.237 | 46.198 16.130 | | Vel = 8.67 |
| 4 to 3 | 0.0 147.28 | 2.635 120 0.0590 | 2E 16.474 0.0 | 32.660 16.474 | 65.010 0.0 | | Vel = 8.67 |
| 3 to 2 | 0.0 147.28 | 4.026 120 0.0075 | 1E 10.0 0.0 | 5.000 10.000 | 67.907 0.0 | | Vel = 3.71 |
| 2 to 1 | 0.0 147.28 | 4.026 120 0.0075 | 1A 17.0 1G 2.0 | 6.416 19.000 | 68.019 2.779 | | Vel = 3.71 |
| 1 to TEST | 0.0 147.28 | 6.16 140 0.0007 | 0.0 0.0 | 15.000 0.0 | 70.988 0.0 | | Vel = 1.59 |
| | 100.00 247.28 | | 0.0 | 15.000 | 0.011 | | Qa = 100.00 K Factor = 29.35 |
| | | | | | 70.999 | | |



... Fire Protection by Computer Design

FREEDOM FIRE PROTECTION INC.
209 QUAKER RIDGE ROAD
CASCO, MAINE 04015
207-627-4109

Job Name : 178 MIDDLE STREET HC3
Building : 178 MIDDLE STREET
Location : PORTLAND, MAINE 04101
System : #1 AREA#3
Contract :
Data File : 178 MIDDLE STREET HC3.WXF

Hydraulic Design Information Sheet

Name - 178 MIDDLE STREET Date - 1/22/13
Location - PORTLAND, MAINE 04101
Building - 178 MIDDLE STREET System No. - #1 AREA#3
Contractor - Contract No. -
Calculated By - MIKE NOBLIT Drawing No. - FP-2
Construction: (X) Combustible () Non-Combustible Ceiling Height - 7'-11"
Occupancy - BASEMENT STORAGE

S (X) NFPA 13 () Lt. Haz. Ord.Haz.Gp. (X) 1 () 2 () 3 () Ex.Haz.
Y () NFPA 231 () NFPA 231C () Figure Curve

S Other
T Specific Ruling Made By Date

E
M Area of Sprinkler Operation - ROOM System Type Sprinkler/Nozzle
Density - 0.15 (X) Wet Make TYCO
D Area Per Sprinkler - 130 () Dry Model TY-FRB
E Elevation at Highest Outlet - 6'-11" () Deluge Size 1/2"
S Hose Allowance - Inside - () Preaction K-Factor 5.6
I Rack Sprinkler Allowance - () Other Temp.Rat.155
G Hose Allowance - Outside - 250
N

Note

Calculation Flow Required - 407.054 Press Required - 52.216 At Test
Summary C-Factor Used: 120 Overhead 140 Underground

W Water Flow Test: Pump Data: Tank or Reservoir:
A Date of Test - 7/19/2009 Cap. -
T Time of Test - Rated Cap.- Elev.-
E Static Press - 83 @ Press -
R Residual Press - 0 Elev. - Well
Flow - 1342 Proof Flow
S Elevation -

U
P Location -
P
L Source of Information - PORTLAND WATER DISTRICT
Y


Water Supply Curve (C)

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC3

Page 2
Date 1/22/13

City Water Supply:
C1 - Static Pressure : 83
C2 - Residual Pressure: 0
C2 - Residual Flow : 1342

Demand:
D1 - Elevation : 2.995
D2 - System Flow : 157.054
D2 - System Pressure : 52.216
Hose (Adj City) :
Hose (Demand) : 250
D3 - System Demand : 407.054
Safety Margin : 21.651



Pressure / Flow Summary - STANDARD

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC3

Page 4
Date 1/22/13

| Node No. | Elevation | K-Fact | Pt Actual | Pn | Flow Actual | Density | Area | Press Req. |
|----------|-----------|--------|-----------|----|-------------|---------|------|------------|
| 304 | 6.916 | 5.6 | 12.13 | na | 19.5 | 0.15 | 130 | 7.0 |
| 303 | 6.916 | 5.6 | 13.12 | na | 20.28 | 0.15 | 130 | 7.0 |
| 302 | 6.916 | 5.6 | 18.89 | na | 24.34 | 0.15 | 130 | 7.0 |
| 301 | 6.916 | 5.6 | 21.91 | na | 26.21 | 0.15 | 130 | 7.0 |
| 306 | 6.916 | 5.6 | 14.21 | na | 21.11 | 0.15 | 130 | 7.0 |
| 307 | 6.916 | 5.6 | 13.82 | na | 20.82 | 0.15 | 130 | 7.0 |
| 35 | 6.916 | | 15.07 | na | | | | |
| 305 | 6.916 | 5.6 | 19.59 | na | 24.79 | 0.15 | 130 | 7.0 |
| 34 | 6.916 | | 25.45 | na | | | | |
| 33 | 6.916 | | 25.81 | na | | | | |
| 32 | 6.916 | | 40.11 | na | | | | |
| 31 | 6.416 | | 42.58 | na | | | | |
| 30 | 6.416 | | 49.11 | na | | | | |
| 2 | 6.416 | | 49.21 | na | | | | |
| 1 | 0.0 | | 52.2 | na | | | | |
| TEST | 0.0 | | 52.22 | na | 250.0 | | | |

The maximum velocity is 19.38 and it occurs in the pipe between nodes 301 and 33

Final Calculations - Hazen-Williams

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC3

Page 5
Date 1/22/13

| Hyd. Ref. Point | Qa Qt | Dia. "C" Pf/Ft | Fitting or Eqv. Ln. | Pipe Ftnng's Total | Pt Pe Pf | Pt Pv Pn | ***** | Notes | ***** |
|-----------------|----------|-------------------|------------------------|-----------------------|----------------|----------------|-------|------------------|-------|
| 304 | 19.50 | 1.049 | | 8.000 | 12.125 | | | K Factor = 5.60 | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | | | |
| 303 | 19.5 | 0.1242 | 0.0 | 8.000 | 0.994 | | | Vel = 7.24 | |
| 303 | 20.28 | 1.049 | 0.0 | 12.416 | 13.119 | | | K Factor = 5.60 | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | | | |
| 302 | 39.78 | 0.4644 | 0.0 | 12.416 | 5.766 | | | Vel = 14.77 | |
| 302 | 24.34 | 1.38 | 0.0 | 10.250 | 18.885 | | | K Factor = 5.60 | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | | | |
| 301 | 64.12 | 0.2954 | 0.0 | 10.250 | 3.028 | | | Vel = 13.75 | |
| 301 | 26.21 | 1.38 | 1T 6.0 | 1.000 | 21.913 | | | K Factor = 5.60 | |
| to | | 120 | 0.0 | 6.000 | 0.0 | | | | |
| 33 | 90.33 | 0.5569 | 0.0 | 7.000 | 3.898 | | | Vel = 19.38 | |
| | 0.0 | | | | | | | | |
| | 90.33 | | | | 25.811 | | | K Factor = 17.78 | |
| 306 | 21.11 | 1.049 | 1T 5.0 | 1.000 | 14.212 | | | K Factor = 5.60 | |
| to | | 120 | 0.0 | 5.000 | 0.0 | | | | |
| 35 | 21.11 | 0.1437 | 0.0 | 6.000 | 0.862 | | | Vel = 7.84 | |
| | 0.0 | | | | | | | | |
| | 21.11 | | | | 15.074 | | | K Factor = 5.44 | |
| 307 | 20.82 | 1.049 | 0.0 | 8.916 | 13.824 | | | K Factor = 5.60 | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | | | |
| 35 | 20.82 | 0.1402 | 0.0 | 8.916 | 1.250 | | | Vel = 7.73 | |
| 35 | 21.11 | 1.049 | 0.0 | 8.830 | 15.074 | | | | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | | | |
| 305 | 41.93 | 0.5120 | 0.0 | 8.830 | 4.521 | | | Vel = 15.57 | |
| 305 | 24.79 | 1.38 | 1T 6.0 | 12.416 | 19.595 | | | K Factor = 5.60 | |
| to | | 120 | 0.0 | 6.000 | 0.0 | | | | |
| 34 | 66.72 | 0.3179 | 0.0 | 18.416 | 5.855 | | | Vel = 14.31 | |
| 34 | 0.0 | 2.157 | 0.0 | 10.000 | 25.450 | | | | |
| to | | 120 | 0.0 | 0.0 | 0.0 | | | | |
| 33 | 66.72 | 0.0361 | 0.0 | 10.000 | 0.361 | | | Vel = 5.86 | |
| 33 | 90.33 | 2.157 | 1E 6.153 | 75.083 | 25.811 | | | | |
| to | | 120 | 0.0 | 6.153 | 0.0 | | | | |
| 32 | 157.05 | 0.1760 | 0.0 | 81.236 | 14.297 | | | Vel = 13.79 | |
| 32 | 0.0 | 2.157 | 1T 12.307 | 0.500 | 40.108 | | | | |
| to | | 120 | 0.0 | 12.307 | 0.217 | | | | |
| 31 | 157.05 | 0.1759 | 0.0 | 12.807 | 2.253 | | | Vel = 13.79 | |
| 31 | 0.0 | 2.157 | 1T 12.307 | 24.830 | 42.578 | | | | |
| to | | 120 | 0.0 | 12.307 | 0.0 | | | | |
| 30 | 157.05 | 0.1760 | 0.0 | 37.137 | 6.536 | | | Vel = 13.79 | |
| 30 | 0.0 | 4.26 | 1E 13.167 | 2.000 | 49.114 | | | | |
| to | | 120 | 0.0 | 13.167 | 0.0 | | | | |
| 2 | 157.05 | 0.0064 | 0.0 | 15.167 | 0.097 | | | Vel = 3.54 | |

Final Calculations - Standard

FREEDOM FIRE PROTECTION INC.
178 MIDDLE STREET HC3

Page 6
Date 1/22/13

| Hyd. Ref. Point | Qa Qt | Dia. "C" Pf/Ft | Fitting or Eqv. Ln. | Pipe Ftng's Total | Pt Pe Pf | Pt Pv Pn | ***** Notes ***** |
|-----------------------|------------------|------------------------|---------------------------|---------------------------|--------------------------|----------------|---------------------------------|
| 2 to 1 | 0.0 157.05 | 4.026 120 0.0084 | 1A 17.0 1G 2.0 0.0 | 6.416 19.000 25.416 | 49.211 2.779 0.214 | | Vel = 3.96 |
| 1 to TEST | 0.0 157.05 | 6.16 140 0.0008 | 0.0 0.0 0.0 | 15.000 0.0 15.000 | 52.204 0.0 0.012 | | Vel = 1.69 |
| | 250.00 407.05 | | | | 52.216 | | Qa = 250.00 K Factor = 56.33 |