

The Existing Bracket is steel and affixed to the building with Lags and Lagshields.
The sign panel is Painted SignFoam with either painted routed Logo or HP Vinyl lettering.
Stainless Steel screws will hold the sign panel to the bracket.

