

TYPE	DESCRIPTION	LIGHT SOURCE	MANUFACTURER & CATALOG NUMBER	MAX. WATTS	/ft
A	Surface mounted on wall, LED, down light, natural aluminum finish, 5" round monopoint canopy. Remote power supply/driver required.	Integral LED 3000 kelvin Wide Flood	B-K Lighting Alpine AP-LED-X47-WFL-SAP-12-E	45	
B	Letter Not Used			0	
C	Recessed in wall/stair riser, LED, rectangular, louvered step light; core drill mounting; machined brass finish; Remote power supply/driver required.	Integral LED 3000 kelvin	B-K Lighting Brick Star S-CD-BQL-LED-e65-A9-MACD	10	
D	Horizontal 2" pipe mounted with heavy duty aluminum C-clamp, 120 volt, color changing LED, ip66 rated; half shield; silver finish; outdoor power lead included, DMX protocol, control with ETC control system. *10 fixtures max. per 15 amp circuit	Integral 7 color LED array	ETC Lighting Desire SELD60XTI-V-HH-ON Silver	*	
D1	Horizontal 2" pipe mounted with heavy duty aluminum C-clamp, 120 volt, fixed color LED, ip66 rated; top hat 6" tube shield; silver finish; outdoor power lead included, DMX protocol, control with ETC control system. *10 fixtures max. per 15 amp circuit	Integral LED 3000 kelvin	ETC Lighting Desire SELD40TO-5X+400PTH6	*	
G	Recessed in ground, LED, adjustable angle well light; soft focus lens, machined brass finish; Remote power supply.	Integral LED 3000 kelvin Wide Flood	B-K Lighting Well Star AW-LED-e22-WFL-A9-MAC-12	10	

Lighting Equipment Schedule
For Pricing Only

TYPE	DESCRIPTION	LIGHT SOURCE	MANUFACTURER & CATALOG NUMBER	MAX. WATTS	/ft
G1	Recessed in granite pavers, LED, adjustable angle well light; rectilinear lens, machined brass finish; Remote power supply.	Integral LED 3000 kelvin Wide Flood	B-K Lighting Well Star AW-LED-e22-WFL-A9- MAC-13	10	
G2	Recessed in granite pavers, LED, fixed angle 2.25" dia. Flush mount well light; soft focus lens, provision for colored gel; machined brass finish; Remote power supply.	Integral LED 3000 kelvin Medium Flood	B-K Lighting Mini- Micro B-UL-F-MM-LED- e71-MFL-A9-MAC-12	10	
G3	Recessed in granite pavers, LED, fixed angle 4" dia. Flush mount well light; soft focus lens, provision for colored gel; machined brass finish; Remote power supply.	Integral LED 3000 kelvin Medium Flood	B-K Lighting Artistar B- UL-F-AR-LED-e65-MFL- A9-MAC-12	10	
G4	Recessed in granite pavers, LED, fixed angle 5" dia. Flush mount well light; soft focus lens, provision for colored gel; machined brass finish; Remote power supply.	Integral LED 3000 kelvin Flood	B-K Lighting Denali B- UL-F-DE-LED-x31-FL- MAC-12	20	