

**COMcheck Software Version 4.0.0**  
**Interior Lighting Compliance Certificate**

**Project Information**

Energy Code: 90.1 (2007) Standard  
 Project Title: Fatface  
 Project Type: Alteration  
 Construction Site: 34 Exchange Street, Portland, ME 04104  
 Owner/Agent: Fiskaa, 589 8th Ave, New York, NY 10018  
 Designer/Contractor: Fiskaa, 589 8th Ave, New York, NY 10018

**Allowed Interior Lighting Power**

A Area Category	B Floor Area (ft <sup>2</sup> )	C Allowed Watts / ft <sup>2</sup>	D Allowed Watts (B X C)
1-Sales/Storefront/Cashwrap (Retail/Sales Area)	1312	1.70	2230
Allowance: Furniture, clothing, cosmetics highlighting / Fix. ID: C Track 40.8W	660 (a)	2.60	1200 (b)
Allowance: Furniture, clothing, cosmetics highlighting / Fix. ID: C Track 40.8W	300 (a)	2.60	780 (b)
Allowance: Furniture, clothing, cosmetics highlighting / Fix. ID: A/B Track 55W	60 (a)	2.60	156 (b)
2-Fitting Room (Common Space Types:Dressing/Locker/Fitting Room)	77	0.50	46
3-Entrance (Common Space Types:Corridor/Transition)	49	0.50	24
4-Main Office (Common Space Types:Office - Enclosed)	61	1.10	67
5-Stock (Common Space Types:Active Storage)	865	0.80	692
6-Restroom (Common Space Types:Restrooms)	55	0.90	50
7-Pantry (Common Space Types:Conference/Meeting/Multipurpose)	108	1.30	140
8-Stairs (Common Space Types:Stairs-Active)	76	0.60	46
Supplemental Allowed Watts (c) =			234
Total Allowed Watts =			5666

- (a) Area claimed may exceed total floor area when Retail Merchandise Highlighting allowance(s) are specified.  
 (b) Allowance is (B x C) or the actual wattage of the fixtures given in Proposed Power section, whichever is less.  
 (c) Supplemental watts must be associated with retail merchandise highlighting fixtures.

**Proposed Interior Lighting Power**

A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	B Lamps/ Fixture	C # of Fixtures	D Fixture Watt.	E (C X D)
Sales/Storefront/Cashwrap (Retail/Sales Area 1312 sq.ft.)				
Track lighting 1 copy 3: C Track 40.8W: Sales Track: Wattage based on current limiting device capacity	0	0	1200	1200
Track lighting 1 copy 4: C Track 40.8W: Sales Track: Wattage based on current limiting device capacity	0	0	1080	1080
Track lighting 1 copy 5: C Track 40.8W: Sales Track: Wattage based on current limiting device capacity	0	0	840	840
Track lighting 1 copy 1: A/B Track 55W: Window Track: Wattage based on current limiting device capacity	0	0	330	330
Incandescent 2: P: Pendant: Incandescent 60W:	1	5	60	300
Fitting Room (Common Space Types:Dressing/Locker/Fitting Room 77 sq.ft.)				

Project Title: Fatface  
 Data filename: P:\2015 Projects\15.102.00 - Fatface-Portland, ME\02 - Internal Project Data\06 - Calculations\0 Page 1 of 6  
 Energy Code\Fatface - comcheck v3.cck

A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	B Lamps/ Fixture	C # of Fixtures	D Fixture Watt.	E (C X D)
LED 5 copy 1: D: Other:	1	4	52	208
Entrance (Common Space Types:Corridor/Transition 49 sq.ft.)				
Incandescent 1: P: Incandescent 60W:	1	3	60	180
LED 5: D: Other:	1	2	52	104
Main Office (Common Space Types:Office - Enclosed 61 sq.ft.)				
LED 2 copy 1: LP-1: Other:	1	1	48	48
LED 3 copy 1: F: Other:	1	10	3	30
Stock (Common Space Types:Active Storage 865 sq.ft.)				
Linear Fluorescent 1: SL: 48" T8 32W: Electronic:	2	11	64	704
Restroom (Common Space Types:Restrooms 55 sq.ft.)				
Linear Fluorescent 1 copy 1: SL: 48" T8 32W: Electronic:	2	1	64	64
Pantry (Common Space Types:Conference/Meeting/Multipurpose 108 sq.ft.)				
Linear Fluorescent 1 copy 2: SL: 48" T8 32W: Electronic:	2	1	64	64
LED 2: LP-1: Other:	1	1	48	48
LED 3: F: Other:	1	10	3	30
Stairs (Common Space Types:Stairs-Active 76 sq.ft.)				
Linear Fluorescent 1 copy 2: SL: 48" T8 32W: Electronic:	2	2	64	128
Total Proposed Watts =				5358


**Interior Lighting PASSES**

**Interior Lighting Compliance Statement**

Compliance Statement: The proposed interior lighting alteration on building plans, specifications, and other calculations submitted with systems have been designed to meet the 90.1 (2007) Standard req mandatory requirements listed in the Inspection Checklist.

This document is consistent with the proposed interior lighting < Version 4.0.0 and to comply with the

Name - Title \_\_\_\_\_ Signature \_\_\_\_\_ Date \_\_\_\_\_



Project Title: Fatface  
 Data filename: P:\2015 Projects\15.102.00 - Fatface-Portland, ME\02 - Internal Project Data\06 - Calculations\0 Page 2 of 6  
 Energy Code\Fatface - comcheck v3.cck

BARRY MICHAEL LUDLOW, AIA ARCHITECT  
 102 ROSE LANE GARDEN, CT 06820  
 TELEPHONE 646.747.3736 EMAIL B.LUDLOW@DESIGNREPUBLIC.US.COM

CLIENT/OWNER/TENANT  
 FAT FACE LTD  
 1-3 RIDGWAY HAVANT, PO9 1QJ  
 UNITED KINGDOM  
 CONTACT: DAVID LILLEY  
 TEL: 0044.2392.441100  
 E: DAVID.LILLEY@FATFACE.COM

DESIGNER  
 BOX OF FROGS LTD  
 2 WILLOW PARK STROKE POGES BUCKS SL2 4ES  
 CONTACT: SARAH MALCOM-RICHARDS  
 TEL: 007748606997  
 E: SARAH@BOXOFFROGS.WEB.COM


MEP ENGINEER  
 FISKAA  
 589 8TH AVENUE  
 NEW YORK, NY, 10018  
 CONTACT: ERIC MARTINSEN  
 TEL: 212.736.9500  
 E: EMARTINSEN@FISKAA.COM

Issue	Date	Issue	Date
A. ISSUE FOR LL REVIEW & HISTORIC REVIEW	07/10/2015		
B. ISSUE FOR DEMO PERMIT	07/20/2015		
C. ISSUE FOR PERMIT	07/24/2015		

Project:  
**FAT FACE PORTLAND**  
**34 EXCHANGE STREET**  
**PORTLAND, ME 04104**

Drawing Title  
**COMCHECK FORMS**

Project No. 15.102.00  
 Drawn By JM  
 Date ---  
 Scale ---  
 Floor(s) ---



Drawing No.  
**E-103**