



- KEY NOTES:**
- CAM LOCK WITH NICKEL PLATED FINISH
 - GROMMET BY DOUG MOCKETT NUMBER BG5 (1 1/2" DIA) FINISH: SATIN CHROME (26D).
 - GROMMET BY DOUG MOCKETT NUMBER BG3 (1 1/2" DIA) FINISH: MATTE BLACK (80).
 - 'STRUCT U RAIL' SYSTEM by LIVERS ANCHORED TO SLAB WITH HILTI KWIK BOLT 1/2" DIA FINISH: STAINLESS STEEL (304) ANCHORS SPACED AT 12" ON CENTER WITH A MINIMUM 2" EFFECTIVE EMBEDMENT INTO THE EXISTING CONCRETE SLAB ON GRADE (EXISTING SLAB SHALL BE 4" MIN THICKNESS AND FC = 3000 PSI MIN). ANCHORS SHALL HAVE A MINIMUM 5" CONCRETE EDGE DISTANCE.
 - 2-GANG POWER OUTLETS FLUSH IN MILLWORK TO BE INSTALLED BY ELECTRICIAN IN FIELD. G.C. TO COORDINATE INSTALLATION. REFER TO ID-301 AND ELECTRICAL DRAWINGS FOR COORDINATION.
 - 1-GANG TEL/DATA JACK FLUSH IN MILLWORK TO BE INSTALLED BY TEL/DATA CONTRACTOR IN FIELD. G.C. TO COORDINATE INSTALLATION. REFER TO ID-301 AND ENGINEERING DRAWINGS FOR COORDINATION.
 - RAM-101U-B-246 MONITOR MOUNT. FLAT BLACK.
 - 9" LAZY SUSAN BY TRIANGLE WITH STOPS AT 15 DEGREES and 345 DEGREES.
 - LS-40-D JOHNSONITE SUBFLOOR LEVELER
- GENERAL NOTES:**
- REFER TO DRAWING ID-010 FOR FINISH LEGEND
 - REFER TO ID-301 FOR EQUIPMENT LEGEND

KLING STUBBINS

2301 Chestnut Street
Philadelphia, Pennsylvania
19103

P 215.569.2900
F 215.569.5963
W www.klingstubbins.com

Fidelity's Engineering Consultant:

RDK ENGINEERS

Richard D. Kimball Company, Inc.

Seaport Center
Boston, MA 02210-1964

P 617-345-8885
F 617-345-4226
W www.rdkengineers.com

Seals:

Joseph A. Castner, Maine License No. 3583

General Notes:

Project Title:

Fidelity INVESTMENTS

Fidelity Real Estate Company
245 Summer Street
Boston, MA 02110

Fidelity Investor Center
3 Canal Plaza
Portland, ME 04112
Branch ID No. 120

Number	Description	Date
1	ISSUED FOR PERMIT & CONST	03 OCT 14

Ka Plan: Project North

CAD File: PDR_ID-840.dgn
Project No: K2812515 R24
Copyright: 2014 KlingStubbins, Inc or LLC

Drawing Sheet Title:

TRADING KIOSK PLAN, ELEVATIONS AND DETAILS

Drawing Sheet Number:
ID-840

Owner's Drawing Sheet No.:

K:\K2812515\2515R24\Portland ME\Examination\Design\Discipline\Interior\POR_ID-840 (Trading Kiosk).dgn
 Printed on Tuesday, September 30, 2014 at 12:08PM
 kmackenzie