LIGHTING FIXTURE SCHEDULE

TYPE	MANUFACTURERS	CATALOG NUMBER	DESCRIPTION	LAMPS	IMPUT

PORCELAIN & CERAMIC TILE				NO.	TYPE	VOLTS	WATTS
C	LIGHTOLIER	#C6L15NUVBZ10V	CALCULITE LED 6" RECESSED DOWNLIGHT	1	3500K/ 3000 LUMEN	120	36

FINISH SCHEDULE

KEY	SPECIFICATION	LOCATION	REMARKS
PORCELAIN & CERAMIC TILE			
T-21	MFG: DAL TILE NAME: PTS FABRIQUE NUMBER: P690 COLOR: GRIS LINEN - unpolished SIZE: 12" x 24" x 3/8" 4" x 24" x 3/8" @ BASE (cut floor tile to size, exposed edge @ wall covering to be factory finished edge)	TOILET ROOM FLOORS	GROUT FOR FLOOR: MFG: BOSTIK TRUCOLOR GROUT COLOR: DELOREAN GRAY H160 1 / 8" THICK GROUT JOINT AS PER MFG RECOMMENDATIONS. ANTI-FRACTURE MEMBRANE-DITRA BY SCHULTER SYSTEMS REQUIRED TO BE USED
T-22	MFG: AMERICAN OLEAN NAME: URBAN CANVAS WALL NUMBER: 0025 COLOR: ICE WHITE SIZE: 4 1/4" x 12 3/4" FIELD TILE, 4 1/4" x 8 1/2" FLAT COVE BASE AND 2" x 6" BULLNOSE (TRIM FROM AMERICAN OLEAN URBAN CANVAS AND BRIGHT & WHITE COLLECTION)	TOILET ROOM WALLS, FIEILD, BULL NOSE & COVE BASE	GROUT FOR WALLS: MFG: LATICRETE PERMA COLOR GROUT COLOR: 44 BRIGHT WHITE 1 / 16" THICK GROUT JOINT AS PER MFG RECOMMENDATIONS
T-23	MFG: CROSSVILLE NAME: GLASS BLOX NUMBER: G046 COLOR: ICED TEA SIZE: 1 / 2" x 6" AND 2" x 4"	TOILET ROOM WALLS, ACCENT TILE	GROUT FOR WALLS: MFG: LATICRETE PERMA COLOR GROUT COLOR: 44 BRIGHT WHITE
PAINT			
P-4	MANUF SHERWIN WILLIAMS (NO SUBSTITUTES) NAME: CEILING BRIGHT WHITE COLOR: SW7007 FINISH: FLAT	GWB CEILING	FLAT FINISH ON GWB CEILINGS
P-5	MFG: SHERWIN WILLIAMS (NO SUBSTITUTES) NAME: SAND BEACH COLOR: SW 7529 FINISH: EGGSHELL FINISH	RESTROOM WALLS ABOVE CERAMIC TILE WAINSCOT	
CEILING FINISH			
ACT-1	MFG: ARMSTRONG NAME: ULTIMA, 1912 COLOR: WHITE SIZE: 24" X 24" X BEV. TEGULAR		ARMSTRONG SHADOW WALL MOLDING #7874 WHITE (1/4" REVEAL & 9/16" FLANGE)
GRID	MFG: ARMSTRONG NAME: SILHOUETTE XL (9/16") w/ 1/4" REVEAL COLOR: WHITE		
CEILING FINISH - ALTERNATE			
ACT-1	MFG: CERTANITEED NAME: SYMPHONY m COLOR: WHITE SIZE: 24" X 24" X BEV. TEGULAR		CERTAINTEED SHADOWLINE WALL MOLDING COLOR: WHITE (1/4" REVEAL & 9/16" FLANGE)
GRID	MFG: CERTAINTEED NAME: 9/16" SMOOTHLINE BOLT SLOT w/ 1/4" REVEAL COLOR: WHITE		

4 PROPOSED FINISH PLAN
DSK-201 SCALE: 1/4" = 1'-0"

FINISH PLAN NOTES

(A) FULL START TILE. SEE DETAIL 2/DSK-810.

(B) SEE SHEET DSK-810 FOR NEW FINISH EXTENTS IN TOILET ROOMS.

3 PROPOSED REFLECTED CEILING PLAN
DSK-201 SCALE: 1/4" = 1'-0"

RCP NOTES

(1) STARTING POINT OF NEW GRID

(2) PROVIDE SHADOW MOLDING BETWEEN GWB AND ACT.

RCP SHEET NOTES

1. ALL CEILING GRID TO BE ACT-1, U.N.O.
2. ALL LIGHT FIXTURES TO BE PLACED IN CENTER OF CEILING TILE, U.N.O.
3. DIMENSIONS SHOWN ARE FROM CENTER LINE OF LIGHT FIXTURE U.N.O.

2 PROPOSED ARCHITECTURAL PLAN
DSK-201 SCALE: 1/4" = 1'-0"

ARCHITECTURAL NOTES

1. PROVIDE ADDITIONAL UNISTRUT FRAMING CONCEALED ABOVE CEILING FOR SUPPORT OF SUSPENDED TOILET PARTITION ASSEMBLIES. LATERALLY BRACE, TYPICAL.
2. INSTALL NEW TOTO UNDERMOUNT BATHROOM SINKS, MODEL: LT542G#01, COTTON 20-7/8", FAUCET: ELECTRONIC FAUCET, MODEL: K-13468, SOLID SURFACE COUNTER TOP
3. INSTALL NEW SOAP DISPENSER: BOBRICK SUREFLO AUTOMATIC, TOP FILL BULK FOAM SOAP DISPENSER, MODEL: B-828
4. INSTALL NEW WATER CLOSETS: AMERICAN STANDARD RAPIDWAY ELONGATED TOILET, ADA COMPLIANT, VALVE: TOTO TET1LN SERIES HIGH-EFFICIENCY TOILET ECOPOWER FLUSHOMETER VALVE, 1.28 GPF
5. INSTALL NEW WASTE RECEPTACLE: BOBRICK CONTURA SERIES RECESSED WASTE RECEPTACLE #B-43644
6. INSTALL NEW HAND DRYER: XLERATOR: XL-SB BRUSHED STAINLESS STEEL FINISH W/ S.S. WALL GUARD 89S MOUNT BOTTOM OF HAND DRYER @ 44" A.F.F.
7. INSTALL NEW TOILET PAPER DISPENSER: BOBRICK CONTURA SERIES RECESSED MULTI-ROLL TOILET TISSUE DISPENSER #B-4388

1 PROPOSED DEMOLITION PLAN
DSK-201 SCALE: 1/4" = 1'-0"

DEMOLITION NOTES

(1) REMOVE ALL EXISTING PLUMING FIXTURES. INSTALL NEW TOTO UNDERMOUNT BATHROOM SINKS

(2) EXISTING MIRRORS SHALL BE REMOVED

(3) REMOVE EXISTING CEILING SYSTEM AND LIGHTING.

(4) REMOVE EXISTING WALL AND FLOOR FINISHES THROUGHOUT. PREP SURFACES FOR NEWLY SPECIFIED FINISHES.

(5) REMOVE EXISTING TOILET PARTITIONS AND ACCESSORIES.

JACOBS
Jacobs Consultants, Inc.
2301 Chestnut Street
Philadelphia, Pennsylvania
19103

P 215.569.2900
F 215.569.5969
W www.jacobs.com

Fidelity's Engineering Consultant:
RDK ENGINEERS
Richard D. Kimball Company, Inc.
Seaport Center
Boston, MA 02210-1964

P 617-345-9885
F 617-345-6226
W www.rdkengineers.com

Seals:

General Notes:

Project Title:
Fidelity INVESTMENTS
Fidelity Real Estate Company
Seaport World Trade Center
200 Seaport Boulevard
Boston, MA 02210

Fidelity Investor Center
3 Canal Plaza
Portland, ME 04112
Branch ID No. 120

Number	Description	Date
		03 MAR 16

Key Plan:

Project North

CAD File:	POR_DSK-201.dgn
Project No.:	K2812517 R11
Copyright:	2016 Jacobs Consultants, Inc.

Drawing Sheet Title:
PROPOSED COMMON TOILET ROOM FINISH CHANGES

Drawing Sheet Number:
DSK-201

Owner's Drawing Sheet No.:

Inspection Division
Date: 08/11/16