1 PROPOSED ENLARGED TOILET ROOM PLAN
DSK-810 SCALE: 1/2" = 1'-0"

2 FLOOR TILE START POINT DETAIL
DSK-810 SCALE: N.T.S.

3 TOILET ROOM ELEVATIONS
DSK-810 SCALE: 1/2" = 1'-0"

TOILET ACCESSORIES

1. WASTE RECEPTACLE: BOBRICK CONTURA SERIES RECESSED WASTE RECEPTACLE #B-43644
2. 36" GRAB BAR MOUNT HORIZONTAL BOBRICK B-5806.99
3. 42" GRAB BAR MOUNT HORIZONTAL BOBRICK B-5806.99
4. SURFACE MOUNTED TOILET SEAT COVER DISPENSER BOBRICK B-221
5. PARTITION MOUNTED MULTI-ROLL TOILET TISSUE DISPENSER BOBRICK B-386 (SERVES TWO COMPARTMENTS)
5A. TOILET PAPER DISPENSER: BOBRICK CONTURA RECESSED MULTI-ROLL DISPENSER #B-4388
6. PARITION MOUNTED SANITARY NAPKIN DISPOSAL BOBRICK B-354 (SERVES TOW COMPARTMENTS)
6A. RECESSED SANITARY NAPKIN DISPOSAL BOBRICK B-35303
7. HAND DRYER: XLERATOR: XL-SB, MOUNT BOTTOM OF HAND DRYER @ 44" A.F.F.
8. WATER CLOSETS: AMERICAN STANDARD RAPIDWAY ELONGATED TOILET
9. TOTO UNDERMOUNT BATHROOM SINKS, MODEL: LT542G#01, COTTON 20-7/8", FAUCET: ELECTRONIC FAUCET, MODEL: K-13468, SOLID SURFACE COUNTER TOP: CAESARSTONE, QUARTZ SURFACES, (OR EQUAL) ATLANTIC SALT, #6270
10. COAT HOOK MOUNTED ON BACK OF DOOR: 60" AFF ON 24" DOORS AND 48" ON 34" DOORS. MODEL: PETER PEPPER 2035AL
11. TOILET PARTITIONS:

MNF:	GLOBAL PARTITIONS
PARTITIONS:	STEEL W/ WHITE (#2129) BAKED ENAMEL FINISH, SOUND DEADENING HONEYCOMB & INTERNALLY REINFORCED FOR HARDWARE.
THICKNESS:	1" FINISH THICKNESS FOR DOORS, PANELS, AND SCREENS 1 1/2" FINISH THICKNESS FOR PILASTERS.
COMPARTMENTS:	CEILING HUNG
URINAL SCREENS:	NOT USED
DOORS:	24" IN SWING & 34" OUT SWING
HARDWARE:	ALL HARDWARE TO BE STAINLESS STEEL.
MISC:	HINGE: SELF CLOSING WITH HOLD OPEN UP TO 90d LATCH AND KEEPER: SURFACE MOUNTED WITH EMERGENCY ACCESS AND COMBINED RUBBER FACED DOOR STRIKE AND KEEPER COAT HOOK: INSIDE OF DOOR DOOR BUMPER: ON OUT SWING DOOR OR ENTRANCE SCREEN DOOR DOOR PULL: ON OUTSWING DOORS AND ON BOTH SIDES OF ADA INDICATED DOOR

12. SOAP DISPENSER: BOBRICK SUREFLO AUTOMATIC, TOP FILL BULK FOAM SOAP DISPENSER, MODEL: B-828

PLAN NOTES

1. REFER TO DETAIL 3, THIS SHEET, FOR EXTENT OF TILE ON PARTITIONS SCHEDULED TO RECEIVE TILE.
2. TOILET ACCESSORIES - ADDITIONAL INFORMATION SEE SHEET DSK-201
3. SEE DSK-201 FOR TILE PATTERN. SEE DETAIL 2 THIS SHEET FOR TILE START POINT.
4. PROVIDE ADDITIONAL BLOCKING AND FRAMING ABOVE CEILING FOR SUPPORT OF TOILET PARTITIONS.
5. PROVIDE WATERPROOF MEMBRANE FOR FULL EXTENT OF FLOOR TILE INSTALLATION. EXTEND MEMBRANE UP WALLS 6" TO BE SCHLUTER "KERDI SYSTEM" OR EQUAL.
6. RE-INSTALL EXISTING MIRRORS.

SHEET NOTES

1. SEE FINISH SCHEDULE ON SHEET DSK-201.

JACOBS
Jacobs Consultants, Inc.
2301 Chestnut Street
Philadelphia, Pennsylvania
19103
P 215.569.2900
F 215.569.5963
W www.jacobs.com

Fidelity's Engineering Consultant:
RDK ENGINEERS
Richard D. Kimball Company, Inc.
Seaport Center
Boston, MA 02210-1964
P 617-345-9885
F 617-345-4226
W www.rdkengineers.com

Scale:

General Notes:

Project Title:
Fidelity INVESTMENTS
Fidelity Real Estate Company
Seaport World Trade Center
200 Seaport Boulevard
Boston, MA 02210

Fidelity Investor Center
3 Canal Plaza
Portland, ME 04112
Branch ID No. 120

Number	Description	Date
		03 MAR 16

Key Plan:
Project North

CAD File: POR_ID-810.dgn
Project No.: K2812517 R11
Copyright: 2016 Jacobs Consultants, Inc.

Drawing Sheet Title:
PROPOSED ENLARGED TOILET ROOM PLANS FINISH ALTERATIONS

Drawing Sheet Number:
DSK-810

Owner's Drawing Sheet No.: