




GENERAL NOTES:

- IT IS THE BUILDING OWNERS RESPONSIBILITY TO PROVIDE ADEQUATE HEAT FOR ALL AREAS IN THE BUILDING PROTECTED BY WET SPRINKLER SYSTEMS AND FOR ALL WATER FILLED SUPPLY PIPES, VALVES AND SYSTEM RISERS IN ALL DRY PIPE SPRINKLER SYSTEMS.
- ALL NEW PIPING IS TO BE HYDROSTATICALLY TESTED AT NOT LESS THAN 200 PSI FOR 2 HOURS, OR AT 50 PSI IN EXCESS OF THE MAXIMUM PRESSURE, WHEN THE MAXIMUM PRESSURE TO BE MAINTAINED IS IN EXCESS OF 150 PSI. (PER NFPA 13)
- WHETHER OR NOT INDICATED ON DRAWINGS, THE FOLLOWING ITEMS ARE TO BE PROVIDED:
 - . SPARE HEAD CABINET WITH WRENCH (NFPA 13)
 - . PROVISIONS FOR FLUSHING CONNECTIONS AND DRAINING OF ALL PIPE.
 - . INSPECTORS TEST CONNECTION SHALL BE PROVIDED FOR EACH SYSTEM
 - A) FOR WET PIPE SYSTEMS SEE NFPA 13)
 - B) FOR DRY PIPE SYSTEMS SEE NFPA 13)
 - . AIR PRESSURE SHALL BE MAINTAINED ON ALL DRY PIPE SYSTEMS BY AN APPROVED AUTOMATIC AIR COMPRESSOR OR PLANT AIR SYSTEM SPECIFICALLY APPROVED FOR AND CAPABLE OF AUTOMATICALLY MAINTAINING THE REQUIRED AIR PRESSURE.
 - . GRIDDED WET PIPE SYSTEMS SHALL BE PROVIDED WITH A RELIEF VALVE NOT LESS THAN 1/4" IN SIZE. (NFPA 13).
- ALL PIPE 1" SHALL BE SCHEDULE 40 STEEL WITH MALLEABLE IRON FITTINGS.
- ALL PIPE 1 1/2" AND LARGER, SHALL BE SCHEDULE 10 STEEL, WITH GROOVED COUPLINGS AND VICTAULIC® MECHANICAL FITTINGS OR EQUIVALENT.
- ALL MECHANICAL TRADES ARE TO COORDINATE THEIR WORK WITH SPRINKLER WORK AS SHOWN ON THESE PLANS.
- ALL HANGERS AND LOCATIONS ARE TO BE IN ACCORDANCE WITH N.F.P.A. 13.
- ALL SPRINKLER HEADS IN SUSPENDED CEILING TILES ARE TO BE LOCATED IN THE CENTER OF THE ACUSTICAL CEILING PANEL.
- ALL PIPING IS TO BE PITCHED IN ACCORDANCE WITH N.F.P.A. 13.
- HYDRAULIC DATA REFERENCE POINTS: (B)
- CENTER LINE OF PIPE ABOVE FINISH FLOOR: VARIES
- PROTECTIVE CAPS ARE TO REMAIN ON THE SPRINKLER HEADS UNTIL AFTER CEILINGS ARE INSTALLED.
- WHERE SURFACE MOUNTED OBSTRUCTIONS EXIST DEEP ESCUTCHEON SPRINKLER HEADS WILL BE INSTALLED.
- WORK IS LIMITED TO THE WORK SHOWN ON THESE DOCUMENTS.



HYDRAULIC DATA NAMEPLATE

This Building is protected by a hydraulically designed Automatic Sprinkler System

Location AREA 1

No. of Sprinkler 12

Basis of design

1. Density .15 gpm/ft²
2. Design area of discharge 1125 ft²

System Demand

1. Water Flow Rate
- Base 252.30 gpm
2. Residual Pressure
- Base 86.813 psi
- CUSHION 43.308 psi

HYDRAULIC DATA NAMEPLATE

This Building is protected by a hydraulically designed Automatic Sprinkler System

Location AREA 2

No. of Sprinkler 9

Basis of design


1. Density .15 gpm/ft²
2. Design area of discharge ENTIRE ft²

System Demand


1. Water Flow Rate
- Base 182.95 gpm
2. Residual Pressure
- Base 78.003 psi
- CUSHION 54.914 psi

QUICK RESPONSE PENDENT DETAIL WITH OBSTRUCTION


SYMBOL = ●




SECTION 1 DETAIL
Scale: 1/4" = 1'



Fin. Flr. Elev. @ 186'-0"
Scale: 1/4" = 1'




STANDPIPE DETAIL: UP FROM MECH. ROOM
Scale: NTS



AREA ABOVE FILTER ROOMS
Scale: 1/4" = 1'

SUBMITTAL COPY

1. Type of Hazard LIGHT
2. Deflector Distance PER SPEC
3. Pipe Type Used BLK SCH 40/10
4. Sprinkler Area PER SPEC
5. Type of Construction NON-COMBUSTIBLE
6. Maximum Spacing Allowed PER NFPA 13
7. PIPE SIZING METHOD: PIPE SCHEDULE HYDRAULICALLY CALCULATED
8. ALL HANGERS AND LOCATIONS TO BE IN ACCORDANCE WITH N.F.P.A. PAMPHLET NO. 13
9. HIGH DEGREE TEMPERATURE SPRINKLER HEADS TO BE INSTALLED IN ACCORDANCE WITH N.F.P.A. PAMPHLET NO. 13



HANGERS

AS SHOWN IN DETAIL

ABBREVIATIONS

B	Bottom of Beam
D	Bottom of Deck
P	Bottom of Pipe
HV	Hot Valve
N & C	Nipple and Cap
NC	Not in Contract
NTS	Not to Scale
OSL	Open Bar Joist
PRV	Pressure Red Valve
RM	Roof Manifold
SF	Strap
T	Top of Beam
TYP	Typical
TOP	Top of Pipe
TOS	Top of Slab
UNLESS OTHERWISE NOTED	Unless Otherwise Noted
CL	Centerline
NAS	No Automatic Sprinklers
OTA	Open to Above

CONTRACT RESPONSIBILITIES

ITEM	FPC	OTHERS
STREET CONN	●	●
UGD MAN	●	●
EXCAVATION	●	●
FLUSHING	●	●
WRING	●	●
PAINTING	●	●
TAMPER SWITCHES	●	●
FLOW SWITCHES	●	●
STREET CONN	●	●

SPRINKLER HEAD LEGEND

SYMBOL	MAKE	MODEL	SIN	FINISH	TEMP	NPT	ORIFICE	K-FACTOR	TOTAL	
○	RELIABLE	F1FR	RA1414	WHITE	PENDENT	155' F	1/2"	1/2"	5.6	1
○	RELIABLE	F1FR	RA1425	BRONZE	UPRIGHT	200' F	1/2"	1/2"	5.6	44
									TOTAL	45

SUBMITTALS

SENT TO	DATE SENT	DATE RECEIVED
ISO	09/15/15	
FM		
LM		
IRI		
LA		
STATE FIRE		
LOCAL FIRE		
LOCAL WATER		
OWNER		

LICENSE# 093
R.M.S.# 442

PERMIT # ?????

P.O. BOX 1285
LEWISTON MAINE
04243-1285

3 CANAL PLAZA Mech. Pent.
3 CANAL PLAZA
PORTLAND, MAINE

CONTRACT WITH: EAST BROWN COW

SYSTEM TYPE	NO.	DATE	DESCRIPTION
WET			
DRY			
DELUGE			
PREACTION			
ME. LIFE			
HYDRO-PRO			

DATE: 09/15/2015
TOTAL 'SPRKS' ON JOB: 45
SHEET# 1 of 2
JOB# 15100