FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WAINSCOT	WALL MATERIAL	WALL FINISH ALL	N	E	S	W	CEILING MATL	CEILING HT.	TRIM	REMARKS OTHER
FIRST FLOOR														
101	RECEPTION	A	B1		GYP.	P1					ATC		P2	
102	EQUIPMENT ROOM	C	B2		GYP.	P1					ATC		P2	
103	WORK ROOM	C	B2		GYP.	P1					ATC		P2	
104	CABE	A	B2		GYP.	WC1					ATC		P2	
105	PANTRY	C	B2		GYP.	P1					ACT		P2	
106	OPEN OFFICE AREA	A	B1		GYP.	WC1					ATC		P2	
107	OFFICE	B	B1		GYP.	WC2					ATC		P2	
108	OFFICE	B	B1		GYP.	WC2					ATC		P2	
109	OFFICE	B	B1		GYP.	WC2					ATC		P2	
110	OFFICE	B	B1		GYP.	P1					ATC		P2	
111	OFFICE	B	B1		GYP.	P1					ATC		P2	
112	OFFICE	B	B1		GYP.	P1					ATC		P2	
113	OFFICE	B	B1		GYP.	WC2					ATC		P2	
114	OFFICE	B	B1		GYP.	WC2					ATC		P2	
115	OFFICE	B	B1		GYP	WC2					ATC		P2	
116	OFFICE	B	B1		GYP.	WC2					ATC		P2	
117	OFFICE	B	B1		GYP.	WC2					ATC		P2	
118	OFFICE	B	B1		GYP.	WC2					ATC		P2	
119	OFFICE	B	B1		GYP.	WC2					ATC		P2	
120	CONFERENCE ROOM	B	B1		GYP.	WC3					ATC		P2	

FINISH LEGEND

FINISH NO.	MATERIAL	DESCRIPTION
A	CARPET	SHAW CONTRACT: SURFACES EL #50320. COLOR # 20330 FAIRWAY
B	CARPET	SHAW CONTRACT: TROUBADOR 24 # 50290 COLOR # 95379 LODEN
C	VINYL TILE	ARMSTRONG EXCELON # 51810 WASHED LINEN & # 51802 SILVER GREEN - CHECKERBOARD
WC1	VINYL	MAHARAM FREESTYLE # 361304 COLOR # 08 DOESKIN
WC2	VINYL	MAHARAM CARLISLE CREPE # 382301 COLOR # 008 OYSTER
WC3	FABRIC	MAHARAM TEX-WALL "RAINDANCE" # 305801 COLOR # 004 NAVAJO
B1	WOOD	3" HIGH PAINT GRADE BIRCH: SEE DETAIL SHEETS FOR PROFILE
BT2	RUBBER	JOHNSONITE 4" HIGH COVE TYPE, COLOR: TO BE SELECTED.
P1	PAINT	SHERWIN WILLIAMS: EGGSHELL FINISH: COLOR # SW7102 CHENILLE WHITE
P2	PAINT	SHERWIN WILLIAMS: SEMI-GLOSS: COLOR # SW7101 CHINA DOLL

DOOR SCHEDULE

DOOR NO.	OPENING SIZE WIDTH	OPENING SIZE HEIGHT	DOOR THICKNESS	DOOR MATERIAL	DOOR TYPE	DOOR LOUVER	DOOR GLASS	FRAME MATERIAL	FRAME TYPE	THRES-HOLD	HARD-WARE	LABEL	REMARKS
NINTH FLOOR													
01	6'-0"	7'-0"	1-3/4"	H.M.	EXIST'G			H.M.	EXIST'G		EXIST'G	E	EXISTING TO REMAIN
01A	2'-6"	7'-0"	1-3/4"	WOOD	C			H.M.			H1		
02	3'-0"	7'-0"	1-3/4"	WOOD	B			H.M.			H3		
03	3'-0"	7'-0"	1-3/4"	WOOD	B			H.M.			H1		
04	3'-0"	7'-0"	1-3/4"	WOOD	B			H.M.			H4		
05	3'-0"	7'-0"	1-3/4"	WOOD	B			H.M.	EXIST'G		H2	C	
06	3'-0"	7'-0"	1-3/4"	WOOD	D			H.M.			H2	C	
07	3'-0"	7'-0"	1-3/4"	WOOD	B			H.M.			H1		
08	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		SIDELITE TO FIT OPENING
09	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
10	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
11	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
12	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
13	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
14	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		SIDELITE TO FIT OPENING
15	3'-0"	7'-0"	1-3/4"	WOOD	B			H.M.			H1		
16	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
17	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
18	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
19	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		
20	3'-0"	7'-0"	1-3/4"	WOOD	A			H.M.			H1		SIDELITE TO FIT OPENING

FINISH NOTES

1. ALL FLOOR SURFACES NOT OTHERWISE DESIGNATED SHALL RECEIVE FLOOR FINISH 'A'. FOR CARPET CLARIFICATION AND PRICING, CONTACT MR. TODD SHRINER SHAW CONTRACT - RICHMOND - TEL. NO. 684-762-4655.
2. ALL AREAS NOT DESIGNATED SHALL RECEIVE BASE B1.
3. ALL WALL SURFACES NOT DESIGNATED SHALL RECEIVE PAINT P1.
4. ALL SPECIFIED FINISHES SHALL BE APPLIED IN STRICT ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS FOR EACH SPECIFIC SUBSURFACE.
5. 12 X 12 SAMPLES OF ALL FINISH ITEMS SPECIFIED SHALL BE SUBMITTED TO MCCORMICK ARCHITECTS FOR REVIEW AND APPROVAL PRIOR TO ORDERING OR COMMENCEMENT OF WORK.
6. FLOORING SUBCONTRACTOR SHALL SUBMIT CARPET SEAMING PLANS FOR APPROVAL.
7. UNLESS OTHERWISE NOTED ON PLANS, FLOOR FINISH OF CLOSETS SHALL MATCH THAT OF AREAS FROM WHICH THEY ARE ENTERED.
8. PROVIDE APPROPRIATE TRANSITION STRIPS @ ALL INTERSECTIONS OF DISSIMILAR FLOORING TYPES. TRANSITION STRIP SHALL MATCH THE HARD SURFACE FLOORING.
9. ALL CARPET SHALL BE DIRECT GLUE-DOWN INSTALLATION.
10. ALL STAINED WOOD FINISH SHALL MATCH ARCHITECT SAMPLE SCOPE SHALL INCLUDE, BUT IS NOT LIMITED TO, DOORS BASE, AND SELECTED MILLWORK.
11. ALL HOLLOW METAL DOOR FRAMES TO BE PAINTED P2.
12. CONNECTOR COVERS TO BE PAINTED P2.
13. CONTRACTOR SHALL PROVIDE AND ADD ALTERNATE TO WRAP EXISTING DOUBLE HAL ENTRY DOORS WITH FLEXIWOOD FLEXIBLE VENEER.

DOOR AND FRAME TYPES

TYPE "A": 3'-0" X 7'-0" X 1 3/4" SOLID CORE, FLUSH PANEL, STAIN GRADE BIRCH DOOR SET IN A K.D. HOLLOW METAL FRAME WITH ARMACENT SIDELITE. SEE TYP. ELEVATION SHT. A5

TYPE "B": 3'-0" X 7'-0" X 1 3/4" TBK. SOLID CORE, FLUSH PANEL, STAIN GRADE BIRCH DOOR SET IN A K.D. HOLLOW METAL FRAME SIM. TO TYPE A.

TYPE "D": 2'-6" X 7'-0" X 1 3/4" TBK. SOLID CORE, FLUSH PANEL, STAIN GRADE BIRCH DOOR SET IN A K.D. HOLLOW METAL FRAME.

TYPE "E": 3'-0" X 7'-0" X 1 3/4" TBK. SOLID CORE FLUSH PANEL STAIN GRADE BIRCH VENEER - 'C' LABEL SET IN A HOLLOW METAL FRAME.

DOOR FRAME AND HARDWARE NOTES:

1. CONTRACTOR SHALL SUBMIT DOOR, FRAME & HARDWARE SCHEDULES FOR APPROVAL.
2. ALL SIDELITE PANELS SHALL BE CLEAR SAFETY GLASS.
3. ALL STAINED WOODS SHALL MATCH ARCHITECTS SAMPLE.
4. SEE ELEVATION SHEET FOR TYPICAL DOOR ELEVATION.

HARDWARE SET SCHEDULE

SET H1: 1 1/2 PAIR BUTT HINGES, CYLINDRICAL LEVER LATCHSET & FLOOR STOP.

SET H2: 1 1/2 PAIR BUTT HINGES: CYLINDRICAL LEVER LOCKSET, CLOSER & FLOOR STOP

SET H3: 1 1/2 PAIR BUTT HINGES CYLINDRICAL LEVER LOCKSET, CLOSER, FLOOR STOP, PERIMETER SEALS & AUTOMATIC DOOR BOTTOM

SET H4: 1 1/2 PAIR BUTT HINGES, MECHANICAL COMBINATION LOCK, CLOSER AND STOP.

HARDWARE SPECIFICATIONS

BUTT HINGES:	MCKINNEY, BALL BEARING TYPE, 4 1/2 X 4 1/2 USA OR EQUAL.
LATCHSETS:	SCHLAGE "D" SERIES HEAVY DUTY CYLINDRICAL LEVER TYPE WITH FLAIR KNOBS TRIM US4 OR EQUAL.
LOCKSETS:	SCHLAGE "D" SERIES HEAVY DUTY CYLINDRICAL LEVER TYPE WITH KNOBS TRIM US4 OR EQUAL.
CLOSERS:	SARGENT DOMERCLINE 1250 SERIES OR EQUAL AS REQUIRED BY DOOR FUNCTION. FINISH TO MATCH US4.
FLOOR STOPS:	GLAULEY HARDWARE, DOME TYPE US4 OR EQUAL. FURNISH RISER INSERTS AS REQUIRED.
PERIMETER DOOR SEALS:	ZERO INTERNATIONAL # 475A
AUTOMATIC DOOR BOTTOM:	ZERO INTERNATIONAL # 365A INCLUDING # 654 A FLAT SADDLE.
MECHANICAL PUSH BUTTON LOCK:	SIMPLEX 'UNICAN' W/ KEY OVERRIDE SERIES # 1800L

McCormick
Architects+
Designers, Inc.

40 24th Street
Pittsburgh
Pennsylvania
15222

Telephone
412.471.3800
Facsimile
412.471.2642

Project Title

FIRST UNION Securities

TWO CANAL PLAZA
PLAZA LEVEL

PORTLAND
MAINE

Revisions	By	Date
RE-ISSUED		2-9-01
⚠ REVISED AS SHOWN		2-9-01

Drawing Title

DOOR AND FINISH SCHEDULE

Project No. Sheet #1

Scale: 1/8" = 1'-0"

Drawn by: BW/BFA

Issue date: 12-21-00

A4