


KEY PLAN
N.T.S.


| IBC 2009 CODE DATA | | BUSINESS | | | |
|--|---|----------|----|--------------|---|
| USE GROUP CLASSIFICATION | 2A (SEE NOTE #0) | People | 0 | | |
| TYPE OF CONSTRUCTION | EXISTING TO REMAIN | SF | 00 | SF/ PERSON = | 0 |
| EXISTING BUILDING AREA | EXISTING TO REMAIN | | | | |
| PROPOSED BUILDING AREA | EXISTING TO REMAIN | | | | |
| TOTAL AREA OF WORK | 208 sqft | | | | |
| BUILDING HEIGHT (STORES/ FEET) | 10 STORES | | | | |
| BUILDING AREA LIMITATION - SQ FT (TABLE 503) | EXISTING TO REMAIN | | | | |
| BUILDING HEIGHT LIMITATION - STORES (TABLE 503) | EXISTING TO REMAIN | | | | |
| INCREASE STREET FRONTAGE (BOX AREA) - SQ FT | - | | | | |
| INCREASE AUTOMATIC SPRINKLER SYSTEM AREA (200% AREA) - SQ FT | - | | | | |
| INCREASE AUTOMATIC SPRINKLER SYSTEM HEIGHT (1 STORY) | N/A | | | | |
| TRAVEL COMMON PATH LIMIT (ALLOWABLE/ ACTUAL) | 300/ NONE | | | | |
| TRAVEL DEAD-END LIMIT (ALLOWABLE/ ACTUAL) | 300/ NONE | | | | |
| TRAVEL EXIT ACCESS TRAVEL DISTANCE LIMIT (ALLOWABLE/ ACTUAL) | 300/ ETR | | | | |
| FIRE SUPPRESSION SYSTEM | Yes, per NFPA 13 | | | | |
| NUMBER OF REQUIRED EXITS | TWO (AT TENANT SPACE) | | | | |
| EXIT ACCESS FIRE RATINGS | | | | | |
| FIRE WALLS/ BARRIERS | | | | | |
| OCCUPANCY SEPARATION | ETR | | | | |
| PARTY WALLS | ETR | | | | |
| STAR ENCLOSURES | 2HR | | | | |
| SHAFTS | ETR | | | | |
| EXIT ACCESS CORRIDORS | ETR | | | | |
| FIRE PROTECTION OF STRUCTURE | | | | | |
| PRIMARY STRUCTURAL FRAME | ETR | | | | |
| SECONDARY STRUCTURAL FRAME | ETR | | | | |
| LOAD BEARING WALLS - EXTERIOR | ETR | | | | |
| LOAD BEARING WALLS - INTERIOR | ETR | | | | |
| NON-LOAD BEARING WALLS - EXTERIOR | ETR | | | | |
| NON-LOAD BEARING WALLS - INTERIOR | ETR | | | | |
| FLOOR CONSTRUCTION | ETR | | | | |
| ROOF CONSTRUCTION | ETR | | | | |
| OCCUPANT LOAD | 0 | People | 0 | | |
| BUSINESS | 0 | SF | 00 | SF/ PERSON = | 0 |
| GENERAL NOTES | Area of work is at tenant entry point & a reconfiguration of doors, no addition of space. | | | | |

| NFPA 101 2009 & 220 2006 CODE DATA | | BUSINESS | | | |
|--|---|----------|----|--------------|---|
| USE GROUP CLASSIFICATION | 2010 (SEE NOTE #0) | People | 0 | | |
| TYPE OF CONSTRUCTION | EXISTING TO REMAIN | SF | 00 | SF/ PERSON = | 0 |
| EXISTING BUILDING AREA | EXISTING TO REMAIN | | | | |
| PROPOSED BUILDING AREA | EXISTING TO REMAIN | | | | |
| TOTAL AREA OF WORK | 208 sqft | | | | |
| BUILDING HEIGHT (STORES/ FEET) | 10 STORES | | | | |
| BUILDING AREA LIMITATION - SQ FT | EXISTING TO REMAIN | | | | |
| BUILDING HEIGHT LIMITATION - STORES | EXISTING TO REMAIN | | | | |
| TRAVEL COMMON PATH LIMIT (ALLOWABLE/ ACTUAL) | 300/ NONE | | | | |
| TRAVEL DEAD-END LIMIT (ALLOWABLE/ ACTUAL) | 300/ NONE | | | | |
| TRAVEL EXIT ACCESS TRAVEL DISTANCE LIMIT (ALLOWABLE/ ACTUAL) | 300/ N/A | | | | |
| FIRE SUPPRESSION SYSTEM | Yes, per NFPA 13 | | | | |
| NUMBER OF REQUIRED EXITS | TWO (AT TENANT SPACE) | | | | |
| EXIT ACCESS FIRE RATINGS | | | | | |
| FIRE WALLS/ BARRIERS | | | | | |
| OCCUPANCY SEPARATION | ETR | | | | |
| PARTY WALLS | ETR | | | | |
| STAR ENCLOSURES | 2HR | | | | |
| SHAFTS | ETR | | | | |
| EXIT ACCESS CORRIDORS | ETR | | | | |
| FIRE PROTECTION OF STRUCTURE | | | | | |
| COLUMNS | ETR | | | | |
| BEAMS, BRACES, TRUSSES & ARCHES | ETR | | | | |
| LOAD BEARING WALLS - EXTERIOR | ETR | | | | |
| LOAD BEARING WALLS - INTERIOR | ETR | | | | |
| NON-LOAD BEARING WALLS - EXTERIOR | ETR | | | | |
| NON-LOAD BEARING WALLS - INTERIOR | ETR | | | | |
| FLOOR CONSTRUCTION | ETR | | | | |
| ROOF CONSTRUCTION | ETR | | | | |
| OCCUPANT LOAD | 0 | People | 0 | | |
| BUSINESS | 0 | SF | 00 | SF/ PERSON = | 0 |
| GENERAL NOTES | Area of work is at tenant entry point & a reconfiguration of doors, no addition of space. | | | | |

* INSTALL ALL MATERIALS PER MANUFACTURE REQUIREMENTS



WALL LEGEND



DOOR NOTES:


- 1 NEW GLASS DOUBLE DOOR W/ MAG LOCK AND OCC SENSOR COORDINATE W/ FIRE ALARM SYSTEM TO 'FAIL SAFE'. INSTALL CARD READER AND TIE INTO TENANT SECURITY SYSTEM.

DEMOLITION NOTES:

- ALL DASHED WALLS AS SHOWN TO BE REMOVED. G.C. TO FIELD VERIFY & REPORT ANY DISCREPANCIES OR LOAD BEARING WALLS TO THE ARCHITECT.
- ELECTRIC POWER TO THE TENANT SPACE ONLY SHALL BE DISCONNECTED PRIOR TO DEMOLITION. VERIFY WATER SHUT-OFF W/ BUILDING OWNER. EXISTING DUCT WORK TO REMAIN SHALL BE SEALED. SPRINKLER SYSTEMS, WHERE APPLICABLE, SHALL REMAIN OPERATIONAL UNLESS PERMITTED BY THE CITY BUILDING INSPECTOR. FIRE ALARM SYSTEMS TO REMAIN FULLY OPERATIONAL DURING DEMOLITION.
- DUST BARRIER PARTITIONING SHALL BE INSTALLED @ TENANT SEPARATIONS AS REQUIRED.
- ALL DEMOLITION SHALL BE REMOVED FROM THE REAR OF THE BUILDING ONLY.
- REMOVE EXISTING CEILINGS IN THEIR ENTIRETY AS REQUIRED PER PLAN.
- ALL FIRE PROTECTION, GYPSUM DRYWALL &/ OR FIRESPRAY ON STRUCTURAL MEMBERS, INCLUDING BEARING WALLS, FIRE SEPARATION WALLS, BEAMS, COLUMNS & FIRE RATED FLOOR/ CEILING ASSEMBLIES SHALL NOT BE REMOVED.
- PROTECT ALL FINISHES, MATERIALS AND EQUIPMENT NOTED AS EXISTING TO REMAIN.
- DIMENSIONS INDICATED +/- ARE EXISTING CONDITION DIMENSIONS TO BE VERIFIED IN FIELD.
- REMOVE EXISTING PLUMBING FIXTURES IF ANY, VENTING AND ASSOCIATED EXHAUST FANS. CAP PLUMBING FLUSH WITH FLOOR.
- FIELD VERIFY ALL STRUCTURAL COMPONENTS PRIOR TO DEMOLITION. REPORT ANY DISCREPANCIES IMMEDIATELY TO ARCHITECT.

PROJECT NOTES


- THE CONSTRUCTION TYPE NOTED WITHIN IS LIMITED TO THE SCOPE OF WORK FOR THE PROJECT AS SHOWN AND OUTLINED IN THE CONSTRUCTION DOCUMENTS. CONSTRUCTION TYPE AND USE BEYOND THIS SCOPE OF WORK SHALL BE OUTSIDE THE RESPONSIBILITY OF THE ARCHITECT.
- SCOPE OF WORK: THE PROJECT INCLUDES THE TENANT FIT-UP OF INTERIOR WALLS FOR "STONE COAST FUND SERVICES" (NO CHANGE OF USE).
- THE TENANT SPACE SHALL BE CONSTRUCTED TO CONFORM WITH ALL APPLICABLE CODES INCLUDING, BUT NOT LIMITED TO, THE LATEST EDITIONS OF IBC, NFPA 101, ANSL UFAS, HUD/AG, ADA/AG, MFS.
- THE CONTRACTOR SHALL WORK FROM GIVEN DIMENSIONS AND LARGE SCALE DETAILS ONLY. DO NOT SCALE THE DRAWINGS.
- INSTALL BLOCKING FOR SURFACE APPLIED FIXTURES, TRIM, WHEN MOUNTED ON STUD WALLS, INCLUDING ALL FUTURE INSTALLATIONS.
- INSTALL U.L. FIRE-STOPPING SEALANT/SYSTEM EQUAL TO THE FIRE RATED FLOOR, CEILING AND WALL ASSEMBLY.
- ALL INTERIOR FINISHES SHALL MEET: WALLS & CEILINGS: CLASS A OR B FLOOR FINISHES: NOT LESS THAN CLASS II.
- FURNITURE, FIXTURES AND EQUIPMENT: SHALL BE FLAME RESISTANT AND MEET NFPA 701, STANDARD METHODS OF FIRE TESTS FOR FLAME PROPAGATION OF TEXTILES AND FILMS.
- ELECTRICAL: ALL NEW WORK SHALL MEET THE NEC AND NFPA 70.
- LIFE SAFETY INTEGRATION W/ THE EXISTING SHALL MEET NFPA 72 & CITY OF PORTLAND FIRE DEPARTMENT. SYSTEM SHALL BE DESIGNED AND INSTALLED BY A CITY/ STATE APPROVED DESIGNER & CONTRACTOR.
- SPRINKLER SYSTEM SHALL MEET NFPA 13 - NEW HEADS PER PLAN.
- ALL EXISTING EGRESS COMPONENTS SHALL REMAIN AS SHOWN ON DRAWINGS.
- HVAC - VERIFY EXISTING HVAC SYSTEM & DUCT WORK WITH PROPOSED PLAN.



MARK MUELLER ARCHITECTS
A.I.A.
100 Commercial Street
Suite 205
Portland, Maine 04101
Phone: 207.774.9057
Email: rfi@muellerarchitects.com

© COPYRIGHT 2015
MARK MUELLER ARCHITECTS


STONE COAST FOUND SERVICES
ONE CANAL PLAZA
PORTLAND, MAINE



- NEW PAINT THROUGHOUT SPACE IN IT'S ENTIRETY
- REMOVE EXISTING WALLS & DOORS AS SHOWN (DASHED)
- NEW WALL AND DOUBLE DOOR
- NEW CARPET THROUGHOUT SPACE IN IT'S ENTIRETY

6TH FLOOR PLAN
SCALE: 3/16"=1'-0"

PERMIT SET : OCTOBER 20, 2015



| REVISIONS | DATE |
|-----------|----------------------------|
| | 10/16/15 |
| PROJECT | STONE COAST FOUND SERVICES |
| DRAWN BY | M.M./T.D. |
| CHECK BY | M.M. |

A-1.1