

Sidewalk Closed Signs at corner of Middle and Union Streets

Schedule = February 11, 2013 to May 9, 2014

GENERAL NOTES

- 1 - Contractor parking will occur off site - on street occupancy permits will not be requested from the City
- 2 - To the greatest extent possible, deliveries will be staged to avoid queuing outside the construction fence. The contractor will provide a staging area outside of the Old Port area for delivery trucks to stage before heading to the site.
- 3 - Snow removal along the construction fence within the public right of way in Union and Fore Streets will be by the Consigli.
- 4a - Maintain 24 feet from curb line on south side of Fore Street to construction fence for one way traffic / fire department access (17 feet) plus parking spaces (7 feet).
- 4b - Please note there will be a 3 week period in late July / mid August 2013 where parking spaces need to be taken out of service on Fore Street for exterior wall panel erection. Fire department access (17 feet) will be maintained during this work. Consigli will provide one (1) month advance notice to the City on specific dates for this work.
- 5a - A minimum 20 feet width along Union Street for Fire Department access will be maintained.
- 5b - Construction fence along Union Street will be placed on the center line of the street approximately 22 feet from the curb line.
- 6 - Knox padlocks for gates within construction fence will be ordered by Consigli at Central Fire Station.
- 7 - It is anticipated that all utility connection work within Union and Fore Streets will occur between April 15th and July 31st. Each utility (water, sewer, gas, electric, communications) will be permitted for street openings, coordinated and scheduled with the City. Night and weekend work to minimize disruptions at intersections is anticipated.
- 8 - Types, locations and quantities of traffic signage will be reviewed and mutually agreed upon between the City and Consigli, including detour signage on adjacent streets.

TWO WAY TRAFFIC (TWO LANES ONLY - 24 feet wide total) AT UNION STREET INTERSECTION

Approximately 130 feet fence

Material Hoist

Jersey Barriers w/ Fence & Scrim

Temporary pavement markings to route traffic at intersection to be determined with City of Portland

Parking spaces on this side of Fore Street will remain in service, except as indicated in General Note 4b

Approximately 180 feet fence

Canal Plaza Hotel Construction Management Plan

January 24, 2013

One (1) Parking space on this side of street will be out of service for the temporary pedestrian crosswalk

- SIGNAGE KEY PLAN**
- A- NO Right Turn Sign
 - B- NO Left Turn Sign
 - C- One Way - Do Not Enter Sign
 - D- Sidewalk Closed Sign

ADA Accessible Temporary Pedestrian Crosswalk

One Way - Do Not Enter Signs at Parking Garage Entry and Dana Street Intersection

