Reviewed for Code Compliance
Inspections Division
Portland, Maria Pinkham

Date: 06/19/17

MARK		QT	ITEM	BTUper unit	TOTAL BTU
1	N	3	FRYER	110,000	330,000
2	N	1	GRIDDLE		68,000
3	N	1	OVEN		268,000
	E	1	(E) A/C UNITS CARRIER 59SP5A100E21-20		97,000
	N	2	NORITZ NC380 TANKLESS WATER HEATER	380,000	760,000
			TOTAL BTU		1,523,000

1. TOTAL CONNECTED LOAD :1,523,000 / 1100 = 1,385 CFH
2. DISTANCE FROM MOST REMOTE OUTLET TO GAS METER :XX FT

2

1 GAS PIPE SIZING
1/4" = 1'-0"

2 GAS LINE DIAGRAM
1/4" = 1'-0"

3 GAS LINE RISER
1/4" = 1'-0"

REVISION	
Revision 2	4-10-2017

Tenant Improvement
Old Port Lobster Shack

425 FORE STREET
PORTLAND ME

PROJECT NUMBER	150101
DRAWN	Author
CHECKED	Checker
DATE	
SCALE	

GAS LINE

P-3.0