



LIGHTING PLAN
1/4"=1'-0"

CODED NOTES

- ① 20 AMP DEDICATED CIRCUIT WITH ISOLATED GROUND FOR STOREFRONT SIGN. FIELD COORDINATE EXACT LOCATION AND REQUIREMENTS.
- ② 4-BOX FOR HOOD LIGHTS. HOOD LIGHT FIXTURES BY HOOD SUPPLIER. WIRED BY THE ELECTRICAL CONTRACTOR. ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL 100W A-19 LIGHT BULBS IN FIXTURES AS REQUIRED.
- ③ OCCUPANCY SENSOR SWITCH WITH TUNED OUT OFF. HUBBELL #MS202E
- ④ DINING AREA SWITCH LOCATION. LETTER DESIGNATES CIRCUIT TO BE SWITCHED. SWITCH "C" SHALL BE A LUTRON #MT-800 DIMMER SWITCH OR EQUAL. VERIFY SWITCH LOCATIONS WITH OWNER PRIOR TO ROUGH-IN.
- ⑤ EX-2 AND EX-3 ARE CEILING MOUNTED EXHAUST FANS BY THE MECHANICAL CONTRACTOR. FANS TO BE CONTROLLED BY THE LIGHT SWITCH IN EACH LAV. COORDINATE WITH MECHANICAL CONTRACTOR.

LIGHTING SCHEDULE

| TYPE | SYMBOL | DESCRIPTION | MOUNTING | MANUFACTURER/MODEL | LAMP(S) | WATTS EACH | NOTES |
|------|--------|--|---|---|------------------------------------|------------|--|
| A | | RECESSED 2'x4' TROFFER | RECESSED IN CEILING | INDUSTRIAL LIGHTING GROUP LIG-R24 1-LWV-428-1 20 | (4) 172W 18/SP41 /LWV/ED0 LAMPS | 88 W | LENS (SMOOTH SIDE DOWN) |
| B | | RECESSED 2'x2' TROFFER | RECESSED IN CEILING | INDUSTRIAL LIGHTING GROUP LIG-R22-LWV-23206-120 | (2) 172W 18/SP41 /LWV LAMPS | 48 W | LENS (SMOOTH SIDE DOWN) |
| R | | DECORATIVE PENDANT WITH RED FINISH (PAINTED RED INSIDE & OUT) | INSTALL @ 8'-6" AFF. (ADJUST FOR EXISTING CONDITIONS) | INDUSTRIAL LIGHTING GROUP LIG-R8518-21BLE | (1) P45 13-LIG - 97040 LAMPS | 13 W | INSTALL @ 8'-6" AFF. (ADJUST FOR EXISTING CONDITIONS) - DO NOT PAINT WIRING. |
| W | | DECORATIVE PENDANT WITH WHITE FINISH (PAINTED WHITE INSIDE & OUT) | INSTALL @ 8'-6" AFF. (ADJUST FOR EXISTING CONDITIONS) | INDUSTRIAL LIGHTING GROUP LIG-R8518-21BLE | (1) P45 13-LIG - 97040 LAMPS | 13 W | INSTALL @ 8'-6" AFF. (ADJUST FOR EXISTING CONDITIONS) - DO NOT PAINT WIRING. |
| EM | | TWIN HEAD EMERGENCY BATTERY UNIT WITH WHITE POLYCARBONATE HOUSING AND INTERNAL BATTERY BACK-UP | WALL MOUNTED | LIGHTING BY DESIGN LIG-ED-2-W | INCLUDED | | LAMP INCLUDED WITH FIXTURE. |
| EX | | LED EXIT SIGN WITH WHITE THROU-PLASTIC HOUSING, INTERNAL BATTERY BACK-UP AND REMOTE HEAD CAPABILITIES. | WALL ABOVE EXITS | LIGHTING BY DESIGN LIG-TP-U-R-W-EM | INCLUDED | | LAMP INCLUDED WITH FIXTURE. COORDINATE COLOR WITH AUTHORITY HAVING JURISDICTION. |
| REM | | MENU BOARD TRACK LIGHTING (LED) | EXTERIOR WALL | LIGHTING BY DESIGN LIG-WM-SR | INCLUDED | | |
| | | SEQUOL LIGHTING (LED) | WALL MOUNTED | LIGHTING BY DESIGN LIG-TP-U-R-W-EM | INCLUDED | | |

NOTE: CIRCUIT ALL EXIT SIGNS, EMERGENCY LIGHTS AND NIGHT LIGHTS (NL) AHEAD OF ANY LOCAL SWITCHING.

NOTE: EXIT LIGHTING SHALL PROVIDE ADEQUATE DIRECTION AND LOCATION OF EXITS AND MEANS OF EGRESS TO ALL EXITS. EMERGENCY LIGHTING SHALL BE PROVIDED FOR ALL MEANS OF EGRESS, AND OVER THE EXTERIOR OF ALL EXIT DOORS, GIVING ADEQUATE COVERAGE AND CORRECT ILLUMINATION OF THE MEANS OF EGRESS AND MEANS OF EXIT ACCESS. NOT ALL LIGHT FIXTURES SHOWN IN SCHEDULE ARE USED.

NOTE: ALL FIXTURES IN KITCHEN, DISH WASH AREA AND FOOD SERVICE AREA TO BE LENSED OR HAVE SHATTER PROOF LAMPS. LAMPS TO BE SHATTER PROOFED WITH THE FOLLOWING: NOBMAN LAMPS, INC. (800-992-8020)

NOTE: RESTROOMS TO HAVE OCCUPANCY OR VACANCY SENSOR

NOTE: RESTROOMS TO HAVE OCCUPANCY OR VACANCY SENSOR

REVISIONS:

| # | DATE: | DESCRIPTION: |
|---|------------|---|
| 1 | 12/15/10 | ISSUED FOR PERMIT |
| 1 | 01/12/11 | REVISED PER LL MUNICIPAL 4 CORP. COMMENTS |
| 1 | 02/08/2011 | ISSUED FOR CONSTRUCTION |

FIVE GUYS
BURGERS and FRIES

425 FORE STREET
PORTLAND, MAINE 04101-4396

PROJECT NUMBER: 10232
DRAWN BY: CM
CHECKED BY: CM

APPLIED ENGINEERING GROUP LTD.
MEP Building Consultants

7402 East Broad Street
Blacklick, Ohio 43004
Phone: 614.322.7050
Fax: 614.322.7049
www.aegtltd.com

APPLIED ENGINEERING GROUP LTD.
MEP Building Consultants

LINGLE DESIGN GROUP, INC.

158 WEST MAIN STREET
LENA, IL 61048

PHONE: 815-369-9155
FAX: 815-369-4495
WWW.LINGLEDESIGN.COM

LINGLEDESIGNGROUP, INC.

SHEET NUMBER:
E2

SHEET TITLE:
LIGHTING PLAN