



LIGHTING PLAN  
1/4"=1'-0"

**CODED NOTES**

- 1 20 AMP DEDICATED CIRCUIT WITH ISOLATED GROUND FOR STOREFRONT SIGN. FIELD COORDINATE EXACT LOCATION AND REQUIREMENTS.
- 2 4-BOX FOR HOOD LIGHTS. HOOD LIGHT FIXTURES BY HOOD SUPPLIER. WIRED BY THE ELECTRICAL CONTRACTOR. ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL 100W A-19 LIGHT BULBS IN FIXTURES AS REQUIRED.
- 3 OCCUPANCY SENSOR SWITCH WITH TILED OUT OFF. HUBBELL #MS202E
- 4 DINING AREA SWITCH LOCATION. LETTER DESIGNATES CIRCUIT TO BE SWITCHED. SWITCH "C" SHALL BE A LUTRON #MT-800 DIMMER SWITCH OR EQUAL. VERIFY SWITCH LOCATIONS WITH OWNER PRIOR TO ROUGH-IN.
- 5 E-2 AND E-3 ARE CEILING MOUNTED EXHAUST FANS BY THE MECHANICAL CONTRACTOR. FANS TO BE CONTROLLED BY THE LIGHT SWITCH IN EACH LAV. COORDINATE WITH MECHANICAL CONTRACTOR.

**LIGHTING SCHEDULE**

TYPE	SYMBOL	DESCRIPTION	MOUNTING	MANUFACTURER/MODEL	LAMP(S)	WATTS EACH	NOTES
A	[Symbol]	RECESSED 2'x4' TROFFER	RECESSED IN CEILING	INDUSTRIAL LIGHTING GROUP LIG-824 1-LWV-428-1 20	(4) T20W 18/SP41 /LAMP/ECO LAMPS	88 W	LENS (SMOOTH SIDE DOWN)
B	[Symbol]	RECESSED 2'x2' TROFFER	RECESSED IN CEILING	INDUSTRIAL LIGHTING GROUP LIG-822-LUM-23206-120	(2) T20W 18/SP41 /LAMP	48 W	LENS (SMOOTH SIDE DOWN)
R	[Symbol]	DECORATIVE PENDANT WITH RED FINISH (PAINTED RED INSIDE & OUT)	INSTALL @ 8'-6" AFF. (ADJUST FOR EXISTING CONDITIONS)	INDUSTRIAL LIGHTING GROUP LIG-85318-21BLE	(1) P43 13-LG - 97040 LAMPS	13 W	INSTALL @ 8'-6" AFF. (ADJUST FOR EXISTING CONDITIONS) - 00
W	[Symbol]	DECORATIVE PENDANT WITH WHITE FINISH (PAINTED WHITE INSIDE & OUT)	INSTALL @ 8'-6" AFF. (ADJUST FOR EXISTING CONDITIONS)	INDUSTRIAL LIGHTING GROUP LIG-85318-21BLE	(1) P43 13-LG - 97040 LAMPS	13 W	INSTALL @ 8'-6" AFF. (ADJUST FOR EXISTING CONDITIONS) - 00
EM	[Symbol]	LED EXIT SIGN WITH WHITE THROUGH-PLASTIC HOUSING, INTERNAL BATTERY BACK-UP AND REMOTE HEAD CAPABILITIES.	WALL MOUNTED	LIGHTING BY DESIGN LIG-EP-U-R-W-EM	INCLUDED		LAMP INCLUDED WITH FIXTURE. COORDINATE COLOR WITH AUTHORITY HAVING JURISDICTION.
EX	[Symbol]	LED EXIT SIGN WITH WHITE THROUGH-PLASTIC HOUSING, INTERNAL BATTERY BACK-UP AND REMOTE HEAD CAPABILITIES.	WALL MOUNTED	LIGHTING BY DESIGN LIG-EP-U-R-W-EM	INCLUDED		LAMP INCLUDED WITH FIXTURE. COORDINATE COLOR WITH AUTHORITY HAVING JURISDICTION.
REM	[Symbol]	MENU BOARD TRACK LIGHTING (LED)	WALL MOUNTED	SEAGULL LIGHTING LIT-LP34M-WHITE (4' TRACK) LIT-LT837W-WHITE (END CONNECTOR)	INCLUDED		(QTY. 4 HEADS)

NOTE: CIRCUIT ALL EXIT SIGNS, EMERGENCY LIGHTS AND NIGHT LIGHTS (NL) AHEAD OF ANY LOCAL SWITCHING. EXIT LIGHTING SHALL PROVIDE ADEQUATE DIRECTION AND LOCATION OF EXITS AND MEANS OF EGRESS TO ALL EXITS. EMERGENCY LIGHTING SHALL BE PROVIDED FOR ALL MEANS OF EGRESS, AND OVER THE EXTERIOR OF ALL EXIT DOORS, GIVING ADEQUATE COVERAGE AND CORRECT ILLUMINATION OF THE MEANS OF EGRESS AND MEANS OF EXIT ACCESS. NOT ALL LIGHT FIXTURES SHOWN IN SCHEDULE ARE USED.

NOTE: ALL FIXTURES IN KITCHEN, DISH WASH AREA AND FOOD SERVICE AREA TO BE LENSED OR HAVE SHATTER PROOF LAMPS. LAMPS TO BE SHATTER PROOFED WITH THE FOLLOWING: NORBAM LAMPS, INC. (800-992-8020)

NOTE: RESTROOMS TO HAVE OCCUPANCY OR VACANCY SENSOR

LINGLEDESIGNGROUP, INC  
158 WEST MAIN STREET  
LENA, IL 61048  
PHONE: 815-369-9155  
FAX: 815-369-4495  
WWW.LINGLEDESIGN.COM

APPLIED ENGINEERING GROUP LTD.  
7402 East Broad Street  
Blacklick, Ohio 43004  
Phone: 614.322.7050  
Fax: 614.322.7049  
www.aegtld.com  
MEP Building Consultants

**FIVE GUYS**  
BURGERS and FRIES  
425 FORE STREET  
PORTLAND, MAINE 04101-4396

REVISIONS:

#	DATE:	DESCRIPTION:
1	12/15/10	ISSUED FOR PERMIT

SHEET TITLE:  
**LIGHTING PLAN**

PROJECT NUMBER:  
10232

DRAWN BY:  
CM

CHECKED BY:  
CM

SHEET NUMBER:  
**E2**