




- 1 Set(s) of Reverse Back Lit Remote reading MAINE LOBSTER SHACK with LED lighting
- 9" Block Letters
- Faces: Aluminum - .090 Mill Finish
- 3 in return Aluminum - .063 Mill Finish
- Paint: Exterior - MAP Satin White, Interior - MAP White High Reflective VOC
- Polycarbonate Backs: Polycarbonate - Clear .150 x 76 x 120
- LEDs: 1 Row of LED- Principal Fusion 2 PL-FS2-TW170-P - 2 mod/ft
- Power Supply: LED Power Supply-Principal PL-60-12-U 120-277VAC
- Outdoor UL Listed lit letters

These letters will be mounted to a blue 203.25"x25" panel that will house the wiring. Sign installed ready for electrical connection to supplied power source.

203.25 in
173.5 in




 <p>PortsmouthSign.com 603-436-0047</p>	<p>REVISION: All orders under \$250 include 1 revision only. All orders over \$250 include 3 revisions only. Additional revisions will be charged at \$25 per revision.</p> <p>PLEASE NOTE: Designs are NOT actual size and color may vary depending on printer and/or monitor.</p>	<p>01/12/18</p> <p>RETURN SIGNED TO: service@portsmouthsign.com</p> <p>I understand this Order Form is the final production order and replaces all previous drawings, notes and verbal instructions to this job. Standard vinyl & paint colors will be used. Custom colors and specific matches to PMS colors will be an additional fee. I have carefully reviewed this form and verify that it contains all necessary specifications and represents my order. I authorize fabrication according to this approval.</p> <p>SIGNATURE: _____ Date: _____</p>
---	---	--

Member of:



©COPYRIGHT 2017, BY PORTSMOUTH SIGN COMPANY. All designs and custom artwork remain the property of Portsmouth Sign Company until the order is complete and paid in full.

Shop Use Only	Qty: SS <input type="checkbox"/> DS <input type="checkbox"/>	Materials:	Background Color:	Vinyl Color: HP <input type="checkbox"/> Int <input type="checkbox"/>	Other: 
---------------	--	------------	-------------------	---	--