

FIXTURE ANNOTATION KEY		
MOUNTING CONDITIONS	MOUNTING PLANE	Project Specific Fixture Annotations
P PENDANT	B BUILT-IN	PF FLOOR LAMP
R RECESSED	C CEILING	PT TABLE LAMP
S SURFACE	G GROUND WALL	UW UNDERWATER

- NOTES:**
- 1) RED FIXTURE INDICATES A FIX
 - 2) BLUE FIXTURE INDICATES A FIXTURE IS MOUNTED BELOW 7'
 - 3) REFER TO ARCHITECTS SECTIONS FOR ALL MOUNTING HEIGHTS PER FLOOR
 - 4) REFER TO FIXTURE SPECIFICATIONS FOR DETAILED INFORMATION ON EACH FIXTURE
 - 5) #W PER R/FT = (NOMINAL WATTS CONSUMED PER RUNNING FOOT)

FIXTURE SYMBOL	FIXTURE ITEM #	FIXTURE CODE	FIXTURE DESCRIPTION	FIXTURE LOCATION	Architectural Fixture	Decorative Fixture G.C. Installed	Decorative Fixture
	P-604-01	PC1	Partially Dimmable - Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Above Host Stand		■	
	P-604-02	PC2	Dimmable - Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Gallery		■	
	P-604-03	PC3	Dimmable - Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Lounge 1 / Sun Room		■	
	P-604-04	PC4	Dimmable - Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Guest Kitchen Community Table		■	
	P-604-05	PC5	Dimmable - Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Bar/Café Community Table		■	
	P-604-06	PC5A	Dimmable - Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Bar/Café Pendant		■	
	P-604-07	PC6	Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Elevator Lobby 1st floor		■	
	P-604-09	PC7	Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Elevator Lobby - Typical Floors		■	
	G-604-03	PC8	Pendant Ceiling Mounted Decorative Fixture, refer to Interior Design Specification sheets for additional information.	Decorative Fixture in Suites (Room Type KE and KG only)		■	
	P-603-01	PF1	Decorative Floor Lamp, refer to Interior Design Specification sheets for additional information.	Lobby @ Lounge 2			■
	P-602-02	PT1	Table Lamp, refer to Interior Design Specification sheets for additional information.	Gallery			■
	P-602-01	PT2	Table Lamp, refer to Interior Design Specification sheets for additional information.	Lobby @ E-Room			■
		RB1	Fixture Recessed in Feature Wall - (Reference Millwork Drawings) (1) Lamp 28W T5 Lineal Fluorescent - Non Dimmable	Gallery @ Focal Wall	■		
		RB2	Recessed Built-In Linear 28W T5 Fluorescent Undercabinet Light - Non Dimmable	Kitchen Dining - Under cabinet	■		
		RB3	Recessed Built-Into Shelving Linear "Warm White" LED Strip or Rope Light (Allow 2.4 W per R/FT) - Low Voltage - Dimmable	Kitchen Dining - On top of cabinets	■		
		RB4	Recessed Built-Into Shelving 1-Lamp 28W T5 Linear Fluorescent Fixture with Frosted Lens Cover (by others) - Line Voltage - Non Dimmable	Lobby @ Host	■		
	G-702-02	RB6	Recessed Built-Into Mirror, refer to Interior Design Specification sheets for additional information.	Mirror at Vanity - Room type KC, KD, KE, KF, and QC		■	
	G-702-03	RB7	Back Lit - Polished Edge Mirror, refer to Interior Design Specification sheets for additional information.	Mirror at Vanity - Room type KA, KB, KG, QA, and QB		■	
		RC1	Dimmable - Recessed Ceiling 4" Dia. 50W MR16 Downlight	Bar/Café, Kitchen/Dining, Vestibule, Elevator Lobby - 1st Floor, Meeting Rms., Meeting Rm. Corridor, Vending	■		
		RC2	Recessed Ceiling 4" Aperture 50W MR16 Adjustable Accent Lights with 25° Distribution - Non Dimmable.	Guest Room Entry in Rms. KE, KG	■		

FIXTURE SYMBOL	FIXTURE ITEM #	FIXTURE CODE	FIXTURE DESCRIPTION	FIXTURE LOCATION	Architectural Fixture	Decorative Fixture G.C. Installed	Decorative Fixture
		RC2A	Dimmable - Recessed Ceiling 4" Aperture 50W MR16 Adjustable Accent Lights with 25° Distribution.	Lobby @ E-Room, Bird on a Wire, Sunroom & Meeting Room.	■		
		RC3	Recessed Ceiling 6" Horizontal. (1) lamp 26W CFL Downlight - Non Dimmable.	Guest Rooms Recessed in Bath Ceiling, Meeting Rm Corridor, Indoor Pool .	■		
		RC3A	Recessed Ceiling 6" Dia. Horizontal (1) Lamp 26W CFL Single Kicker Wallwasher - Non Dimmable.	Lobby Near E-Room, Elevator Lobby - Flrs. 2-6, Meeting Rm. Corridor	■		
		RC3B	Dimmable - Recessed Ceiling 6" Horizontal. (1) lamp 26W CFL Downlight.	Bird on a Wire, Bar/Café, Lounge 1 & 2, BOH Corridor, Vestibule, Meeting Rooms.	■		
		RC3C	Dimmable - Recessed Ceiling 6" Dia. Horizontal (1) Lamp 26W CFL Single Kicker Wallwasher.	Lobby Near E-Room, Bird on a Wire, Meeting Rooms.	■		
		RC5	Recessed Ceiling 2x2' - (2) lamp 14W T-5 Linear Florescent Fixture with Inverted Lens - Non Dimmable.	Kitchen	■		
		RC6	Recessed Ceiling 2x4' - (2) lamp 28W T-5 Fluorescent Fixture - Non Dimmable.	Computer Room, BOH, Meeting Room Storage, GM Office, Kitchen	■		
		RC6A	Recessed Ceiling 2x4' - (2) lamp 28W T-5 Fluorescent Fixture w/ Inverted Lens - Non Dimmable	Kitchen	■		
	P-604-08	RC7	Ceiling Pendant, refer to Interior Design Specification sheets for additional information.	Corridor		■	
		RC8	Recessed Ceiling 6" Dia. Horizontal (1) lamp 26W CFL Lensed Shower Downlight. Non Dimming.	Guest Bathroom Over Shower (Room Type KC, KE, KG, and QC).	■		
		RC10	Recessed Ceiling 4" Dia Vertical (1) lamp LED Downlight - Non Dimmable.	Public Restrooms	■		
		RC11	LED Mini Downlight with Electronic Transformer - Dimmable	Bar / Café	■		
		RC12	Recessed Ceiling 2'X4' (2) lamp 28W T5 Fluorescent Fixture - Non Dimmable.	Meeting Room	■		
		RC13	Recessed Ceiling 2'X2' (2) lamp 14W T5 Fluorescent Fixture - Non Dimmable.	Fitness Center	■		
		RC14	ADD - Recessed Ceiling 6" 90W PAR38 Downlight - Dimmable - For high (17') ceiling in lobby.	Lobby / 17' Ceiling	■		
		UW1	No Spec. Fixture is Provided by Pool Contractor (per local jurisdiction requirements) Under Water 6" Dia. 18W "Cool White" LED Lights - Non Dimmable	Pool Lights - Provided by Pool Contractor	■		
		SC1	4' Industrial (2) lamp 28W T5 Linear Fluorescent Fixture with chain hanging assembly - Non Dimmable.	BOH - Electrical, Mechanical, Telephone, Equipment, Maintenance, Guestroom Flrs. Storage and Housekeeping	■		
	P-605-01	SW1	Surface wall mounted fixture, refer to Interior Design Specification sheets for additional information.	Public Restroom Vanity Lights		■	
	P-601-01	SW2	Dimmable - Surface wall mount fixture, refer to Interior Design Specification sheets for additional information.	Sunroom Wall Sconce		■	
	P-601-02	SW3	Dimmable - Surface wall mounted fixture, refer to Interior Design Specification sheets for additional information.	Meeting Room Wall Sconce		■	