



Flow Summary:

Coverage	Dim.	Nozzle	Flows	Notes
Hood: Single Bank	184 x 54	1N x2	2	2-4 in. from filter face, center of height dimension, aimed down filter length.
Duct: Square	14 x 10	1100	1	2-8 in. into center of duct opening, aimed up
Duct: Square	14 x 10	1100	1	2-8 in. into center of duct opening, aimed up
Fryer: 1 vat, dripboard	16 x 26	3N	3	25"-35", FRONT HALF of perimeter, aimed at center
Range: 2 burners	12 x 26	1F	1	40"-48", front edge of burner, nozzle flats parallel with burner front-to-rear cente ... See Note 1
Griddle	36 x 26	1N	1	35"-40", 0-2 in. inside perimeter, aimed at center
Pizza Oven	36 x 36	1N x2	2	Opposite ends (either corner) of the enclosed cooking chamber, 1 to 3 inches above s ... See Note 2
Total Flow Points			11	